

PROFFERS

RZ 2003-PR-043 VAN METRE LAND LIMITED PARTNERSHIP

July 7, 2004

Pursuant to Sect. 15.2-2303A of the 1950 Code of Virginia, as amended, the undersigned applicant and owners, for themselves and their successors or assigns (hereinafter referred to as "Applicant"), hereby proffer the following conditions provided the Subject Property is rezoned as proffered herein.

- 1. Conceptual/Final Development Plan.** Development of the property shall be in substantial conformance with the plan entitled "Conceptual Development Plan/Final Development Plan Woodford Place" ("CDP/FDP"), consisting of eight (8) sheets prepared by Land Design Consultants, Inc., revised as of May 28, 2004. The CDP portion of the CDP/FDP shall constitute the entire plan relative to the points of access, the total number of units, type of units and general location of common open space areas and general location and orientation of streets. However, the unit constructed on Lot 5 shall be constructed as a Unit A building instead of a Unit B building (see Typical Lot diagram on Sheet 2 of 8 of the CDP/FDP). The Applicant shall have the option to request Final Development Plan Amendments ("FDPAs") from the Planning Commission for portions of the plan in accordance with the provisions set forth in Sect. 16-402 of the Zoning Ordinance.
- 2. Minor Modifications.** Pursuant to Paragraph 4 of Sect. 16-403 of the Zoning Ordinance, minor modifications to the FDP may be permitted where it is determined by the Zoning Administrator that such are in substantial conformance with the approved FDP. The Applicant shall have the right to make minor adjustments to the building footprints and driveways, and parking configurations, provided such changes are in substantial conformance with the FDP and do not increase the number of units or decrease the amount of open space, peripheral setbacks, access or parking spaces, without requiring approval of an amended FDP.
- 3. Side Yard Setbacks.** All dwellings shall have minimum side yards of five (5) feet. However, the minimum distance between two dwellings with contiguous side yards shall be no less than fourteen (14) feet (less and except bump-outs where bay windows or fireplaces are installed), provided further, however, that the minimum distance between the dwellings on Lots 6 and 7 and the minimum distance between the dwellings on Lots 8 and 7 shall be twenty-two (22) feet.
- 4. Lot 32.** The proposed house on Lot 32 shall not be constructed until such time as the temporary turnaround easement is no longer needed, as determined by the Virginia Department of Transportation ("VDOT").

5. **Lot 33.** The single family detached dwelling on Lot 33 may be expanded, modified or reconstructed within the building envelope shown on the CDP/FDP without a Proffered Condition Amendment.
6. **Energy Efficiency.** All homes constructed on the property shall meet the thermal standards of the Cabo Model Energy Program for energy efficient homes, or its equivalent, as determined by the Department of Public Works and Environmental Services ("DPWES") for either electric or gas energy homes, as applicable.
7. **Architectural Design.** The design and architecture of the approved units shall be in substantial conformance with the illustrative elevations attached as Sheet 1 of the CDP/FDP, or of comparable quality as determined by DPWES. The exterior facades of the new homes constructed on the site shall be covered with brick, stone or cementitious siding (e.g., HardiPlank by James Hardie Building Products), or a combination thereof. Each front facade shall have a minimum of sixty percent (60%) brick or stone veneer covering. In addition, the side exterior facade of the unit on Lot 21 facing Woodford Road shall consist of the same building materials and shall have a consistent pattern of architectural detailing and percentage of building materials as the front facade on this unit. The roof slopes of the units from front to rear shall not exceed an 8:12 pitch. All units shall be limited to thirty-five (35) feet in height. No walk-out basements will be provided. Notwithstanding the note on Sheet 2 of the CDP/FDP referencing Sect. 2-412(2) of the Zoning Ordinance, any deck constructed within a required rear yard shall be limited to a maximum height of four (4) feet above finished ground level and no closer than twelve (12) feet from the rear property line. Notice of this restriction shall be enclosed in the Homeowners' Association documents. The Applicant will also provide prospective purchasers with written information as to the size and height of decks that are permitted on each lot. Units installed on Lots 5 through 8 shall be limited to the size of the building footprints shown on the CDP/FDP.
8. **Private Street.** The on-site private street shall be constructed in conformance with the Public Facilities Manual ("PFM") and shall be constructed of materials and depth of pavement consistent with Sect. 7-0502 of the PFM, subject to any design modifications approved by the Director of DPWES. The Homeowners' Association shall be responsible for the maintenance of the on-site private street. All prospective purchasers shall be advised of this maintenance obligation prior to entering into a contract of sale and said obligation will be disclosed in the Homeowners' Association documents.
9. **Tree Preservation.**
 - a. **Tree Preservation.** The Applicant shall submit a tree preservation plan as part of the first and all subsequent subdivision plan submissions. The preservation plan shall be prepared by a professional with experience in the preparation of tree preservation plans, such as a certified arborist or landscape architect, and reviewed and approved by the Urban Forestry Division. The tree preservation plan shall consist of a tree survey that includes the location, species, size, crown spread and condition rating percentage of all trees twelve (12) inches or greater in

diameter, ten (10) feet to either side of the proposed limits of clearing and grading as shown on the approved CDP/FDP. The tree survey shall also include areas of clearing and grading not shown on the CDP/FDP resulting from engineering requirements, such as off-site clearing and grading for utilities or stormwater outfall. The condition analysis shall be prepared using methods outlined in the latest edition of the *Guide for Plant Appraisal*. Specific tree preservation activities designed to maximize the survivability of trees designated for preservation shall be provided. Activities may include, but are not limited to, crown pruning, root pruning, mulching and fertilization.

- b. **Tree Transplantation.** To implement the transplantation referenced on Sheet 2 of the CDP/FDP, the Applicant shall provide a transplantation plan as part of the first and all subsequent submissions of the subdivision plan. The plan shall be prepared by a professional with experience in the preparation of tree transplanting plans, such as a certified arborist or landscape architect. Depending upon site constraints, the plan shall address one or all of the following items: (i) the species and sizes to be transplanted; (ii) the existing locations of the trees; (iii) the proposed final locations of the trees; (iv) the proposed time of year when the trees will be moved; (v) the transplant methods to be used, including tree spade size, if applicable; and (vi) details regarding after-transplant care, including mulching and watering, and, if necessary, support measures such as cabling, guying or staking.
- c. **Tree Preservation Walk-Through.** The Applicant shall have the limits of clearing and grading marked with a continuous line of flagging prior to the pre-construction meeting. Before or during the pre-construction meeting, the Applicant shall walk the limits of clearing and grading with an Urban Forestry Division representative and the developer's certified arborist to determine where minor adjustments to the clearing limits can be made to increase the survivability of trees at the edge of the limits of clearing and grading. Trees that are not likely to survive construction due to their species and/or their proximity to disturbance will also be identified at this time and the Applicant shall be given the option of removing them as part of the clearing operation. Any tree that is designated for removal, at the edge of the limits of clearing and grading or within a tree preservation area, shall be removed using a chain saw to avoid damage to surrounding trees. If a stump must be removed, this shall be done using a stump-grinding machine in a manner causing as little disturbance as possible to the adjacent trees.
- d. **Tree Preservation Fencing.** All areas of tree save depicted on the CDP/FDP shall be protected by tree protection fencing in the form of four (4) foot high, 14-gauge welded wire, attached to six (6) foot steel posts, driven eighteen (18) inches into the ground and placed no further than ten (10) feet apart. This fence type shall be shown on the Phase I and II erosion and sediment control sheets. The tree protection fencing shall be made clearly visible to all construction personnel, and shall be installed immediately after root pruning has taken place and prior to any clearing and grading activities on the site, including the demolition of any

existing structures. The installation of the tree protection fencing shall be performed under the supervision of a certified arborist. Prior to the commencement of any clearing, grading or demolition activities, the Applicant's certified arborist shall verify in writing that the tree protection fencing has been properly installed.

- e. **Root Pruning.** Prior to the commencement of any clearing, grading or other demolition activities, the limits of clearing and grading adjacent to all tree save areas depicted on the CDP/FDP shall be root-pruned to a depth of eighteen (18) inches with a trencher or vibratory plow. The Applicant's certified arborist shall verify in writing that the root pruning has taken place.
- f. **Mulching.** Immediately after the Phase I erosion and sediment controls have been installed, all areas of tree save shall be mulched ten (10) feet inside the limits of clearing and grading with four (4) inches of shredded hardwood bark mulch or equivalent.
- g. **Site Monitoring.** The Applicant shall retain the services of a certified arborist or landscape architect to monitor all construction work and tree preservation efforts in order to ensure conformance with Proffer No. 9. The monitoring schedule shall be described in detail in the tree preservation plan, and reviewed and approved by the Urban Forestry Division.
- h. **Replacement Value.** The Applicant shall retain a professional with experience in plant appraisal, such as a certified arborist or landscape architect, to determine the replacement value of abutting off-site trees as shown on the CDP/FDP ("designated trees"). These trees and their value shall be identified on the tree preservation plan at the time of the first submission of the subdivision plan. The replacement value shall be determined according to the methods contained in the latest edition of the *Guide for Plant Appraisal* published by the International Society of Arboriculture, subject to review and approval by the Urban Forestry Division.

At the time of subdivision plan approval, the Applicant will post a cash bond or letter of credit payable to the County of Fairfax to ensure preservation and/or replacement of the designated trees that die or are dying due to construction activities. The terms of the letter of credit shall be subject to approval by the County Attorney. The total amount of the cash bond or letter of credit shall be in the amount of the sum of the assigned replacement values of the designated trees, but in any event shall not exceed \$20,000.

At the time of bond release, if any designated trees are determined to be dead or dying due to construction activities, funds from the cash bond, or letter of credit, shall be used to plant similar species, or species appropriate to the site, in consultation with the Urban Forestry Division and the Applicant's certified arborist. The cash bond or letter of credit shall not be used for the removal of the

dead/dying trees normally required by the PFM and the Conservation Agreement. If the Applicant's certified arborist or landscape architect, in consultation with the Urban Forestry Division representative, determines that only a certain number of trees can be planted due to space constraints, which amounts to less than the full extent of the security, the remainder of the moneys shall be returned to the Applicant.

The letter of credit or cash bond will be released two (2) years from the date of release of the project's conservation escrow, or sooner, if approved by the Urban Forestry Division.

10. **Stream Restoration.**

- a. **Design Requirements.** The Applicant shall remove the existing rip-rapped ditch traversing the site in a manner subject to the approval of DPWES. In its stead, the Applicant shall relocate and restore the stream in the general location shown on the CDP/FDP. Subject to review and approval of DPWES, the streambed shall be constructed and restored in substantial conformance with the specifications set forth on Sheets 7 and 8 of the CDP/FDP (the "Stream Restoration Plan"). The final stream design shall utilize flow rates developed using either HEC-1, HEC-HMS, TR-20 or TR-55. HEC-RAS shall be used to determine velocities and shear stresses from the design flow rates in the channel bed and overbank flow area (i.e., floodplain). Substrate materials for the stream shall be specified based upon these results. Non-erosive velocities of the substrate material in the stream channel during the two (2) year storm (or top of the bank, whichever is greater) event shall be demonstrated by the design, and velocities in the overbank portion of the stream valley (outside of the "ordinary" stream channel flow area) shall be less than or equal to the allowable velocity for the proposed vegetative cover conditions in the 100-year event. Allowable velocities shall be based upon requirements of the PFM or by other accepted engineering methods as determined by DPWES. The design shall also provide incipient motion, scour, limiting slope criteria and bed armoring calculations to demonstrate the adequacy of the specified cobble size in the streambed. Calculations shall also be provided to check for toe and bank stability. Final design characteristics shall be subject to review and modification by DPWES.
- b. **Bonding.** Contemporaneously with either the release of the performance bond, or the reduction of that portion of the performance bond, whichever is applicable, attributable to completion and final approval of the Stream Restoration Plan (the "Completion Date"), the Applicant shall post a performance bond with Fairfax County in the amount of \$200,000 (the "Maintenance Bond"), to guarantee maintenance of the restored stream and associated riparian plantings for a five (5) year period. The amount of the Maintenance Bond shall be adjusted annually based on changes to the Construction Cost Index, published by the *Engineering News Record*, from the date of approval of the rezoning to the actual date of

payment. The Maintenance Bond shall be subject to annual reductions as provided in paragraph 9.c(3).

- c. **Monitoring Requirements.** Within forty-five (45) days of the Completion Date, representatives of the Applicant, OSDS and the Northern Virginia Soil and Water Conservation District ("NVSWCD") shall meet on site and select eight (8) locations for survey cross-sections of the channel and eight (8) locations for installation of photographic monuments. Within forty-five (45) days of the date of this meeting, the Developer shall prepare and submit to OSDS and NVSWCD for review and approval, the initial baseline stream monitoring report (the "Monitoring Report"). The Monitoring Report shall be sealed by a licensed, professional engineer (the "Engineer") retained by the Applicant.
- (1) The Monitoring Report shall include:
 - (a) The location of the cross-sections;
 - (b) Cross-section survey data, consisting of a graphical section drawing, coordinates of surveyed points (with an average spacing of two [2] feet or less) and the area of the channel below the plan formed by the section monuments;
 - (c) Photographs of the stream from each photo monument;
 - (d) Analysis of the riparian buffer condition relative to the survival rate and plant density specified on the construction plans approved by DPWES; and
 - (e) A narrative statement describing the status of the stream channel.
 - (2) On the date that is one year after the Completion Date, and on each anniversary date thereafter for the next four (4) years, the Applicant shall prepare and submit to DPWES and NVSWCD for review and approval, an annual Monitoring Report sealed by the Engineer. All survey data shall be compared graphically and numerically to the initial Monitoring Report. The narrative statement shall address whether corrective action is required under the Criteria, as hereinafter defined. The Applicant shall complete corrective actions recommended in the annual Monitoring Report.
 - (3) The Maintenance Bond amount shall be subject to a \$40,000 reduction each year, as follows: upon the date of the earlier to occur (i) approval of the annual Monitoring Report by DPWES and NVSWCD for a given year with no corrective action required; or (ii) completion and approval by DPWES and NVSWCD of any require corrective action, Fairfax County shall reduce the Maintenance Bond by \$40,000. Upon submission of the final annual Monitoring Report on the fifth anniversary date, the Applicant

shall complete required corrective actions, if any. If no corrective action is required, or upon approval of required corrective actions by DPWES and NVSWCD, Fairfax County shall release the balance of the Maintenance Bond.

11. **Recreational Facilities.** At the time of subdivision plan approval, pursuant to Sect. 6-110 of the Zoning Ordinance, the Applicant shall contribute the sum of \$955 per approved dwelling unit for the total number of dwelling units on the record plat, to the Fairfax County Park Authority ("Park Authority") for use on recreational facilities in the general vicinity of the Subject Property, subject, however, to a credit pursuant to Sect. 6-160 and Sect. 16-404 of the Zoning Ordinance for expenditures for on-site recreational facilities.
12. **Woodford Road.** At the time of recordation of the record plat for the subdivision, or upon demand by Fairfax County, whichever occurs first, right-of-way along the Woodford Road (Route 697) frontage of the site, necessary for public street purposes and as shown on the CDP/FDP, shall be dedicated and conveyed to the Board in fee simple. The Applicant shall also construct road widening along this frontage and a left turn lane as shown on the CDP/FDP, subject to VDOT approval.
13. **Density Credit.** All density and intensity of use attributable to land areas dedicated and conveyed to the Board pursuant to these proffers shall be subject to the provisions of Paragraph 4 of Sect. 2-308 of the Zoning Ordinance and density hereby reserved to be applied to the residue of the Subject Property.
14. **Homeowners' Association.** The Applicant shall establish a Homeowners' Association ("HOA") for the proposed development to own, manage and maintain the open space areas, including trees planted in these open space areas and the buffer areas on lots referenced in Proffer No. 26 hereinafter and all other community-owned land and improvements, including the private road. The HOA shall also maintain the perimeter fencing shown on the CDP/FDP. In cases where the fence is installed on a lot, the conveyance of that lot shall be subject to an easement to the benefit of the HOA permitting the HOA access to maintain the perimeter fence on that lot. This easement shall be a covenant running with the land. The HOA documents shall disclose these maintenance responsibilities. The HOA shall establish an architectural review committee to ensure that all additions/renovations or outbuildings are architecturally compatible.
15. **Stormwater Management.** Stormwater management and Best Management Practices ("BMPs") shall be accomplished through the provision of a dry pond in the area generally shown on the CDP/FDP. Said pond shall be constructed in accordance with the PFM unless otherwise waived or modified by DPWES but in no event shall the pond extend beyond the limits of clearing and grading. In order to restore a natural appearance to the proposed stormwater management pond, a landscape plan shall be submitted as part of the first submission of the subdivision plan showing extensive landscaping in all possible planting areas of the pond, in keeping with the planting policy of the County.

16. **Landscaping.** As part of the first submission of the subdivision plan, the Applicant shall submit to DPWES a landscape plan in substantial conformance with the landscaping shown on Sheets 2, 6, 7 and 8 of the CDP/FDP. This plan shall be subject to Urban Forestry Division review and approval. This landscape plan may be subject to minor adjustments approved by the Urban Forestry Division due to final engineering and utility layout. In order to curtail the spread of disease or insect infestation, this landscape plan shall include a variety of native tree species (including white oak, red maple, red oak, American holly, American beech, willow oak and dogwood) planted throughout the site where plantings are specified on the CDP/FDP. The Applicant shall also work with the Urban Forester to select plant species that in addition to meeting other landscaping requirements such as durability, availability and aesthetics, also aid in the maintenance of air quality.
17. **Affordable Housing Contribution.** Prior to the issuance of the first building permit, the Applicant shall contribute to the Fairfax County Housing Trust Fund a sum equal to one half of one percent (.5%) of the projected sales price of the new homes to be built on-site, as determined by the Department of Housing and Community Development and DPWES in consultation with the Applicant to assist the County in its goal to provide affordable dwelling elsewhere in the County.
18. **School Contribution.** Prior to the issuance of the first building permit, the Applicant shall contribute \$82,500 to the Board of Supervisors to be utilized for the provision of capital facilities within the Fairfax County School Board's pyramid of schools serving this development. In the event that the approved final subdivision plan yields less than thirty-three (33) units, this contribution amount shall be reduced proportionately based upon a ratio of 33 units to \$82,500.
19. **Archeology.** Prior to clearing and grading activity, the Applicant shall perform a Phase I survey in accordance with the Virginia Department of Historic Resources Guidelines, in the forested and undisturbed portions of the site. If based on the Phase I survey, the County Archeologist concludes that a Phase II and/or Phase III archeological study is warranted, the Applicant shall conduct such study or studies. Artifacts found during the survey process that are deemed significant by the County Archacologist may be removed by the County.
20. **Geotechnical Analysis.** The Applicant shall submit a geotechnical analysis of the soils and surface and sub-surface drainage conditions in accordance with the PFM and subject to the review and approval by DPWES. The Applicant shall implement the recommendations of the study to the satisfaction of DPWES. All foundations shall have sump pumps with interior and exterior drain tile. All exterior walls that are to be backfilled shall be treated with the "Epro" or an equivalent water proofing system.
21. **Driveways.** Driveways shall be a minimum of eighteen (18) feet in length so that vehicles may park within the driveway without overhanging into the sidewalk. In addition, said driveways shall also be of a width that can accommodate two vehicles.

22. **Interparcel Access.** Prior to subdivision plan approval, the Applicant shall post a cash escrow with DPWES to cover the cost of removal of the temporary cul-de-sac at such time as the public road is extended to Electric Avenue. The Applicant shall install a temporary barricade where the public street ends as shown on the CDP/FDP. In addition, the Applicant shall place a conspicuous sign at this location stating that this area will be the site of a future extension of the road by others to provide an interparcel connection. Both the barricade and the sign shall remain in place until the future road connection is made. The HOA shall maintain the sign in good repair.
23. **Telecommuting.** All dwellings shall be pre-wired with broadband, high capacity data/network connections in multiple rooms, in addition to standard phone lines.
24. **Right-of-Way Vacation.** Notwithstanding the submission for processing of any applications, plans or plat in furtherance of the development of the Application Property, the Applicant acknowledges that no such application, plan or plat shall be approved by Fairfax County until or unless the vacation right-of-way proposed as part of the Application Property is approved by the Board of Supervisors ("Board") and is final. In the event that such vacation is not approved by the Board, or in the event that the Board's approval is overturned by a court of competent jurisdiction, any development of the Application Property under the PDH-3 District shall require a proffered condition amendment and the Applicant acknowledges that such amendment may result in a loss of density. The Applicant hereby waives any right to claim or assert a taking or any other cause of action that otherwise may have arisen out of a Board decision to deny in whole or in part the right-of-way vacation.
25. **Construction Hours.** Construction activity will be limited on weekdays from 7:00 a.m. to 9:00 p.m. Monday through Friday. Construction activity after 7:00 p.m. will be limited to indoor work and light equipment operations. Construction activity will be limited to 8:00 a.m. to 5:00 p.m. on Saturdays. No construction activities will be permitted on Sundays, or on Federal holidays. This proffer applies to the original construction only and not to future additions and renovations by homeowners.
26. **Buffer Area.** Prior to entering into a contract of sale, prospective purchasers of houses on Lots 5, 17, 18, 19 and 20 shall be notified in writing by the Applicant that the vegetation provided on the fifteen (15) foot wide buffer planting area shown along their property lines shall not be disturbed or removed and said purchasers shall be required to acknowledge receipt of this information in writing. The HOA shall maintain the landscaping in the buffer areas on these lots, as well as the common open space areas. In cases where the buffer area is located on a lot, the conveyance of that lot shall be subject to an easement to the benefit of the HOA, permitting the HOA access to maintain the perimeter landscaped buffer. This easement shall be a covenant running with the land. The HOA documents shall disclose these maintenance responsibilities. This covenant shall also contain a provision limiting the use of the buffer planting area to passive open space and shall prohibit play equipment, above ground structures of any type and/or storage of materials within the buffer planting area. This covenant shall also run to the benefit of the Homeowners' Association and the form of these covenants shall be

reviewed and approved by the County Attorney, prior to recordation. Each deed of conveyance for said lots shall expressly contain these disclosures and these disclosures shall be contained in the Homeowners' Association documents.


27. **Trail.** The Applicant shall construct a six (6) foot wide asphalt trail extending from the on-site public street to Electric Avenue through Lot 33. The Applicant shall also construct a four (4) foot wide trail in the stream relocation area within the trail easement shown on the CDP/FDP.
28. **Signs.** No temporary signs (including "popsicle" style paper or cardboard signs) which are prohibited by Article 12 of the Zoning Ordinance, and no signs which are prohibited by Chapter 7 of Title 33.1 or Chapter 8 of Title 46.2 of the Code of Virginia shall be placed on- or off-site by the Applicant or at the Applicant's direction to assist in the initial sale of homes on the Property. Furthermore, the Applicant shall direct its agents and employees involved in marketing and sale of residential units on the Property to adhere to this proffer.
29. **Resource Protection Area ("RPA").** Unless determined appropriate by DPWES, no construction activity or clearing shall occur within the on-site RPA depicted on the CDP/FDP.
30. **Parking.** On-street parking spaces shall be located a minimum of ten (10) feet from driveway entrances or street intersections.
31. **Commemorative Sign.** Prior to subdivision plan approval, the Applicant shall contribute \$1,500 to the Fairfax County History Commission to be used towards the establishment of a commemorative sign off-site regarding the history of the Anne C. Williams Heights Subdivision, provided the Fairfax County History Commission determines the site location for the sign and the text of the sign.
32. **Fencing.** In addition to the fencing depicted on the CDP/FDP, the Applicant shall construct a seven (7) foot high wooden fence along the common boundary with Tax Map 39-3 ((1)) Parcel 63 and along the common boundary with Tax Map 39-3 ((1)) Parcel 52 (less and except that portion of the common boundary line that is located within a front yard).
33. **Plan Submission.** With each submission of plans to the County, a set of said plans shall be forwarded by the Applicant to office of the Supervisor for Providence District for review and comment by the Providence District Planning Commissioner and the Providence District Supervisor.
34. **Counterparts.** These proffers may be executed in one or more counterparts, each of which when so executed and delivered shall be deemed an original, and all of which taken together shall constitute but one and the same instrument.

[SIGNATURES ON THE FOLLOWING PAGES]

**APPLICANT/CONTRACT PURCHASER OF SUBJECT
PROPERTY/OWNER OF TAX MAP 39-3 ((1)) PARCELS
59 AND 61 AND A PORTION OF SUNCREST LANE**

VAN METRE LAND LIMITED PARTNERSHIP

By: Fifth Genpar, Inc., General Partner

By: 
Richard J. Rabil, President

**OWNERS OF TAX MAP 39-1 ((1)) PARCELS 13, 14, 14A
AND 15A; TAX MAP 39-3 ((1)) PARCELS 50 AND 51**

Anthony V. Falcone

June A. Falcone

**OWNERS OF TAX MAP 39-3 ((1)) PARCELS 53 AND
55**

Anthony V.J. Falcone


June A. Falcone

OWNER OF TAX MAP 39-3 ((1)) PARCEL 54

CHRISTIAN RELIEF SERVICES OF VIRGINIA, INC.

By: _____
Eugene L. Krizek, President

**OWNER OF TAX MAP 39-3 ((1)) PARCELS 56 AND
60 AND A PORTION OF SUNCREST LANE**



Mary E. Harne

**APPLICANT/CONTRACT PURCHASER OF SUBJECT
PROPERTY/OWNER OF TAX MAP 39-3 ((1)) PARCELS
59 AND 61 AND A PORTION OF SUNCREST LANE**

VAN METRE LAND LIMITED PARTNERSHIP

By: Fifth Genpar, Inc., General Partner

By: _____
Richard J. Rabil, President

**OWNERS OF TAX MAP 39-1 ((1)) PARCELS 13, 14, 14A
AND 15A; TAX MAP 39-3 ((1)) PARCELS 50 AND 51**




Anthony V. Falcone




June A. Falcone

**OWNERS OF TAX MAP 39-3 ((1)) PARCELS 53 AND
55**



Anthony V.J. Falcone



June A. Falcone

OWNER OF TAX MAP 39-3 ((1)) PARCEL 54

CHRISTIAN RELIEF SERVICES OF VIRGINIA, INC.

By: _____
Eugene L. Krizek, President

**OWNER OF TAX MAP 39-3 ((1)) PARCELS 56 AND
60 AND A PORTION OF SUNCREST LANE**

Mary E. Hame

**APPLICANT/CONTRACT PURCHASER OF SUBJECT
PROPERTY/OWNER OF TAX MAP 39-3 ((1)) PARCELS
59 AND 61 AND A PORTION OF SUNCREST LANE**

VAN METRE LAND LIMITED PARTNERSHIP

By: Fifth Genpar, Inc., General Partner

By: _____
Richard J. Rabil, President

**OWNERS OF TAX MAP 39-1 ((1)) PARCELS 13, 14, 14A
AND 15A; TAX MAP 39-3 ((1)) PARCELS 50 AND 51**

Anthony V. Falcone

June A. Falcone

**OWNERS OF TAX MAP 39-3 ((1)) PARCELS 53 AND
55**

Anthony V.J. Falcone

June A. Falcone

OWNER OF TAX MAP 39-3 ((1)) PARCEL 54

CHRISTIAN RELIEF SERVICES OF VIRGINIA, INC.

By:  _____
Bryan L. Krizek, Vice President of Housing

**OWNER OF TAX MAP 39-3 ((1)) PARCELS 56 AND
60 AND A PORTION OF SUNCREST LANE**

Mary E. Harne