SPECIAL EXCEPTION PLAT

ON THE PROPERTY OF

CENTREVILLE UNITED METHODIST CHURCH

6400 OLD CENTREVILLE ROAD, CENTREVILLE, VA 20121



SPECIAL EXCEPTION NOTES:

1. THE PARCELS SHOWN HEREON ARE DELINEATED ON FAIRFAX COUNTY ASSESSMENT MAP NO. 65-1, ((1)), 14A AND 14A1, AND 65-1, ((5)), J1.
2. BOUNDARY INFORMATION SHOWN HEREON IS FROM INFORMATION OF RECORD.
3. TOPOGRAPHIC INFORMATION SHOWN HEREON IS AERIAL FROM INFORMATION OF RECORD.
4. PARCELS 65-1, ((1)), 14A AND 14A1 ARE ZONED R-1, CONTAINING 3.11 ACRES OF LAND.
5. PARCEL 65-1, ((5)), J1 IS ZONED PDH-12, CONTAINING 6.35 ACRES OF LAND.
6. THE EXISTING CHURCH BUILDING ON PARCEL J1 IS 26.7 FEET IN HEIGHT IN THE TWO-STORY PORTIONS. IT WAS BUILT IN 1992. A PROJECT TO COMPLETE MASTER PLANNED IMPROVEMENTS WAS COMPLETED IN 2006. THE EXISTING CHURCH BUILDING WILL BE RETAINED AND NO WORK IS PROPOSED ON PARCEL J1. THE EXISTING HOUSE ON PARCEL 14 WAS BUILT IN 1935. IT IS APPROXIMATELY 19 FEET IN HEIGHT, IS IN POOR CONDITION, AND WILL BE REMOVED.
7. THIS PLAN PROPOSES NO IMPROVEMENTS TO EXISTING RIGHTS-OF-WAY.
8. PARCEL J1 (THE CHURCH PARCEL) IS SERVED BY PUBLIC WATER AND SEWER. PARCELS 14A AND 14A1 HAVE NO SEWER OR WATER SERVICE, NOR IS ANY WATER OR SEWER SERVICE PROPOSED FOR THIS PLAN. USERS OF THE RECREATIONAL PARCEL WILL USE FACILITIES IN THE CHURCH BUILDING.
9. A VERY SMALL INCREASE IN IMPERVIOUS AREA IS PROPOSED WITH THIS PROJECT. THE NEW IMPERVIOUS AREAS ARE AT THE TOP OF THE PROPERTY. SIGNIFICANT OPEN SPACE AND VEGETATION ON THE PROPERTY WILL ATTENUATE THE MINIMAL INCREASE IN RUNOFF FROM THIS PROJECT.
10. THE GROSS FLOOR AREA OF THE EXISTING CHURCH BUILDING IS 61,345 SF AND THE FAR ASSOCIATED WITH PARCEL J1 IS 0.225, WITH NO CHANGES PROPOSED TO PARCEL J1. THE EXISTING HOUSE CONTAINS APPROXIMATELY 880 SF, EQUATING TO A FAR OF 0.006, AND WILL BE REMOVED. THERE WILL BE NO DWELLING UNITS PROPOSED ON THE PROPERTY OWNED BY CENTREVILLE UNITED METHODIST CHURCH.
11. EXISTING VEGETATED AREAS ARE AS SHOWN ON THE PLAN. SEVERAL EXISTING DEAD OR DYING TREES WITHIN THE AREA OF THE PROPOSED IMPROVEMENTS WILL BE REMOVED FOR SAFETY AS SHOWN ON THE PLAN. VEGETATED AREAS TO BE SAVED INCLUDE A MIX OF HARDWOOD AND EVERGREEN. OPEN AREAS CONSIST OF TALL GRASSES AND BUSHES.
12. THERE ARE NO FLOODPLAINS OR RESOURCE PROTECTION AREAS WITHIN THE BOUNDARIES OF THIS SITE.
13. AN OPEN PAVILION IS PROPOSED SIMILAR TO THOSE SHOWN ON SHEET 4 OF 4. LIGHTING WILL BE PROPOSED IN THE INTERIOR ROOF OF THE STRUCTURE TO LIGHT THE PAVILION ONLY. NO LOUDSPEAKERS WILL BE USED.
14. THERE ARE NO MAJOR UTILITY EASEMENTS ON THE SITE. THERE ARE EXISTING OVERHEAD UTILITY LINES THAT RUN ALONGSIDE ROUTE 28 ON THE WEST SIDE OF THE SOUTHBOUND LANES. AN EXISTING POLE ASSOCIATED WITH THAT SYSTEM IS SECURED BY SEVERAL GUY WIRES THAT ENCROACH ONTO THE RECREATION PARCEL.
15. A MAJOR TRAIL IS INDICATED ON THE WEST SIDE OF THE SOUTHBOUND LANES OF ROUTE 28 BY THE COMPREHENSIVE TRAILS PLAN. A WAIVER OF THE REQUIREMENT TO CONSTRUCT THE TRAIL IS HEREBY REQUESTED. HOWEVER, AN EASEMENT FOR THE TRAIL WILL BE GRANTED AS REQUESTED BY FAIRFAX COUNTY.
16. BASED ON SITE INSPECTION, THERE ARE NO KNOWN GRAVES OR PLACES OF BURIAL ON THE SITE.
17. SIGNAGE WILL BE AS PRESCRIBED BY ARTICLE 12 OF THE FAIRFAX COUNTY ZONING ORDINANCE.
18. THE FOLLOWING WAIVERS ARE HEREBY REQUESTED:

    A WAIVER OF THE REQUIREMENT TO CONSTRUCT AN 8' WIDE PAVED TRAIL ALONG THE WEST SIDE OF THE SOUTHBOUND LANES OF ROUTE 28 IS REQUESTED.

    A WAIVER OF THE DEVELOPER CONDITION TO CONSTRUCT AN 8' WIDE PAVED TRAIL ALONG THE SOUTH SIDE OF THE EASTBOUND LANES OF NEW BRADDOCK ROAD IS REQUESTED.

19. THE FOLLOWING MODIFICATIONS ARE HEREBY REQUESED:

    A MODIFICATION OF THE REQUIREMENT TO PROVIDE BARRIERS AND/OR TRANSITIONAL SCREENING YARDS IS REQUESTED ALONG THE SHARED PROPERTY LINE WITH THE DEBELL PROPERTY (TO THE EAST) IN FAVOR OF PRESERVATION OF EXISTING LANDSCAPING AS SHOWN ON THE PLAN. THERE ARE SEVERAL EXISTING, MATURE TREES ALONG THE EXISTING FENCE INCLUDING EASTERN RED CEDAR, MAPLE, AND TWO 36" OAKS. IN ADDITION, BEYOND THE FENCE THERE IS A TRIANGULAR SHAPED PROPERTY WITH SIGNIFICANT EXISTING VEGETATION CONSISTING OF DECIDUOUS AND EVERGREEN TREES AND UNDERSTORY VEGETATION.

    A MODIFICATION OF THE REQUIREMENT TO PROVIDE BARRIERS AND/OR TRANSITIONAL SCREENING YARDS IS REQUESTED ALONG THE SHARED PROPERTY LINE WITH THE OLD MILL ESTATES PROPERTY IN FAVOR OF THE COMBINED PRESERVATION OF EXISTING VEGETATION AND PROPOSED PLANTINGS SHOWN ON THE PLAN. THIS PLAN ALSO PROPOSES TO CONSTRUCT A WOODEN FENCE ON THE ADJACENT OLD MILL ESTATES DEVELOPMENT AS REQUESTED BY THE HOA.

    MODIFICATIONS TO THE TRANSITIONAL SCREENING REQUIREMENTS TO THE NORTH AND SOUTH ARE REQUESTED IN FAVOR OF THE PRESERVATION OF EXISTING VEGETATION AND REVEGETATION TO THE SOUTH AS SHOWN ON THE PLAN.

SOIL MAP DATA

SOIL ID	SERIES	FOUNDTION SUPPORT	DRAINAGE	INFILTRATION TRENCHES	EROSION POTENTIAL
57C2	BRECKNOCK	GOOD	FAIR	MARGINAL	MODERATE
76B1	CALVERTON	POOR	MARGINAL	POOR	MODERATE

PARKING TABULATION

	REQUIRED	PROVIDED
BASED ON SANCTUARY SEATING 1 SPACE PER 4 SEATS * 640 SEATS	160 SPACES	
NURSERY SCHOOL 0.16 SPACES PER CHILD	24 SPACES	
TOTAL SPACES AS REQUIRED BY FDP 81-S-058	184 SPACES	201 SPACES
HANDICAPPED SPACES INCLUDED IN THE REQUIRED SPACES	3 SPACES	3 SPACES

MAXIMUM ALLOWABLE SPACES 238, PER FDP 81-S-058

Application No. SE 2009 SU-003 Staff DeManche
APPROVED (SE) / SP PLAN
SEE DEV CONDS DATED May 14, 2009
Date of (BOS) (BZA) approval June 1, 2009
Sheet 1 of 5

RECEIVED
Department of Planning & Zoning
APR 21 2009
Zoning Evaluation Division

SHEET INDEX

1	OF 4	COVER SHEET & OVERALL PLAN
2	OF 4	RECREATION PARCEL PLAN
2A	OF 4	CHURCH PARCEL PLAN
3	OF 4	DRAINAGE PLAN
4	OF 4	PHOTOGRAPHS

1	1/25/09	COUNTY COMMENTS
2	4/20/09	COUNTY COMMENTS

SEAL

COMMONWEALTH OF VIRGINIA
LAURA F. MILLER
Lic. No. 35537
4/20/09
PROFESSIONAL ENGINEER

COVER SHEET & OVERALL PLAN

CENTREVILLE UNITED METHODIST CHURCH
SULLY DISTRICT
FAIRFAX COUNTY, VIRGINIA

ODESTY, LLC
6941 CONFEDERATE RIDGE LANE
CENTREVILLE, VA 20121
(703) 507-1227

PROJECT 08-004 CUMC
FILE 004-0V
DATE NOVEMBER 2008
SHEET 1 OF 4



EXISTING VEGETATION

EXISTING VEGETATION ON THIS SITE CONSISTS OF A MIXTURE OF HARDWOODS AND EVERGREENS, WITH LARGE AREAS OF OPEN GRASSLANDS, GENERALLY AS SHOWN ON THE MAP ABOVE. IN THE CENTER OF THE SITE, GENERALLY IN THE VICINITY OF THE PROPOSED RECREATIONAL IMPROVEMENTS, THERE ARE SEVERAL DEAD OR DYING TREES THAT WILL BE REMOVED. PICTURES OF THE VEGETATION ARE INCLUDED ON SHEET 4. ADDITIONAL RELATIVELY SMALL AREAS OF TREES WILL BE REMOVED AS SHOWN FOR THE T-BALL FIELD AND THE OPEN PLAY AREA EXTENDING INTO THE SOUTHERN POINT OF THE SITE. OTHER THAN THE INDIVIDUAL TREES SHOWN TO BE REMOVED ON THE SITE, THE INTENT IS TO MINIMIZE REMOVAL OF VEGETATION. THE PROPOSED TRAIL AND WORSHIP AREA WILL BE MEANDERED THROUGH THE EXISTING VEGETATION TO TAKE ADVANTAGE OF THE NATURAL AREAS.

THE LARGEST PERCENTAGE OF EXISITNG VEGETATION ON SITE IS DECIDUOUS CONSISTING OF OAK, MAPLE, WALNUT, DOGWOOD, TULIP, AND OTHER VARIETIES. THE SMALLER PERCENTAGE IS EVERGREEN INCLUDING EASTERN RED CEDAR, SCOTCH PINE AND OTHER VARIETIES. THERE IS SIGNIFICANT UNDERSTORY GROWTH INCLUDING SMALL TREES AND SHRUBS, AND TALL MEADOW GRASSES IN THE OPEN AREAS. IN ADDITION, THERE ARE TWO DISTINCT BAMBOO COMMUNITIES ON THE SITE, BOTH WITHIN THE TREE SAVE AREA ON THE SOUTH END OF THE SITE.

EXISTING CONDITIONS PLAN

GRAPHIC SCALE: 1" = 40'

PROPOSED IMPROVEMENTS

THE ACTIVITIES FIELDS SHOWN ARE FOR USE BY THE PRE-SCHOOL STUDENTS OF CENTREVILLE DAY SCHOOL AND BY THE CHURCH MEMBERSHIP. FIELDS WILL BE CONSTRUCTED BY BRUSH HOGGING THE EXISTING LOT, REMOVAL OF TRIPPING HAZARDS, AND ESTABLISHMENT OF LAWN WITHIN THE FIELD AREAS. CONCRETE PAD AND MULCH SURFACES FOR TRAIL AND PAVILION WILL BE CONSTRUCTED ON EXISTING GRADE TO AVOID EXCAVATION.

ALL CONSTRUCTION WILL BE PHASED AS FUNDING BECOMES AVAILABLE SUCH THAT NO MORE THAN 2500 SF OF LAND SHALL BE DISTURBED AT ANY ONE TIME.

PROPOSED IMPROVEMENTS PLAN

GRAPHIC SCALE: 1" = 40'

1	1/25/09	COUNTY COMMENTS
2	4/20/09	COUNTY COMMENTS

SEAL

COMMONWEALTH OF VIRGINIA
LAURA F. MILLER
Lic. No. 35537
4/20/09
PROFESSIONAL ENGINEER

RECREATION PARCEL PLAN

CENTREVILLE UNITED METHODIST CHURCH

SULLY DISTRICT

FAIRFAX COUNTY, VIRGINIA

Application No SE 2007-SU-003 Staff Reviewer Nemanche
APPROVED (SE) SP PLAN
SEE DEV CONDS DATED May 14, 2009
Date of (BOS) (BZA) approval June 1, 2009
Sheet 2 of 5

ODESTY, LLC
6941 CONFEDERATE RIDGE LANE
CENTREVILLE, VA 20121
(703) 507-1227

PROJECT	08-004 CUMC
FILE	004-0V
DATE	NOVEMBER 2008
SHEET	2 OF 4

65-1, ((6)), C1
CENTRE RIDGE, SECTION 6A3
PARCEL C1
ZONE: PDH-12
USE: RESIDENTIAL OPEN SPACE
DB 7441, PG 980

65-1, ((6)), B8
CENTRE RIDGE, PARCEL 10-B6
ZONE: PDC
USE: SHOPPING CENTER
DB 11782, PG 890

65-1, ((6)), D3
CENTRE RIDGE, SEC. 8B
PARCEL D1
ZONE: PDH-12
USE: OPEN SPACE
D.B. 7569, PG. 638

NEW BRADDOCK ROAD - RT. 620
POSTED SPEED = 40MPH
R/W WIDTHS
VPD = 22,000

CENTREWOOD DRIVE - ROUTE 8351
POSTED SPEED = 30 MPH
R/W WIDTHS
12,000 VPD

OLD CENTREVILLE ROAD - ROUTE 657
POSTED SPEED = 30 MPH
R/W WIDTHS
12,000 VPD

65-1, ((1)), 1
TRUSTEES OF CENTREVILLE UNITED METHODIST CHURCH
EXISTING TWO-STORY CHURCH TO REMAIN
6400 OLD CENTREVILLE ROAD
276,831 SF OR 6.3506 ACRES
DB 7555 PG 1534
ZONED: PDH-12
FF = 345.42
EX BUILDING HEIGHT == 26.67' (EXCEPT SANCTUARY)

DAY SCHOOL (1ST FLOOR)
EXISTING PLAY AREA
EX MULCH
EX 6' HT SOLID WOOD FENCE

65-1, ((6)), F1
N/F OLD MILL COMMUNITY ASSOCIATION
C/O EQUITABLE FEDERAL SAVINGS BANK
ZONE: PDH-3
USE: SINGLE FAMILY DETACHED
DB 8261, PG 884

65-1, ((1)), 8C
N/F MILDRED K. DEBELL TRUSTEE
ZONE: R-1
USE: SINGLE FAMILY DETACHED
DB 12426, PG 2009

65-1, ((1)), 8A1
N/F MILDRED K. DEBELL TRUSTEE
ZONE: R-1
USE: VACANT LAND
DB 10701, PG 637

EX. 15 FCWA EASEMENT DB 7872 PG 929
EX. 10' FCWA EASEMENT DB 7872 PG 929

EX. STORM MANHOLE TOP=340.57
15" INV IN=336.98
15" INV OUT=334.97

EX. STORM CURB INLET
TOP=335.89
15" INV IN=331.19
15" INV OUT=331.00

EX. STORM SEW. MH
TOP=340.51
6" INV IN=337.50
6" INV OUT=337.20

EX. STORM CURB INLET
TOP=340.51
6" INV IN


NEA BRADDOCK ROAD - ROUTE 620
SULLY ROAD - ROUTE 28
CENTREVILLE UNITED METHODIST CHURCH
SITE
OPEN CHANNEL
CLOSED CONDUIT
OPEN CHANNEL
POND
CLOSED CONDUIT
CENTREVILLE ELEMENTARY SCHOOL
LIMIT OF DOWNSTREAM REVIEW
DRAINAGE AREA = 130 AC±
Easement
Centreville
Multiplex
Sweetwater
Belt
Buckle Ct.
Canteen
Button Ct.
Company
Shaving
Grainery
Cobie
Laskey Ct.
Federation
Colonial
Singletons
Green Trails Blvd.
Rt. 8024
Rt. 7783
Rt. 7712
Rt. 7784
Rt. 7774
Rt. 8551
Rt. 8556
Rt. 8558
Rt. 8632
Rt. 8634
Rt. 8635
Rt. 8636
Rt. 8637
Rt. 8638
Rt. 8639
Rt. 8640
Rt. 8641
Rt. 8642
Rt. 8643
Rt. 8644
Rt. 8645
Rt. 8646
Rt. 8647
Rt. 8648
Rt. 8649
Rt. 8650
Rt. 8651
Rt. 8652
Rt. 8653
Rt.

(1) LOOKING EAST ON OLD CENTREVILLE ROAD



(2) LOOKING TOWARD SITE ENTRANCE



(3) LOOKING INTO SITE FROM ENTRANCE (4)



(5) (6) (7) (8)

VIEW FROM FUTURE HOME PLATE



EXISTING HOUSE TO BE DEMOLISHED



EXISTING SHED AND TRAILER TO REMAIN



EXAMPLES OF OUTDOOR PAVILION



(9) LOOKING SOUTH ALONG ROUTE 28



(10) LOOKING WEST INTO SITE FROM ROUTE 28



(11) LOOKING NORTH ALONG ROUTE 28

Application No. SE 2009-SU-002 Staff DeManche
APPROVED (SE) / SP PLAN
SEE DEV CONDS DATED May 14, 2009
Date of (BOS) (BZA) approval June 1, 2009
Sheet 5 of 5

1	1/25/09	COUNTY COMMENTS
2	4/20/09	COUNTY COMMENTS

SEAL

COMMONWEALTH OF VIRGINIA
LAURA F. MILLER
Lic. No. 35537
4/20/09
PROFESSIONAL ENGINEER

PHOTOGRAPHS

CENTREVILLE UNITED METHODIST CHURCH

SULLY DISTRICT
FAIRFAX COUNTY, VIRGINIA

ODESTY, LLC
6941 CONFEDERATE RIDGE LANE
CENTREVILLE, VA 20121
(703) 507-1227

PROJECT
08-004 CUMC

FILE
004-PH

DATE
NOVEMBER 2008

SHEET
4 OF 4