

METRO PLACE AT DUNN LORING

PROVIDENCE DISTRICT FAIRFAX COUNTY, VIRGINIA

PCA 84-P-129-5 / FDPA 84-P-129-4

CONCEPTUAL / FINAL DEVELOPMENT PLAN AMENDMENT

NOTES:

- THE PROPERTY THAT IS THE SUBJECT OF THIS CONCEPTUAL DEVELOPMENT PLAN AMENDMENT (CDPA)/FINAL DEVELOPMENT PLAN AMENDMENT (FDPA) IS IDENTIFIED ON THE FAIRFAX COUNTY ZONING MAP AS 49-2 (37) C1, D2, E, AND F1.
- THE BOUNDARY INFORMATION SHOWN HEREON IS FROM EXISTING RECORDS. GREENHORNE & O'MARA, INC. ASSUMES NO RESPONSIBILITY FOR DESIGN OR CONSTRUCTION CHANGES CAUSED BY INACCURACIES IN THE BOUNDARY INFORMATION.
- THE TOPOGRAPHY SHOWN HEREON IS AT A CONTOUR INTERVAL OF 0.5 METERS FROM A FIELD RUN SURVEY BY GREENHORNE & O'MARA, INC.
- STORMWATER MANAGEMENT (SWM) AND BEST MANAGEMENT PRACTICES (BMP) REQUIREMENTS FOR THE DEVELOPMENT OF THIS SITE WILL BE PROVIDED ON-SITE IN PROPOSED UNDERGROUND FACILITIES AS SHOWN ON THE GRAPHIC UNLESS WAIVED TO THE EXISTING OFFSITE REGIONAL SWM LAKE AT FAIRVIEW PARK (RESERVOIR 2A), SUBJECT TO THE UPGRADE OF AN OFFSITE STORM DRAIN OUTFALL AND THE EXECUTION OF A BMP AGREEMENT WITH THE OWNER OF THE REGIONAL SWM LAKE. THE EXACT SIZE AND LOCATIONS OF THE FACILITIES WILL BE DETERMINED AT THE TIME OF FINAL ENGINEERING AND DESIGN.
- THE LANDSCAPED OPEN SPACE AREAS REPRESENTED ON THE GRAPHIC ARE PRELIMINARY AND SUBJECT TO MINOR MODIFICATION AT TIME OF FINAL ENGINEERING AND DESIGN. LANDSCAPING AND TREE COVER WILL BE PROVIDED IN ACCORDANCE WITH THE APPLICABLE PROVISIONS OF ARTICLE 13.
- IN ACCORDANCE WITH PAR 4 OF SECT 16-403 OF THE ZONING ORDINANCE, MINOR MODIFICATIONS TO THE SIZES, DIMENSIONS, FOOTPRINTS AND LOCATIONS OF BUILDINGS, SIDEWALKS/TRAILS, AND UTILITIES MAY OCCUR WITH FINAL ENGINEERING AND DESIGN.

THE APPLICANT RESERVES THE RIGHT TO DEVELOP A LESSER NUMBER OF DWELLING UNITS THAN THAT NUMBER REPRESENTED IN THE TABULATION AND REDUCE THE NUMBER OF PARKING SPACES, ACCORDINGLY OR PROVIDE ADDITIONAL PARKING SPACES IN THE AREA(S) OF THE REDUCED BUILDING FOOTPRINTS.
- IT IS TO BE UNDERSTOOD THAT ADDITIONAL SITE FEATURES SUCH AS CAZEBOS, TRELISES, SITE FURNITURE, SIGNS, PLANTERS, FENCES, GATES AND/OR WALLS NOT REPRESENTED HEREON MAY BE PROVIDED. IT IS TO BE FURTHER UNDERSTOOD THAT ARCHITECTURAL FEATURES SUCH AS BALCONIES AND STAIRWELLS MAY ALSO BE PROVIDED.
- AFFORDABLE DWELLING UNITS WILL BE PROVIDED IN ACCORDANCE WITH ARTICLE 2-800 OF THE ZONING ORDINANCE. THE NUMBER OF ADUS TO BE PROVIDED WILL BE ADJUSTED BASED UPON THE ACTUAL NUMBER OF UNITS CONSTRUCTED.
- AT A MINIMUM, PARKING WILL BE PROVIDED IN ACCORDANCE WITH THE PROVISIONS OF ARTICLE 11 OF THE ZONING ORDINANCE. THE APPLICANT RESERVES THE RIGHT TO PROVIDE MORE THAN THE MINIMUM REQUIRED NUMBER OF PARKING SPACES AND MORE THAN THE NUMBER REPRESENTED IN THE TABULATION AS LONG AS THE AMOUNT OF OPEN SPACE REPRESENTED IN THE TABULATION AND THE MINIMUM DISTANCES FROM THE SPACES TO THE PERIPHERAL LOT LINES ARE NOT DIMINISHED.
- THE NUMBER AND LOCATION OF ACCESSIBLE PARKING SPACES AND LOADING SPACES TO BE PROVIDED WILL BE DETERMINED AT THE TIME OF SITE PLAN SUBMISSION AND WILL BE IN ACCORDANCE WITH THE PROVISIONS OF ARTICLE 11 OF THE ZONING ORDINANCE.
- PUBLIC IMPROVEMENTS HAVE BEEN/WILL BE PROVIDED IN ACCORDANCE WITH THE PROFFERS FOR METRO PLACE AT DUNN LORING PCA 84-P-129-2, PCA 84-P-129-3, AND PCA 84-P-129-4.
- LANDSCAPED COURTS AND A COMMUNITY CENTER WILL BE PROVIDED AS SPECIAL AMENITIES FOR THE PROPOSED DEVELOPMENT.

- THERE ARE NO PUBLIC FACILITIES PROPOSED.
- THE ENTIRE SITE IS SUBJECT TO CLEARING AND GRADING.
- THERE IS NO FLOODPLAIN DESIGNATED BY THE FEDERAL INSURANCE ADMINISTRATION, UNITED STATES GEOLOGICAL SURVEY OR FAIRFAX COUNTY, OR ANY ENVIRONMENTAL QUALITY CORRIDOR (EQC) OR RESOURCE PROTECTION AREA (RPA) LOCATED ON THE SUBJECT PROPERTY.
- THERE ARE NO AREAS THAT HAVE SCENIC ASSETS OR NATURAL FEATURES DESERVING OF PROTECTION OR PRESERVATION ON THE SITE.
- THERE ARE NO UTILITY EASEMENTS LOCATED ON THE SUBJECT PROPERTY THAT HAVE A WIDTH OF TWENTY-FIVE (25) FEET OR MORE.
- SANITARY SEWER AND WATER ARE CURRENTLY AVAILABLE AND WILL BE EXTENDED TO THE SUBJECT PROPERTY AS SHOWN ON THE GRAPHIC.
- THERE ARE EXISTING MULTIPLE-FAMILY DWELLING UNITS LOCATED TO THE EAST AND SOUTH OF THE DEVELOPMENT. THERE IS A METRO STOP STATION COMPLEX LOCATED TO THE WEST AND AN INTERSTATE HIGHWAY LOCATED TO THE NORTH OF THE DEVELOPMENT. THE PROPOSED MULTIPLE-FAMILY AND SINGLE-FAMILY ATTACHED DWELLING UNITS WILL NOT POSE ANY ADVERSE EFFECTS ON ADJACENT OR NEIGHBORING PROPERTIES.
- THE PROPOSED DEVELOPMENT IS LOCATED WITHIN THE MERRIFIELD COMMUNITY PLANNING SECTOR (J6) OF THE JEFFERSON PLANNING DISTRICT AND THE DUNN LORING TRANSIT STATION AREA (TRACT B), MERRIFIELD SUBURBAN CENTER OF AREA 1 OF THE COMPREHENSIVE PLAN. THE COMPREHENSIVE PLAN RECOMMENDS MIXED-USE WITH A MAXIMUM FLOOR AREA RATIO (FOR ALL USES, INCLUDING RESIDENTIAL) OF 1.4. THE PROPOSED DEVELOPMENT IS IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE COMPREHENSIVE PLAN.
- SUBJECT TO MARKET CONDITIONS, IT IS CURRENTLY ANTICIPATED THAT CONSTRUCTION OF THE PROPOSED DEVELOPMENT WILL COMMENCE AS SOON AS ALL NECESSARY COUNTY APPROVALS AND PERMITS ARE OBTAINED.
- TO THE BEST OF OUR KNOWLEDGE, THERE ARE NO GRAVES LOCATED ON THE SUBJECT PROPERTY.
- TO THE BEST OF OUR KNOWLEDGE, NO HAZARDOUS AND TOXIC SUBSTANCES AS SET FORTH IN TITLE 40, CODE OF FEDERAL REGULATIONS PARTS 116.4, 302.4 AND 355; HAZARDOUS WASTE AS SET FORTH IN THE VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY HAZARDOUS MANAGEMENT REGULATIONS; AND/OR PETROLEUM PRODUCTS AS DEFINED IN TITLE 40, CODE OF FEDERAL REGULATIONS PART 280 WILL BE GENERATED, UTILIZED, STORED, TREATED OR DISPOSED OF ON THE SUBJECT PROPERTY INCLUDING ANY EXISTING OR PROPOSED STORAGE TANKS OR CONTAINERS AND THEIR CONTENTS.
- A STATEMENT WHICH CONFIRMS THE OWNERSHIP OF THE SUBJECT PROPERTY, AND THE NATURE OF THE APPLICANT'S INTEREST IN THE SAME IS PROVIDED IN A SEPARATE ASSOCIATED DOCUMENT.
- THERE IS AN EXISTING SIDEWALK ALONG GALLOWS ROAD AS REQUIRED BY THE ADOPTED COMPREHENSIVE PLAN.
- THE CDPA SHALL CONSTITUTE THE ENTIRE PLAN RELATIVE TO THE POINTS OF ACCESS, THE TOTAL GROSS FLOOR AREA, NUMBER OF DWELLING UNITS, THE USES AND THE GENERAL LOCATION AND AMOUNT OF OPEN SPACE AREAS AND BUILDINGS.
- THE LOCATION AND ARRANGEMENT OF THE STRUCTURES REFLECTED IN THE LAYOUT AND SITE IMPROVEMENTS SHOWN HEREON MAY BE MODIFIED WITH ONLY THE APPROVAL OF A FDPA THAT MAY BE SUBSEQUENTLY FILED AND A CDPA/PCA MAY OR MAY NOT BE REQUIRED.
- THE DEVELOPER SHALL HAVE THE OPTION TO REQUEST AN FDPA FOR THE ENTIRE PLAN OR PORTIONS THEREOF IN ACCORDANCE WITH THE PROVISIONS SET FORTH IN SECT. 16-402 OF THE ZONING ORDINANCE.
- INFORMATION ON THE SOIL TYPES LOCATED ON THE SUBJECT PROPERTY IS NOT AVAILABLE IN THE FAIRFAX COUNTY SOILS MAPS REVISED TO JANUARY 1, 1990. THE INFORMATION HAS BEEN REQUESTED AND WILL BE PROVIDED AT A LATER DATE.
- TO THE BEST OF OUR KNOWLEDGE THE PROPOSED DEVELOPMENT OF THE SUBJECT PROPERTY CONFORMS TO ALL CURRENT APPLICABLE LAND DEVELOPMENT ORDINANCES, REGULATIONS AND ADOPTED STANDARDS.
- A WAIVER IS REQUESTED TO ELIMINATE THE REQUIREMENT FOR PROVIDING LOADING SPACES AS REQUIRED PER ARTICLE 11-203.

- A WAIVER IS REQUESTED TO ELIMINATE THE REAR YARD REQUIREMENT FOR A MINIMUM OF 200 SF REAR YARD PER ARTICLE 6-207 AND 6-306. THIS WAIVER IS SOUGHT SO THAT INNOVATIVE ARCHITECTURE (I.E. REAR LOADED GARAGES & ENGLISH BASEMENT ENTRANCES) CAN BE PROVIDED.
- ELEVATIONS REFER TO METRIC UNITS.
- DUMPSTERS AND RECYCLE BINS WILL BE PROVIDED WITHIN PARKING GARAGES OF PARCELS C1, F1, AND G1. PARCELS D2 & E WILL UTILIZE INDIVIDUAL TRASH RECYCLE CONTAINERS TO BE COLLECTED BY A TRASH/RECYCLE COLLECTION SERVICE.
- PARKING FOR TOWNHOUSES IS ACCOMPLISHED IN TWO CAR GARAGES WITH 16 FT WIDE DOORS; BY PROVIDING TWO 8.5 FT BY 18 FT SPACES WITHIN 18 FT WIDE UNIT GARAGES AND 9 FT BY 18 FT SPACES WITHIN 24 FT WIDE UNITS. ADDITIONALLY 17 PARALLEL PARKING SPACES ARE PROVIDED FOR A TOTAL OF 2.3 SPACES PER UNIT.
- A TRANSITIONAL SCREENING WAIVER AND A BARRIER WAIVER ARE REQUESTED FOR THIS SITE WHERE IT ABUTS GALLOWS ROAD.
- THE BUILDING ILLUSTRATIONS HEREON ARE PROVIDED TO ILLUSTRATE THE ARCHITECTURAL THEME AND DESIGN INTENT OF THE COMMUNITY. THE ARCHITECTURAL DESIGN OF THE PROPOSED RESIDENCES SHALL GENERALLY CONFORM WITH THE CHARACTER AND QUALITY OF THESE ILLUSTRATIVE ELEVATIONS, BUT THE APPLICANT RESERVES THE RIGHT TO MODIFY THESE ELEVATIONS BASED ON FINAL ARCHITECTURAL DESIGN.

TABULATIONS:

TABULATION FOR ENTIRE DEVELOPMENT:

EXISTING ZONING	PDH-40 AND PDC
APPROVED LAND AREA	17.86 AC
APPROVED GROSS FLOOR AREA	990,321 SF
APPROVED FLOOR AREA RATIO (FAR)	1.25
APPROVED TOTAL NUMBER OF UNITS	397
APPROVED OPEN SPACE	±4.2 AC
PROPOSED LAND AREA	17.86 AC*
PROPOSED GROSS FLOOR AREA	1,061,641± SF
PROPOSED FLOOR AREA RATIO (FAR)	1.36
PROPOSED NUMBER OF UNITS	395
PROPOSED OPEN SPACE	4.2± AC
DEVELOPED RECREATIONAL OPEN SPACE	4,500± SF
PARKING SPACES REQUIRED	1,728
PARKING SPACES PROPOSED	1,728±

*THE AREA OF THE ENTIRE DEVELOPMENT IS BASED ON THE APPROVED LAND AREA (18.27 AC) LESS THE AREA THAT HAS BEEN DEDICATED FOR THE RIGHT-OF-WAY FOR GALLOWS ROAD.

ALL DENSITY RELATED TO SUCH DEDICATION HAS BEEN RESERVED PURSUANT TO PAR. 4 OF SECT. 2-308 OF THE ZONING ORDINANCE SUCH DENSITY CREDIT WAS RESERVED IN ACCORDANCE WITH PROFFERS DATED MAY 3, 1989. DEDICATION WAS RECORDED IN DEED BOOK 7279 AT PAGE 1410.

PARCEL USE	GFAS(F)	NO. OF UNITS	LAND AREA (AC)	FAR/DENSITY
	(PROPI)	(PRIOR FDPA)	(PROPI)	(PRIOR FDPA)
PDC ZONE				
A OFFICE	144,325	144,325	2.94	1.23 FAR
B SERVICE RETAIL	13,000	13,000		
C OFFICE	233,746	233,746	2.91	1.85 FAR
*C1 RESIDENTIAL (INCLUDE 2 ADUS)	220,000	135,000	2.78	1.82 FAR
D2 RESIDENTIAL	±	±	±	±
H-1 RESIDENTIAL COMMUNITY CENTER	41,550±	45,000	0.75	1.27 FAR
SUBTOTAL PDC	652,621±	573,071	9.38	1.60 FAR
PDH-40 ZONE PROPOSED				
D2 RESIDENTIAL	16,920±	7	0.46	0.84 FAR
E RESIDENTIAL	79,850±	105,000	1.67	1.10 FAR
F1 RESIDENTIAL	99,250±	99,250	1.18	1.93 FAR
G1 RESIDENTIAL	213,000±	213,000	2.53	1.93 FAR
H-1 PRIVATE ROAD			2.64	
SUBTOTAL PDH-40	409,020±	417,250	6.44	1.11 FAR
TOTAL	1,061,641	990,321	17.86	1.36 FAR

* INCLUDES ±2000 SF CLUBHOUSE

TABULATION FOR PDH-40 DISTRICT PROPOSED:

EXISTING ZONING	PDH-40
APPROVED LAND AREA	8.33 AC
APPROVED GROSS FLOOR AREA	459,000 SF
RESIDENTIAL (APPROXIMATELY 403,000± SF)	400 UNITS
PROPOSED LAND AREA	8.48 AC*
PROPOSED GROSS FLOOR AREA	409,020± SF
RESIDENTIAL	409,020± SF
PROPOSED NUMBER OF UNITS	263
PROPOSED DENSITY	1.11 FAR
MAXIMUM HEIGHT OF BUILDINGS (4 STORIES)	60 FT

REQUIRED NUMBER OF PARKING SPACES:

224 MF @ 1.6 SPS / UNIT =	359 SPACES
39 TH @ 2.3 SPS / UNIT =	90 SPACES
TOTAL =	449± SPACES
PROPOSED NUMBER OF PARKING SPACES REQUIRED/PROPOSED OPEN SPACE (35%)	1.82 AC**

*2.64 ACRES OF THE 8.64 ACRES IS FOR PARCEL H-1 PRIVATE ROAD PARCEL. PART OF PARCEL H-1 IS IN THE PDC DISTRICT BUT IT'S TOTAL IS INCLUDED HEREIN.

**OPEN SPACE CALCULATIONS ARE BASED ON LAND AREA AFTER DEDICATION

TABULATION FOR PDC DISTRICT PROPOSED:

EXISTING ZONING	PDC
APPROVED LAND AREA	9.94 AC*
APPROVED GROSS FLOOR AREA	573,071 SF
SERVICE RETAIL	13,000± SF
OFFICE	378,071± SF
RESIDENTIAL (APPROXIMATELY 108 DU'S)	135,000± SF
PROPOSED LAND AREA	9.38 AC**
PROPOSED GROSS FLOOR AREA	652,621± SF
SERVICE RETAIL	13,000± SF
OFFICE GROSS	378,071± SF
RESIDENTIAL	259,550± SF
COMMUNITY CENTER	2,000± SF
PROPOSED FLOOR AREA RATIO (FAR)	1.55

PROPOSED NUMBER OF UNITS: 132

MAXIMUM HEIGHT OF BUILDINGS (5 STORIES): 60 FT

REQUIRED NUMBER OF PARKING SPACES:

SERVICE RETAIL	1,279
OFFICE	783
RESIDENTIAL	16 TH @ 2.3 = 37
	116 MF @ 1.6 = 186
TOTAL	1,279±
PROPOSED NUMBER OF PARKING SPACES	223

REQUIRED OPEN SPACE (15%): 1.50 AC


PROPOSED OPEN SPACE (22±%): 2.16 AC

*THE DIFFERENCE BETWEEN THE APPROVED AND PROPOSED LAND AREA IS DUE TO AN INACCURACY IN THE ORIGINAL SURVEY.

** DENSITY CALCULATIONS ARE BASED ON THE PROPOSED LAND AREA (9.22 AC) PLUS THE AREA THAT HAS BEEN DEDICATED FOR THE RIGHT-OF-WAY FOR GALLOWS ROAD.

TABULATIONS FOR ENTIRE CDPA/FDPA 84-P-129-4: (PARCELS C, E, & F)

APPROVED LAND AREA	6.84 AC
APPROVED GROSS FLOOR AREA	386,250 SF
APPROVED FLOOR AREA RATIO	1.30
APPROVED TOTAL NUMBER OF UNITS	235
APPROVED OPEN SPACE	2.74 AC
PROPOSED LAND AREA	6.84 AC
PROPOSED GROSS FLOOR AREA	457,570 SF
PROPOSED FLOOR AREA RATIO	1.54
PROPOSED TOTAL NUMBER OF UNITS	233 INCLUDING ADUS
ADUS REQUIRED	2
ADUS PROVIDED	2
PROPOSED OPEN SPACE	2.10 AC



APPLICANT:
JADE-DUNN LORING METRO, L.L.C.
8230 OLD COURTHOUSE ROAD, SUITE 422
VIENNA, VIRGINIA 22182


RECEIVED
DEPARTMENT OF PLANNING AND ZONING
JAN 13 1999



THE LISSARD ARCHITECTURAL GROUP
Inc.
8229 BOONE BOULEVARD • SUITE 640 • VIENNA, VA 22182 • 703/760-9344 • FAX 703/760-9328

CONCEPTUAL / FINAL DEVELOPMENT PLAN AMENDMENT
METRO PLACE AT DUNN LORING
PARCELS C1, D2, E & F1
PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA

PLANNING • SITE ENGINEERING • TRANSPORTATION • ENVIRONMENTAL • SURVEYING/MAPPING
Greenhome & O'Mara, Inc.
1121 MAPLES MILL ROAD
FAIRFAX, VIRGINIA 22030
(703) 385-9800
ANNAPOLIS, MD • ATLANTA, GA • FAIRFAX, VA • FREDERICKSBURG, VA • GREENBELT, MD
MECHANICSBURG, PA • RALEIGH, NC • ROCKVILLE, MD • TAMPA, FL • WEST PALM BEACH, FL





No.	REVISION	DATE	BY
1	84-P-129-5	1-13-99	SLH
2	84-P-129-5	1-13-99	SLH
3	84-P-129-5	1-13-99	SLH
4	84-P-129-5	1-13-99	SLH

W/MY DESIGN SLH DRAWN CHECKED
SCALE: N/A DATE: 1/7/99
PROJ No. 5169 FILE No. M-1302
1 OF 4 SHEET





- ### SHEET INDEX:
- COVER SHEET
 - 50 SCALE DEVELOPMENT PLAN
 - TYPICAL BUILDING ELEVATIONS
 - TYPICAL BUILDING ELEVATIONS



BOUNDARY & PARCEL INFORMATION:
SCALE: 1" = 200'



- LEGEND:**
- SURVEYED SITE BOUNDARY AND PROPERTY LINES
 - * PROPOSED EVERGREEN TREE
 - ⊙ PROPOSED ORNAMENTAL TREE
 - PROPOSED MEDIUM SIZED DECIDUOUS TREE
 - PROPOSED LARGE DECIDUOUS TREE
 - EXISTING VEGETATION
 - PROPOSED SANITARY SEWER
 - EXISTING SANITARY SEWER & EASEMENT
 - PROPOSED STORM SEWER
 - EXISTING STORM SEWER & EASEMENT
 - PROPOSED WATERLINE
 - EXISTING WATERLINE & EASEMENT
 - PROPOSED SIDEWALK
 - EXISTING SIDEWALK
 - PROPOSED LOCATION OF UNDERGROUND SWM FACILITY



THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL JURISDICTIONS. THE ARCHITECTURAL GROUP SHALL NOT BE RESPONSIBLE FOR ANY VIOLATIONS OF ANY APPLICABLE CODES, ORDINANCES, REGULATIONS, OR STATUTES. THE ARCHITECTURAL GROUP SHALL NOT BE RESPONSIBLE FOR ANY DAMAGE TO PERSONS OR PROPERTY, INCLUDING BUT NOT LIMITED TO, DAMAGE TO EXISTING UTILITIES, STRUCTURES, OR LANDSCAPE. THE ARCHITECTURAL GROUP SHALL NOT BE RESPONSIBLE FOR ANY DELAYS OR COSTS INCURRED BY THE USER AS A RESULT OF ANY CHANGES TO THE PROJECT. THE ARCHITECTURAL GROUP SHALL NOT BE RESPONSIBLE FOR ANY LIABILITY ARISING OUT OF THE USE OF THIS DRAWING.

THE LESSARD ARCHITECTURAL GROUP
Inc.
1223 BOKOR BOULEVARD • SUITE 640 • VICTORIA, VA 22182 • 703/700-9344 • FAX 703/700-3238




CONCEPTUAL / FINAL DEVELOPMENT PLAN AMENDMENT
METRO PLACE AT DUNN LORING
PARCELS C-1, D-2, E & F-1
PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA

PLANNING • SITE ENGINEERING • TRANSPORTATION • ENVIRONMENTAL • SURVEYING/MAPPING
Greenhome & O'Mara, Inc.
11211 WAPLES MILL ROAD
FAIRFAX, VIRGINIA 22030
(703) 385-9800
ANNAPOLIS, MD • ATLANTA, GA • FARGO, ND • FREDERICKSBURG, VA • GREENBELT, MD
MECHANICSBURG, PA • RALEIGH, NC • ROCKVILLE, MD • TAMPA, FL • WEST PALM BEACH, FL



No.	REVISION	DATE	BY
1	APPROVED DEVELOPMENT PLAN	2-2-99	PK
2	SITE PREPARED	3-22-99	PK

WJMY	SLH	DESIGN	DRAWN	CHECKED
1" = 50'	1/7/99	5169	M-1302	
PROJ. No.	FILE No.	2	4	



PARCEL C-1
FRONT ELEVATION


DATE NOVEMBER 6, 1998

SCALE: 3/16"=1'-0"

JADE DEVELOPMENT

**METRO PLACE
AT DUNN LORING METRO**
FAIRFAX, VIRGINIA

THE LESSARD ARCHITECTURAL GROUP, INC.
6500 Westwood Center Drive, Suite 400, Vienna, VA 22182
703/760-9344 • FAX 703/760-9348
www.lessard.com



PARCEL C-1
REAR ELEVATION

DATE NOVEMBER 6, 1998

SCALE: 3/16"=1'-0"

JADE DEVELOPMENT

**METRO PLACE
AT DUNN LORING METRO**
FAIRFAX, VIRGINIA

THE LESSARD ARCHITECTURAL GROUP, INC.
6500 Westwood Center Drive, Suite 400, Vienna, VA 22182
703/760-9344 • FAX 703/760-9348
www.lessard.com

PC 84-P-129-S Staff LINDA STAGG
APPROVED DEVELOPMENT PLAN
(P) (SD) (P) (P)
SEE PROJECTIONS DATED 2-2-99
Date of (P) (P) approval 3-22-99

FOR INFORMATION ONLY




CONCEPTUAL / FINAL DEVELOPMENT PLAN AMENDMENT
METRO PLACE AT DUNN LORING
PARCELS C-1, D-2, E & F-1
PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA

PLANNING • SITE ENGINEERING • TRANSPORTATION • ENVIRONMENTAL • SURVEYING/MAPPING
Greenhome & O'Mara, Inc.
11211 WAPLES MILL ROAD
FAIRFAX, VIRGINIA 22030
(703) 385-9800
ANNAPOLIS, MD • ATLANTA, GA • FAIRFAX, VA • FREDERICKSBURG, VA • GREENBELT, MD
MECHANICSBURG, PA • RALEIGH, NC • ROCKVILLE, MD • TAMPA, FL • WEST PALM BEACH, FL



No.	REVISION	DATE	BY

WVWY	SLH		
DESIGN	DRAWN	CHECKED	
AS SHOWN	DATE		
SCALE			
5169	M-1302		
PROJ. No.	FILE No.		
3	4		
SHEET			



THE WESTBRIAR PARCEL F-1
AT DUNN LORING METRO
FAIRFAX, VIRGINIA

BUILDING REAR ELEVATION



THE WESTBRIAR PARCEL F-1
AT DUNN LORING METRO
FAIRFAX, VIRGINIA

BUILDING FRONT ELEVATION

Application No. _____ Staff
APPROVED DEVELOPMENT PLAN
(DP) (GDY) (CDP) (LEDP)
SEE PROFFERS DATED _____
Date of (BOS) (PC) approval _____ of _____

FOR INFORMATION ONLY

© 1999 THE LESSARD ARCHITECTURAL GROUP, INC. ALL RIGHTS RESERVED. THIS DRAWING IS THE PROPERTY OF THE LESSARD ARCHITECTURAL GROUP, INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT THE EXPRESS WRITTEN PERMISSION OF THE LESSARD ARCHITECTURAL GROUP, INC.

THE LESSARD ARCHITECTURAL GROUP
Inc.



DESIGN	SLH	CHECKED
AS SHOWN	1/7/99	DATE
5169	M-1302	FILE No.
PROJ No.		
4	OF	4



Greenhorne & O'Mara, Inc.
11211 WAPLES MILL ROAD
FAIRFAX, VIRGINIA 22030
(703) 985-9800

ANNAPOLIS, MD • ATLANTA, GA • FAIRFAX, VA • FREDERICKSBURG, VA • GREENSBET, MD
MECHANICSBURG, PA • RALEIGH, NC • ROCKVILLE, MD • FAIRFAX, VA • WEST PALM BEACH, FL

CONCEPTUAL / FINAL DEVELOPMENT PLAN AMENDMENT
METRO PLACE AT DUNN LORING
PARCELS C-1, D-2, E & F-1
PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA

