



County of Fairfax, Virginia

To protect and enrich the quality of life for the people, neighborhoods and diverse communities of Fairfax County

February 26, 2014

Jill S. Parks
Cooley LLP
One Freedom Square, Reston Town Center
11951 Freedom Drive, Suite 1500
Reston, VA 20190

RE: Rezoning Application RZ 2012-PR-002

Dear Ms. Parks:

Enclosed you will find a copy of an Ordinance adopted by the Board of Supervisors at a regular meeting held on February 25, 2014, granting Rezoning Application RZ 2012-PR-002 in the name of Greensboro Park Property Owner LLC. The Board's action rezones certain property in the Providence District from the C-4 and SC Districts to the PTC and SC Districts to permit office and residential development with an overall Floor Area Ratio (FAR) of 3.23, approval of final development plans and a waiver #6028-WPFM-006-1 to permit the location of underground storm water management facilities in a residential area. The subject property is located in the N.W. quadrant of the intersection of Greensboro Drive and International Drive on approximately 6.98 acres of land, [Tax Map 29-3 ((15)) 12A and 29-4 ((9)) 12B], subject to the proffers dated February 19, 2014, and subject to the Conceptual Development Plan Condition dated February 25, 2014.

The Board also:

- Waived Par. 1 of Sect. 6-506 to allow a district size of less than 10 acres for an application.
- Waived Par. 7 of Sect. 6-505 of the ZO, requiring the designation of specific outdoor dining areas on the FDP, to permit outdoor dining in any area, exclusive of rights-of-way, where the adjoining use includes dining activity. The outdoor dining areas shall be indicated at time of site plan review.
- Waived Par. 2 of Sect. 2-506 of the ZO to allow a parapet wall, cornice or similar projection to exceed the established height limit by more than three feet, as may be indicated on the CDP/FDP.

Office of the Clerk to the Board of Supervisors
12000 Government Center Parkway, Suite 533
Fairfax, Virginia 22035

Phone: 703-324-3151 ♦ Fax: 703-324-3926 ♦ TTY: 703-324-3903
Email: clerktothebos@fairfaxcounty.gov
<http://www.fairfaxcounty.gov/bosclerk>

- Modified Sect. 11-201 and 11-203 of the ZO to permit a reduction in the required number of loading spaces to that shown on the CDP/FDP.
- Modified Sect. 7-0800 of the PFM to allow the use of valet spaces.
- Modified Par. 4 of Sect. 11-202 of the ZO, requiring a minimum distance of 40 feet of a loading space in proximity to drive aisles, to that shown on the CDP/FDP.
- Waived Sect. 11-302 of the ZO to allow a private street to exceed 600 feet in length as shown on the CDP.
- Waived Par. 7 of Sect. 17-201 of the ZO to permit the applicant to establish parking control, signs and parking meters along private streets within the development.
- Modified Sect. 17-201 of the ZO to permit the streetscape and on-road bike lane system shown on the CDP/FDP in place of any trails and bike trails shown for the subject property on the Comprehensive Plan.
- Waived Par. 3 of Sect. 17-201 of the ZO to require only those interparcel connections shown on the CDP/FDP and as proffered.
- Waived Par. 4 of Sect. 17-201 of the ZO to require the proposed frontage improvements indicated on the CDP/FDP and proffers.
- Waived Sect. 2-505 of the ZO to permit structures and vegetation on a corner lot as shown on the CDP/FDP.
- Waived Par. 5 of Sect. 13-203 of the ZO to modify the peripheral landscaping requirements for the existing surface parking lots to remain to that which is shown on the CDP/FDP.
- Modified the Zoning Ordinance and PFM for required tree preservation target and 10 percent canopy coverage on individual lots/land bays, to allow for tree preservation and canopy to be calculated as shown on the overall CDP area.
- Approved a waiver to allow the use of underground stormwater management and best management practices in a residential development, subject to Waiver #6028-WPFM-006-1.

Sincerely,



Catherine A. Chianese
Clerk to the Board of Supervisors

Cc: Chairman Sharon Bulova
Supervisor Linda Smyth, Providence District
Tim Shirocky, Acting Director, Real Estate Division, Dept. of Tax Administration
Barbara Berlin, Director, Zoning Evaluation Division, DPZ
Diane Johnson-Quinn, Deputy Zoning Administrator, Dept. of Planning and Zoning
Thomas Conry, Dept. Manager – GIS - Mapping/Overlay
Angela K. Rodeheaver, Section Chief, Transportation Planning Division
Donald Stephens, Transportation Planning Division
Department of Highways-VDOT
Sandy Stallman, Park Planning Branch Manager, FCPA
Charlene Fuhrman-Schulz, Development Officer, DHCD/Design Development Division
Jill Cooper, Executive Director, Planning Commission
Lee Ann Pender, Office of Capital Facilities/Fairfax County Public Schools
Karyn Moreland, Chief Capital Projects Sections, Dept. of Transportation

At a regular meeting of the Board of Supervisors of Fairfax County, Virginia, held in the Board Auditorium in the Government Center at Fairfax, Virginia, on the 25th day of February, 2014, the following ordinance was adopted:

**AN ORDINANCE AMENDING THE ZONING ORDINANCE
PROPOSAL NUMBER RZ 2012-PR-002**

WHEREAS, Greensboro Park Property Owner LLC, filed in the proper form an application requesting the zoning of a certain parcel of land herein after described, from the C-4 and SC Districts to the PTC and SC Districts, and

WHEREAS, at a duly called public hearing the Planning Commission considered the application and the propriety of amending the Zoning Ordinance in accordance therewith, and thereafter did submit to this Board its recommendation, and

WHEREAS, this Board has today held a duly called public hearing and after due consideration of the reports, recommendation, testimony and facts pertinent to the proposed amendment, the Board is of the opinion that the Ordinance should be amended,

NOW, THEREFORE, BE IT ORDAINED, that that certain parcel of land situated in the Providence District, and more particularly described as follows (see attached legal description):

Be, and hereby is, zoned to the PTC and SC Districts, and said property is subject to the use regulations of said PTC and SC Districts, and further restricted by the conditions proffered and accepted pursuant to Va. Code Ann., 15.2-2303(a), which conditions are in addition to the Zoning Ordinance regulations applicable to said parcel, and

BE IT FURTHER ENACTED, that the boundaries of the Zoning Map heretofore adopted as a part of the Zoning Ordinance be, and they hereby are, amended in accordance with this enactment, and that said zoning map shall annotate and incorporate by reference the additional conditions governing said parcel.

GIVEN under my hand this 25th day of February, 2014.



Catherine A. Chianese

Clerk to the Board of Supervisors

**GREENSBORO PARK PLACE
PROFFER STATEMENT**

RZ 2012-PR-002

**July 26, 2012
November 19, 2012
January 15, 2013
March 22, 2013
April 16, 2013
May 20, 2013
May 31, 2013
September 3, 2013
November 8, 2013
December 5, 2013
December 16, 2013
January 9, 2014
January 16, 2014
February 6, 2014
February 19, 2014**



INDEX

<u>PROFFER</u>	<u>PAGE</u>
1. Substantial Conformance	4
2. Proffered CDP Elements.....	4
3. Minor Modifications to the CDP	4
4. Final Development Plan Amendment.....	5
5. Development Program	6
6. Uses.....	6
7. Gross Floor Area.....	7
8. Residential Dwelling Units.....	7
9. Adjustments to the GFA	7
10. Existing and Interim Structures and Uses.....	7
11. Architecture.....	8
12. Bird-Friendly Design	8
13. Build-To Lines.....	8
14. Building Heights	9
15. Rooftop Telecommunications Equipment and Mechanical Units	9
16. Green Building.....	9
17. Sustainable Energy Practices	12
18. Landscape Plan	12
19. Streetscape	12
A. International Drive	12
B. Greensboro Drive	13
C. Streetscape Elements	14
D. Streetscape Activation	14
E. Alternative Planting Width Details	14
F. Non-Invasive Plant Materials	15
G. Utility Locations	15
H. Fire Marshal	16
I. Sight Distance	16
J. Streetscape Furnishings and Materials	16
K. Lighting	16
L. Construction Lighting	17
M. Signage and Way-finding	17
N. Maintenance of the Pedestrian Realm	17
O. Maintenance Agreement	17
P. Right-of-Way Dedication	18
20. Grid of Streets.....	19
21. Extension of Results Road by Others	20
22. Contributions for the Extension of Results Road and Summit Street.....	21
23. VDOT Acceptance and Dedication	21
24. Tysons Grid Fund Contributions	22
25. Tysons-wide Transportation Contributions for Table 7 Improvements	22
26. Bus Shelter	22
27. Congestion Management Plan	23
28. Notification Letter	23
29. Bicycle Parking.....	23
30. Bicycle Lanes	23

INDEX
CONTINUED

<u>PROFFER</u>	<u>PAGE</u>
31. Parking	23
32. Unbundled Parking for Residential Uses	24
33. Parking for Non-Residential Uses	24
34. Tysons Transportation Management Association.....	24
35. Transportation Demand Management Plan for the Residential Buildings	25
36. Transportation Demand Management Plan for the Existing Office Buildings.....	34
37. Affordable Dwelling Units	37
38. Workforce Dwelling Units.....	37
39. Publicly-Accessible Parks.....	38
40. Private Amenities and Recreational Facilities for Residents.....	39
41. Athletic Field Contribution	39
42. Noise Attenuation	39
43. Public Facility	40
44. Public School Contribution.....	42
45. Stormwater Management.....	43
46. Tree Preservation	44
47. Planting Fund Contribution.....	47
48. Umbrella Owners' Association or Equivalent	47
49. Metrorail Tax District Buyout for Certain Residential Uses	48
50. Escalation in Contribution Amounts.....	48
51. Density Credit	48
52. Tysons Partnership.....	48
53. Condemnation.....	48
54. Delay.....	49
55. Severability	49
56. Binding Effect.....	49
57. Counterparts.....	49

**PROFFER STATEMENT
GREENSBORO PARK PLACE**

RZ 2012-PR-002

Greensboro Park Property Owner LLC (the "Applicant"), as owner of the property identified on the 2013 Fairfax County Tax Map as Tax Map 29-4 ((9)) 12B and 29-3 ((15)) 12A (the "Property"), seeks to rezone the Property from the C-4 (High Intensity Office) and SC (Sign Control Overlay) Districts to the Planned Tysons Corner Urban ("PTC") and SC Districts (the "Rezoning").

Pursuant to Section 15.2-2303(A) of the Code of Virginia, as amended, and subject to approval by the Fairfax County Board of Supervisors of the Rezoning, the Applicant hereby proffers that development of the Property shall be in accordance with the following conditions (the "Proffers"), which, if the Rezoning is approved by the Board of Supervisors, shall replace and supersede any and all existing proffered conditions applicable to the Property. In the event the Rezoning is denied, these Proffers shall immediately be null and void and the previous proffered conditions shall remain in full force and effect.

GENERAL

1. Substantial Conformance. Subject to these Proffers and the provisions of Sections 6-500, 16-400 and 18-204 of the Zoning Ordinance of Fairfax County, as amended (the "Zoning Ordinance"), the Property shall be developed in substantial conformance with the Conceptual Development Plan ("CDP") dated November 22, 2012, as revised through January 16, 2014, and prepared by VIKA, Incorporated.
2. Proffered CDP Elements. The proffered elements of the CDP are limited to the uses, grid of streets, general location of the residential and office buildings and their respective entrances, minimum and maximum building heights, overall maximum gross floor area ("GFA"), build-to lines, general quality and character of the streetscape, minimum amount and general location of the publicly-accessible open space, and other elements as may be specifically identified herein (the "Proffered Elements"). As Final Development Plan ("FDP") approval is requested from the Planning Commission concurrently with approval of the Rezoning, other elements of the CDP may be adjusted or modified with approval of a Final Development Plan Amendment ("FDPA") in accordance with the provisions set forth in Section 16-402 of the Fairfax County Zoning Ordinance (the "Zoning Ordinance"), and these Proffers.
3. Minor Modifications to the CDP. Minor modifications to the Proffered Elements of the CDP may be permitted pursuant to Paragraph 4 of Section 16-403 of the Zoning Ordinance when necessitated by sound engineering or when necessary as part of final site design, and when such modifications are determined to be in substantial conformance with the Proffered Elements and these Proffers, as determined by the Zoning Administrator. The number of residential units and square footage within each Residential Building (as defined below) may be adjusted up or down, so long as (a) the minimum number of residential units is provided; (b) the maximum number of residential

units is not exceeded; (c) the proposed publicly-accessible park space is not reduced; (d) the building heights for each Residential Building are not decreased below the minimum or increased above the maximum heights identified on the CDP/FDP; and (e) the Proposed Development, as defined in Proffer 5 herein, is otherwise in substantial conformance with these Proffers and the CDP.

4. Final Development Plan Amendment. FDP approval is requested from the Planning Commission in accordance with Sect. 16-402 of the Zoning Ordinance. The following tabulations and information may be adjusted or amended with approval of a subsequent FDPA:

- A. Architectural Elements. Design information on building materials, architectural massing and fenestration, and specific features designed to activate the streetscapes, as further described in these Proffers;
- B. Build-to Lines. Proposed Build-to Lines, including any proposed modifications to the Build-to Lines and/or the expanded streetscape areas as identified in Proffer 13;
- C. Conceptual Utility Plans. The Conceptual Utility Plan;
- D. Streetscape Furnishings and Materials. The Streetscape Furnishing and Materials Plan;
- E. Lighting. Specific streetscape lights per Proffer 19(K);
- F. Parking Spaces. The final number and location of surface and structured parking spaces;
- G. Stormwater Management. A detailed Stormwater Management Plan, as described in Proffer 45;
- H. Bicycle Parking. Specific locations and the number of bicycle facilities to be provided as described in Proffer 29;
- I. Publicly-Accessible Parks and Recreational Facilities. The specific details on parks and recreational facilities, as described in Proffer 39 and 40;
- J. Sustainable Energy Practices. The sustainable energy practices described in Proffer 17;
- K. Sight Distance Lines. Sight distance lines shall be shown for all affected intersections;
- L. Phasing/Interim Conditions. Phased improvements and interim conditions in accordance with these Proffers;

- M. Residential Amenities. Facilities and amenities to be provided in each Residential Building;
 - N. Tree Canopy Calculations. A tabulation indicating the tree canopy calculations;
 - O. Landscape Plan. The Landscape Plan, as described in Proffer 18;
 - P. Tabulation. The tabulation indicating the development status of the Property subject to the Rezoning;
 - Q. Parking. The parking tabulations; and,
 - R. Parking Structure/Loading/Service Area Treatments. Proposed parking structure/loading/service area façade treatments.
5. Development Program. The Applicant shall be permitted to develop the Property with a mix of uses and structures that may ultimately consist of the following:
- A. Two (2) existing office buildings containing a mix of commercial uses and totaling approximately 504,574 gross square feet (excluding cellar) (the “Existing Office Buildings”);
 - B. Two new residential buildings containing a mix of residential and community-serving/retail uses totaling approximately 485,000 square feet (the “Residential Buildings”);
 - C. Two (2) existing parking structures associated with the Existing Office Buildings (the “Existing Parking Structures”);
 - D. A new parking structure beneath the Residential Buildings (the “Residential Parking Structure”); and,
 - E. The surface parking spaces shown on the CDP/FDP (the “Surface Parking Spaces”),

all as more particularly shown on the CDP/FDP and described in these Proffers (the “Proposed Development”).

PERMITTED USES AND INTENSITY

6. Uses. The Applicant shall develop the Property primarily with office and residential uses; however, it may also include any accessory, retail, service and/or other non-residential use permitted by-right, by Special Exception (“SE”), or by Special Permit (“SP”) in the Planned Tysons Corner Urban (“PTC”) District, including, but not limited to, public and quasi-public uses, accessory uses and accessory service uses, business service and supply service uses, commercial recreational uses, community uses, eating establishments, financial institutions, garment cleaning establishments, personal service

and repair service establishments and retail sales establishments. Such uses, including eating establishments and retail sales establishments, may be provided generally within the ground floors of the Residential Buildings and/or Existing Office Buildings; however such uses may also be provided within upper floors with approval of a future FDPA. In the Applicant's sole discretion, it may permit a food truck to operate on the Property as an accessory use, provided that any such truck is operated for a maximum of three hours per day, is located on a paved surface that does not interfere with vehicular or pedestrian circulation or parking availability, and its location is coordinated with DPZ.

7. Gross Floor Area. The maximum GFA permitted on the Property is approximately 990,000 square feet (excluding cellar in the Existing Office Buildings).
8. Residential Dwelling Units. Residential Building A shall contain a minimum of Two Hundred and Fifty-Six (256) residential dwelling units and a maximum of Two Hundred and Seventy-Six (276) residential dwelling units. Residential Building B shall contain a minimum of Two Hundred and Twenty-Seven (227) residential dwelling units and a maximum of Two Hundred and Forty-Four (244) residential dwelling units, for a total minimum of Four Hundred and Eighty-Three (483) residential dwelling units and maximum of Five Hundred and Twenty (520) residential dwelling units.
9. Adjustments to the GFA. GFA may be shifted between the two Residential Buildings provided the maximum height shown for each building is not exceeded, the minimum building height is not reduced, the overall urban form and building type as shown on the CDP are maintained and such adjustments are consistent with these Proffers. If at the time of site plan, the GFA approved for one Residential Building is less than the GFA shown on the approved CDP and FDP, the excess GFA may be utilized in the other Residential Building, provided the maximum height for each building is not exceeded, the minimum height for each building is maintained, the overall urban form and building types depicted on the CDP/FDP are maintained, and such adjustments are consistent with these Proffers.
10. Existing and Interim Structures and Uses.
 - A. The Existing Office Buildings and Existing Parking Structures. The Existing Office Buildings and Existing Parking Structures may remain in use until such time as the Applicant elects to redevelop them and proceeds with a Conceptual Development Plan Amendment ("CDPA"), Proffered Condition Amendment ("PCA") and/or FDPA, as applicable. Existing structures may not be modified or enlarged; however, minor structure modifications may be approved by the Zoning Administrator pursuant to the provisions of Par. 4 of Sect. 16-403 of the Zoning Ordinance. Interior modifications to all existing structures shall be permitted.
 - B. The Existing Surface Parking Lot. The existing surface parking lot on the Property may remain in use as parking for the tenants of the Existing Office Buildings until such time as the Applicant elects to commence construction of the Residential Buildings. For purposes of this Proffer, "commence construction" means that the Applicant has (1) executed a contract with a General Contractor;

(2) issued formal notice to proceed for the full scope; and (3) the General Contractor has mobilized at the Property.

- C. Commuter Parking. As an option, before it commences construction of the Residential Buildings (as defined above) and with written notification to FCDOT, the Applicant may elect to use on an interim basis any of its existing parking facilities, including the Existing Parking Structures and the existing surface parking lot, for privately-owned and operated commercial off-street parking and/or commuter parking. In the event the Applicant opts to use the existing surface parking lot for commuter parking per the above, it shall conduct an assessment of queuing at the driveway on Greensboro Drive and submit the same to FCDOT and VDOT for review. If, however, the Applicant opts not to use the surface parking lot for commuter parking, it may, in its discretion, install parking controls to prevent access to the surface parking lot by commuters.

URBAN DESIGN, LANDSCAPING AND STREETScape

11. Architecture. The Residential Buildings shall be designed of high-quality architecture and building materials that are typically used on the exterior of similar Class A Luxury residential buildings, as conceptually depicted on the CDP. Design details such as building materials, architectural massing and fenestration, and specific features designed to activate the streetscapes are provided with the concurrent FDP. However, architectural plans, elevations, illustrations, materials and heights may be adjusted or modified subsequent to CDP/ FDP approval as a result of final architectural and engineering design without requiring CDPA, FDPA, PCA or other zoning approval, provided the quality of design remains in substantial conformance with that shown on the CDP and FDP and set forth in these Proffers, as determined by the Zoning Administrator.
12. Bird-Friendly Design. At the time of site plan submission for the first Residential Building, the Applicant shall prepare and submit to OCR an initial study addressing whether bird-friendly design strategies may be employed to reduce bird injury and death due to in-flight collisions with the Residential Buildings. The strategies to be studied should make the Residential Buildings visible to birds in flight and reduce reflections that distract or confuse birds through the use of appropriate glazing treatments or architectural elements, such as using color, texture, opacity, patterns, louvers, screens, interior window treatments, or ultraviolet materials that are visible to birds. A narrative summarizing the results of that study and which strategies, if any, will be implemented shall be provided at the time of building permit issuance.
13. Build-To Lines. A Build-To Line for the Residential Buildings has been established on the CDP/FDP to create an urban, pedestrian-oriented environment. In general, the building facades of the Residential Buildings are intended to be configured in such a way as to provide a continuous street wall along this line, but modifications to either side of the Build-To Line shall be permitted, provided such modifications are in general conformance with the CDP/FDP.

14. Building Heights. Building heights shall not exceed the maximums nor be reduced below the minimums identified on the CDP/FDP, as measured from the average grade. Final building heights for the Residential Buildings shall be determined at the time of site plan approval, and may be less than the maximum heights shown on the CDP/FDP, provided that the Residential Buildings retain a compatible urban form to that shown on the CDP/FDP and that the average roofline of the Residential Buildings are not less than minimum heights shown in the CDP/FDP tabulations. Maximum building heights for the Residential Buildings shall include penthouses and all rooftop structures. For the Existing Office Buildings, structures that are excluded from the maximum height regulations as set forth in Sect. 2-506 of the Zoning Ordinance shall not exceed thirty (30) feet above the roof levels of the top floors. All building penthouses and rooftop structures shall be integrated into the architecture of the buildings.
15. Rooftop Telecommunications Equipment and Mechanical Units. Telecommunications equipment, mechanical units and all appurtenant facilities may be placed on the rooftop of one or both of either the Existing Office Buildings and/or Residential Buildings. Any such new facilities on the Residential Buildings must comply with the applicable requirements of the Zoning Ordinance and be screened and/or set back sufficiently from the perimeter of the roof and penthouse such that they are generally not visible from the surrounding streets at street level when viewed at a reasonable distance from the property line of the Property. Screening measures may, without limitation, (i) include screening with architectural features and/or landscaping compatible with the building façade architecture, (ii) include the facilities as part of the architecture of the buildings, (iii) utilize compatible colors, and/or (iv) employ telecommunication screening material and flush-mounted antennas. Telecommunications equipment on the rooftops of the Residential Buildings also may be architecturally integrated onto the façades of the building where necessary to ensure on-street and/or open space coverage. Rooftop amenities such as amenity terraces or facilities and landscaping may also screen rooftop telecommunications equipment and mechanical units on the Residential Buildings.
16. Green Building. In order to promote energy conservation and green building techniques, the Applicant shall select one of the following programs to be implemented and will inform the Environment and Development Review Branch of DPZ which program the Applicant has chosen as part of the site plan submission for the first Residential Building.
 - A. National Green Building Standard (“NGBS”). If the Applicant selects the NGBS, then the Applicant shall seek certification of each unit in the Residential Buildings in accordance with the 2012 NGBS rating system using the Energy Star Qualified Homes path for energy performance, as demonstrated through documentation submitted to DPWES and DPZ from a home energy rater certified through the National Association of Home Builders Research Center that demonstrates each unit in the Residential Buildings has attained Bronze level certification prior to the issuance of the RUP for each such unit.
 - B. EarthCraft. If the Applicant selects EarthCraft, then the Applicant shall provide documentation to DPWES and DPZ that the Residential Buildings have been

awarded certification in accordance with the EarthCraft House Program prior to the issuance of the first RUP for each Residential Building.

C. Leadership in Energy and Environmental Design (“LEED”).

- i. If the Applicant selects LEED, then the Applicant shall include a U.S. Green Building Council (“USGBC”) LEED-accredited professional, who is a professional engineer or licensed architect, as a member of its design team. The LEED-accredited professional shall work with the design team to incorporate design elements under the current version, at the time of such owner's registration, of the LEED New Construction (“LEED-NC”) rating system into the Residential Buildings. At the time of site plan submission, the Applicant shall provide documentation to the Environmental Review Branch demonstrating compliance with the commitment to engage such a professional. The Applicant will include, as part of the site plan submission and building permit plan submission for each Residential Building, a list of specific credits within the most current version, at the time of such owner's registration, of the LEED-NC rating system that the Applicant anticipates attaining for such Residential Building. The LEED-accredited professional will provide certification statements at both the time of site plan review and the time of building permit plan review, confirming that the items on the list will meet at least the minimum number of credits necessary to attain LEED certification for each Residential Building. In addition, prior to site plan approval, the Applicant will designate the Chief of the Environmental Review Branch as a team member in the USGBC's LEED online system. This team member will have privileges to review the project status and monitor the progress of all documents submitted by the project team, but will not be assigned responsibility for any LEED credits and will not be provided with the authority to modify any documentation or paperwork. Prior to building permit plan approval for each Residential Building, the Applicant will submit documentation to the Environmental Review Branch demonstrating that the subject Residential Building is anticipated to attain a sufficient number of design-related credits that, along with the anticipated construction-related credits, will be sufficient to attain LEED Silver certification under the LEED-NC program. Prior to release of the bond for the subject Residential Building, the Applicant shall provide documentation to the Environmental Review Branch demonstrating the status of attainment of LEED certification or a higher level certification from the USGBC for the subject Residential Building. If the Applicant is unable to provide the preliminary review of the design-related credit documentation prior to building permit plan approval, but it does anticipate receiving the documentation prior to the attainment of LEED certification, the Applicant may, prior to the issuance of the building permit, post an escrow identical to the one described in Proffer 16(C)(ii) below. This escrow will be released upon the submission of documentation to the Environmental Review Branch from the USGBC

demonstrating that the Residential Building is anticipated to attain a sufficient number of design-related credits that, along with the anticipated construction-related credits, shall be sufficient to attain LEED Silver certification.

- ii. Alternative Green Building Escrow. As an alternative to the actions outlined in Proffer 16(C)(i) above, or if the USGBC's review of design-related credits indicates that the subject Residential Building is not anticipated to attain a sufficient number of design-related credits to support attainment of LEED Silver certification, the Applicant shall post, for that Residential Building, a "Green Building Escrow" in the form of cash or a letter of credit in the amount of \$2.00 per gross square foot of GFA for that Residential Building. This Green Building Escrow will be in addition to, and separate from, other bond or escrow requirements and shall be released upon demonstration of attainment of LEED certification, or a higher level of certification, by the USGBC under the current version of the LEED-NC or other rating system at the time of such owner's registration. The provision to the Environmental Review Branch of documentation from the USGBC that the subject Residential Building has attained such LEED certification will be sufficient to satisfy this commitment. The Green Building Escrow shall be released in accordance with the following: 1) if the Applicant provides to the Environmental Review Branch, within three years of the issuance of the first RUP for the subject Residential Building, documentation demonstrating that LEED certification for that Residential Building has been attained, the entirety of the Green Building Escrow shall be released to the Applicant, 2) if the Applicant provides to the Environmental Review Branch, within three years of the issuance of the first RUP for the subject Residential Building, documentation demonstrating that LEED certification for that Residential Building has not been attained but that the subject Residential Building has been determined by the USGBC to fall within three points of attainment of LEED certification, 50% of the Green Building Escrow shall be released to the Applicant; the other 50% shall be released to Fairfax County and will be posted to a fund within the County budget supporting the implementation of County environmental initiatives, and 3) if the Applicant fails to provide to the Environmental Review Branch, within three years of the issuance of the first RUP for the subject Residential Building, documentation demonstrating the attainment of LEED certification or demonstrating that the subject Residential Building has fallen short of LEED certification by three points or less, the entirety of the Green Building Escrow for that Residential Building shall be released to Fairfax County and will be posted to a fund within the County budget supporting the implementation of County environmental initiatives. If the Applicant provides documentation from the USGBC demonstrating, to the satisfaction of Environmental Review Branch, that USGBC completion of the review of the LEED certification application has been delayed through no fault of the Applicant, the Applicant's contractors or subcontractors,

the proffered time frame may be extended as determined appropriate by the Zoning Administrator, and no release of escrowed funds shall be made to the Applicant or to the County during this extended time frame.

17. Sustainable Energy Practices. To further promote efficient, renewable and sustainable energy practices, prior to issuance of the first initial RUP for the first Residential Building, the Applicant shall provide:
 - A. A minimum of one (1) electric vehicle recharging station that serves two (2) parking spaces for electric cars in the Residential Parking Structure, and space and infrastructure to accommodate additional electric vehicle-ready parking spaces in the Residential Parking Structure; and,
 - B. A minimum of one (1) electric vehicle recharging station that serves two (2) parking spaces for electric cars in each of the Existing Parking Structures. For purposes of this proffer, "electric vehicle-ready" means the provision of space, conduit banks, conduits and access points allowing for the easy installation of vehicle charging stations in the future, and does not include the installation of transformers, switches, wiring or charging stations.
18. Landscape Plan. The CDP/FDP includes a conceptual Landscape Plan for the Property. As part of the first site plan submission for the Proposed Development, the Applicant shall submit to the Urban Forest Management Division of the Department of Public Works and Environmental Services ("UFMD") for review and approval a more detailed landscape plan that is in substantial conformance with the quantity and quality of plantings and landscaping materials shown on the FDP and any FDPAs. The detailed landscape plan shall include, among other things, irrigation information, design details for tree wells and other similar planting areas on structures and along streets. These details shall include the composition of planting materials, methods for providing suspended pavement over tree root zones to prevent soil compaction and methods of ensuring the viability of plantings and structures. Adjustments to the type and location of plantings shall be permitted to avoid conflicts with utilities and other site engineering and design considerations, provided that in the event of a conflict with the future utility locations identified on the Conceptual Utility Plan described in Proffer 4, the Applicant shall first attempt to relocate the new utilities before adjusting the landscaping.
19. Streetscape. The Applicant shall install streetscapes throughout the Property as conceptually illustrated on the CDP/FDP.
 - A. International Drive.
 - i. Retaining Wall Project.
 - a. Prior to issuance of the first initial RUP for the first Residential Building or such later date as may be determined by the Zoning Administrator, the Applicant shall construct the frontage improvements along International Drive, as shown on the CDP/FDP. As part of such improvements, the Applicant shall diligently pursue removal of the retaining wall located along the

Property's frontage on International Drive, and shall construct the same in accordance with the design recommendations provided in the approved Geotechnical Analysis, described below ("Retaining Wall Project").

- b. Prior to approval of the site plan for the Retaining Wall Project, the Applicant shall submit to DPWES (and DPWES may, in turn, seek input from the Fairfax County Geotechnical Review Board) for review and approval a geotechnical analysis that evaluates the structural stability of the existing Parking Structures (the "Geotechnical Analysis").

- ii. Pedestrian Connections. Prior to issuance of the first initial RUP for the first Residential Building, the Applicant shall:

- a. Improve the existing pedestrian connection from the corner of the intersection of International Drive and Greensboro Drive to the upper parking lot associated with the Existing Office Building located at 8180 Greensboro Drive ("Pedestrian Connection 1"), as more particularly shown on the CDP/FDP; and
- b. Construct a new connection from International Drive to the Existing Office Building located at 8180 Greensboro Drive ("Pedestrian Connection 2"), as more particularly shown on the CDP/FDP.

- B. Greensboro Drive. Prior to issuance of the first initial RUP for the first Residential Building, the Applicant shall construct the frontage improvements along Greensboro Drive, as shown on the CDP/FDP ("Greensboro Drive Frontage Improvements"). As part of such improvements, the Applicant shall:

- i. Relocate and reinstall all or a part of the existing traffic signal at the intersection of Greensboro Drive and Pinnacle Drive, as shown on the CDP/FDP ("Traffic Signal Pole Relocation"). Any modifications to this signal shall include those pedestrian enhancements as may be required by VDOT; and,
- ii. Relocate and/or place underground, as applicable, the east switch cabinet located along the Property's frontage on Greensboro Drive and adjacent to the retaining wall (the "East Switch Relocation"); however, if the Applicant discovers based on more detailed analysis following approval of this Rezoning, that there are utilities and/or fiber optics in the public right-of-way that need to be relocated in order to complete the East Switch Relocation, the Applicant shall request the applicable utility and/or fiber optic provider to relocate such utilities and/or fiber optics at the provider's cost. If the applicable utility and/or fiber optic provider refuses to relocate

the impacted utilities and/or fiber optics at its cost, or the Applicant discovers that there are utilities and/or fiber optics within the Property boundaries that need to be relocated in order to complete the East Switch Relocation, its obligation to complete the East Switch Relocation shall be null and void. Instead, the Applicant shall be permitted to leave the switch cabinet in its existing location and shall work with FCDOT, VDOT, DPZ and OCR to find a mutually-agreeable alternative alignment for the pedestrian sidewalk in that location. Notwithstanding the above, the west and north switch cabinets labeled on the CDP/FDP as “West Switch Cabinet” and “North Switch Cabinet” respectively, may remain in their existing locations.

- C. Streetscape Elements. Streetscape elements shall generally include a landscape amenity panel located immediately behind the face of curb, a pedestrian sidewalk adjacent to the landscape amenity panel and a building zone between the pedestrian sidewalk and the face of the building designed to allow access to the building and/or additional landscaping, outdoor display, outdoor dining, and similar uses adjacent to the Residential Buildings, provided that outdoor display and outdoor dining areas are located within the building zone and shall not encroach upon the pedestrian sidewalk areas. Streetscape elements may be adjusted at the time of site plan approval to accommodate final architectural designs, parallel street parking (as shown on the CDP/FDP), sight distance concerns and utilities, as well as to facilitate elements such as outdoor seating for a cafe, entry doors and facilities/structures in the Proposed Development, provided the quality of the streetscape is consistent with that shown on the CDP/FDP. Tree planting sites are set forth conceptually on the CDP/FDP and may be adjusted at the time of site plan approval, subject to UFMD and DPZ approval, in consultation with OCR.
- D. Streetscape Activation. So as to accommodate the Public Facility described in Proffer 43 herein as well as any potential retail uses designed to activate the streetscape, Residential Building B shall generally be constructed with its ground floor having a minimum ceiling height of 18 feet.
- E. Alternative Planting Width Details. Street tree species and planting sites are depicted on the CDP/FDP but may be revised at the time of site plan approval. Where minimum planting widths of eight (8) feet cannot be provided, alternative measures either as identified in the “Tysons Urban Design Guidelines” (endorsed by the Board on January 25, 2012) (the “Tysons Urban Design Guidelines”) or as approved by the UFMD, shall be used to satisfy the following specifications for all planting sites:
 - 1) A minimum of four (4) feet open surface width and 16 square feet of open surface area for Category III and Category IV trees (as defined in Table 12.17 of the PFM), with the tree located in the center of such open area.

- 2) A minimum rooting area of eight (8) feet wide (may be achieved with techniques to provide un-compacted soil below hardscape areas within the Pedestrian Realm) (as defined in these Proffers), with no barrier to root growth within four (4) feet of the base of the tree. Where minimum planting widths of eight (8) feet cannot be provided, structural cell technology or other measures acceptable to the UFMD shall be provided.
- 3) Soil volume for Category III and Category IV trees (as defined in Table 12.17 of the PFM) shall be seven hundred (700) cubic feet per tree for single trees, but may be reduced to a minimum of four hundred (400) cubic feet where paving above root zones is necessary to accommodate pedestrian traffic or where utility locations preclude greater soil volume. For two (2) trees planted in a contiguous planting area, a total soil volume of at least 600 cubic feet per tree shall be provided. For three (3) or more trees planted in a contiguous area, the soil volume shall equal at least five hundred (500) cubic feet per tree. A contiguous area shall be any area that provides root access and soil conditions favorable for root growth throughout the entire area. Minimum soil volumes of seven hundred (700) cubic feet will be achieved in areas of lower pedestrian volume and where pavement is not required over tree rooting zones.
- 4) Soil specifications in planting sites shall be provided in the planting notes to be included in all site plans filed subsequent to the approval of this Rezoning.
- 5) Tree zones shall be installed with a fully automatic drip irrigation system.
- 6) Tree grates shall only be required if necessary to maintain certain sidewalk dimensions.

F. Non-Invasive Plant Materials. Invasive species, as defined in the PFM, shall not be used within the streetscape and landscaped open space areas.

G. Utility Locations. The Applicant has prepared and submitted with the CDP/FDP a Conceptual Utility Plan that identifies the locations of known utilities and proposes future utilities, including but not limited to water, sanitary sewer, storm sewer, electricity, gas and cable television lines. To the extent feasible and in accordance with the Transportation Design Standards for the Tysons Corner Urban Center (the "Transportation Design Standards"), the Applicant has placed such utilities in locations that minimize conflicts with the landscaped open space areas and streetscape elements. If, however, it is determined during site plan review that street tree locations conflict with utility locations, the Applicant shall first make efforts to reconcile the conflict by adjusting the locations of the future utilities. If VDOT, FCDOT or the applicable utility company does not approve such new locations or if the Applicant determines that it is not cost-effective to relocate them, the Applicant may adjust the type of plantings or remove and replace such tree(s) at an alternative location coordinated with the UFMD and

without the need for a PCA, CDPA and/or FDPA. Maintenance access points to SWM Facilities and utility vaults beneath the streetscape shall be located outside the clear pedestrian walkway zone of the streetscape, where feasible. If the utility vaults must be located in the walkway zone, they shall be designed as a lift out panel with the same paving materials as the walkway (subject to the Americans with Disabilities Act (“ADA”) requirements), be flush with the walkway, and meet ADA accessibility requirements.

- H. Fire Marshal. The Applicant has coordinated the layout depicted on the CDP/FDP with the Fire Marshal. If, however, it is determined during site plan review that street tree locations conflict with subsequent comments from the Fire Marshal, the Applicant shall first make efforts to gain the Fire Marshal’s approval of such trees by making minor adjustments to their locations or by removing their lower branches. If the Fire Marshal does not approve such adjustments or other streetscape elements, the Applicant shall be permitted to relocate or delete those conflicting trees and/or make other streetscape adjustments in consultation with UFMD and DPZ and without the need for a PCA/CDPA and/or FDPA.
- I. Sight Distance. If it is determined during site plan review that street tree locations conflict with the sight distance requirements set forth in the Transportation Design Standards, the Applicant shall first make efforts to gain VDOT’s and/or FCDOT’s approval of such trees by making minor adjustments to their locations or by removing their lower branches. If VDOT and/or FCDOT do not approve such adjustments, the Applicant shall be permitted to relocate or delete those conflicting trees in consultation with UFMD and DPZ and without the need for a PCA/CDPA and/or FDPA.
- J. Streetscape Furnishings and Materials. High-quality and unified streetscape materials shall be provided within the public realm in substantial conformance with the CDP/FDP and may include, but shall not be limited to, decorative concrete, unit pavers, seat walls, tree space edging, lighting, traffic signal poles, benches, trash receptacles, and other hardscape elements. The “Streetscape Furnishing and Materials Plan” provided with the CDP/FDP includes general product information and approximate locations of furnishings and materials to be located in the streetscape between the building face and the curb, and in other public realm open spaces. Although minor variations may occur, materials, furnishings, and lighting along public streets shall generally be compatible with any streetscape design approved by the Tysons Partnership.
- K. Lighting. All new streetscape lighting shall be energy efficient. On-site, outdoor and parking garage lighting shall be in conformance with the Outdoor Lighting Standards of Section 14-900 of the Zoning Ordinance, as may be amended. New street lights may either be selected from those listed in the Tysons Urban Design Guidelines, or as approved by DPWES, DPZ and OCR and the same or similar street lights shall be used consistently throughout the Proposed Development. All parking lot and Residential Building-mounted security lighting shall utilize full

cut-off fixtures. Recessed lighting for the Residential Buildings shall be directionally shielded to mitigate the impact on the adjacent residences. Information regarding the lighting of the pedestrian realm, including photometrics for non-standard lighting, shall be provided with the site plan.

- L. Construction Lighting. During construction, the Applicant shall attempt to reduce glare from OSHA, VOSHA, VUSBA and local ordinance required superstructure lighting to the extent possible without violating aforementioned laws, regulations or policies.
- M. Signage and Way-finding. Signage for the Property shall be provided in accordance with the requirements of Article 12 of the Zoning Ordinance, with a Comprehensive Sign Plan (“CSP”) or as part of a larger CSP for the Tysons area. If the Applicant elects to join a larger CSP for the Tysons area, way-finding signage and elements shall be considered to be in substantial conformance with this CDP/FDP. The placement of traffic control signage on public streets shall be coordinated with, and subject to, VDOT review and approval. Way-finding signage and elements shall be coordinated with the Tysons Partnership to facilitate a consistent way-finding and signage system throughout the applicable planning district, but shall not be subject to approval by the Tysons Partnership. Way-finding signage shall include bicycle way-finding and provide direction to locations of prominent attractions, parks, cultural arts destinations, and other public amenities.
- N. Maintenance of the Pedestrian Realm. The “Pedestrian Realm” shall be defined as all areas between the face of curb and the building façade, including the landscape amenity panel and pedestrian sidewalk, both of which will be dedicated to the County as further described in Proffer 19(P) below, and the building zone, which shall remain privately-owned (the landscape amenity panel, pedestrian sidewalk and building zone, collectively the “Pedestrian Realm”). The Applicant shall maintain all elements in the Pedestrian Realm in good repair and in compliance with the ADA, and replace, in kind, as needed, all Pedestrian Realm elements located within or abutting public street right-of-way.
- O. Maintenance Agreement. The Applicant shall enter into an appropriate agreement, in a form approved by the Office of the County Attorney, with the County (or other applicable public entity) to permit it to maintain the publicly-owned landscape amenity panel and pedestrian sidewalk, as described in Proffer 19(N) above. The Applicant shall not be required to repair or restore any elements of the Pedestrian Realm within publicly-owned areas that are damaged by public employees, contractors, or permittees that are not acting under its direct authority. The Applicant may enter into an alternative maintenance arrangement, such as pursuant to a Business Improvement District, without needing a PCA. Maintenance commitments within the Pedestrian Realm shall include but are not limited to:

- i. All plantings including trees, shrubs, perennials, and annuals;
- ii. All associated irrigation elements;
- iii. All hard surfaces, including but not limited to paving and retaining walls;
- iv. All streetscape furnishings including benches and bike racks;
- v. All lighting poles, brackets and fixtures;
- vi. All special drainage features, such as Low Impact Development facilities;
- vii. Snow removal;
- viii. Trash recycling and litter removal;
- ix. Leaf removal;
- x. Any sign posts, traffic signal poles, pedestrian signal poles, mast arms, signal heads and control boxes that are not VDOT standard devices; and
- xi. All urban park amenities in the development including horticultural care, maintenance of all water features, irrigation, lighting, furnishings, paving, recreation courts and features, and art.

P. Right-of-Way Dedication. The landscape amenity panel and pedestrian sidewalk as described in Proffer 19(N) herein and shown on the CDP/FDP shall be dedicated in fee simple to the County (or equivalent government body or agency) concurrent with dedication of the adjacent roadways as specified in Proffer 23, subject to the following:

- i. If, at the time of site plan, it is determined that stormwater management facilities, electric vaults or other similar facilities proposed to be located beneath the landscape amenity panel and/or pedestrian sidewalk will prevent VDOT and/or Fairfax County from accepting the landscape amenity panel and/or pedestrian sidewalk within the right-of-way, the Applicant shall provide dedication measuring 18 inches behind the face of curb and shall reserve for potential future dedication the landscape amenity panel and pedestrian sidewalk areas. A temporary public access easement in a form acceptable to the County Attorney shall be recorded over the reserved landscape amenity panel and/or pedestrian sidewalk areas until such time as such areas are dedicated. This reservation area shall include easements that allow for the installation of signage necessary for safety and operation of the street as well as parking regulation equipment by VDOT and/or the County.

- ii. Should it be determined following final street acceptance inspection that the landscape amenity panel and/or pedestrian sidewalk areas continue to be unacceptable to VDOT and/or Fairfax County for inclusion in the right-of-way, the reservation of potential future dedication of the landscape amenity panel and/or pedestrian sidewalk areas shall be released and the Applicant shall grant a public sidewalk and utility easement, as applicable, in a form acceptable to the Office of the County Attorney. This easement shall allow for the installation of signage necessary for safety and operation of the street as well as parking regulation equipment by VDOT and/or the County.
- iii. If, at the time of site plan it is unclear whether stormwater management facilities, electric vaults or other similar facilities proposed to be located beneath the landscape amenity panel/sidewalk will be acceptable to VDOT and/or Fairfax County, the Applicant shall provide dedication measuring 18 inches behind the face of curb at the time of site plan approval and shall reserve for potential future dedication the landscape amenity panel and/or pedestrian sidewalk areas. A temporary public access easement in a form acceptable to the County Attorney shall be recorded over the reserved landscape amenity panel and/or pedestrian sidewalk areas until such time as such areas are dedicated. The reservation area shall include easements that allow for the installation of signage necessary for safety and operation of the street as well as parking regulation equipment by VDOT and/or the County.
- iv. Should it be determined following final street acceptance inspection that the landscape amenity panel and/or pedestrian sidewalk areas are not acceptable to VDOT and/or Fairfax County to be included in the right-of-way, the reservation of potential future dedication of the landscape amenity panel and/or pedestrian sidewalk areas shall be released and the Applicant shall grant a public sidewalk and utility easement, as applicable, in a form acceptable to the Office of the County Attorney. This easement shall allow for the installation of signage necessary for safety and operation of the street as well as parking regulation equipment by VDOT and/or the County.
- v. All right-of-way dedications shall be subject to advanced density credit as specified in Proffer 51 herein.

TRANSPORTATION

20. Grid of Streets. Subject to FCDOT approval and, where necessary, VDOT approval, the Applicant shall construct the following road improvements prior to issuance of the first initial RUP for the first Residential Building (for purposes of this Proffer, "construct" shall mean completed and open for public use but not necessarily accepted by VDOT for maintenance purposes):

- A. Results Road (Public Collector Street). The Applicant shall construct Results Road from Greensboro Drive to Summit Street, including all streetscape elements located on the Property, as shown on the CDP/FDP.
 - B. Summit Street (Public Local Street). The Applicant shall construct Summit Street, including all streetscape elements located on the Property, as shown on the CDP/FDP.
 - C. Park Place (Private Service Street). The Applicant shall construct Park Place, from Results Road to Summit Street, including all streetscape elements located on the Property, as shown on the CDP/FDP.
21. Extension of Results Road by Others. Results Road may be extended by others in one of the following ways:
- A. Option A. At such time as the property identified on the 2013 Fairfax County Tax Map 29-3 ((15)) 11A2 and located at 8250 Greensboro Drive (currently, the Tysons Sport & Health building) becomes the subject of a zoning application and is redeveloped, the Applicant shall provide the rights-of-way and ancillary and reasonable easements necessary to complete its construction as generally shown on the CDP/FDP, provided (i) FCDOT has demanded the same; (ii) access to/from the then-existing uses on the Property are maintained at all times; and (iii) such improvements are coordinated with the Applicant prior to approval of the site plan that includes such improvements by others (“Option A”).
 - B. Option B. At such time as the property identified on the 2013 Fairfax County Tax Map as 29-3 ((15)) 11B3 and located at 1676 International Drive (currently, the Tysons Center II building) becomes the subject of a zoning application and is redeveloped, the Applicant shall provide all rights-of-way and ancillary and reasonable easements necessary to complete its construction as shown on the CDP/FDP, provided (i) FCDOT has demanded the same; (ii) access to/from the then-existing uses on the Property are maintained at all times; and (iii) such improvements are coordinated with the Applicant prior to approval of the site plan that includes such improvements by others (“Option B”).
 - C. Option C. At such time as both properties to the north (identified on the 2013 Fairfax County Tax Map as 29-3 ((15)) 11A2 and 11B3, the Tysons Sport and Health and the Tysons Center II buildings, respectively; hereinafter, the “Adjacent Properties”) become the subject of zoning applications and are redeveloped, the Applicant shall provide all rights-of-way and ancillary and reasonable easements necessary to complete its construction as shown on the CDP/FDP, provided (i) FCDOT has demanded the same; (ii) access to/from the then-existing uses on the Property are maintained at all times; and (iii) such improvements are coordinated with the Applicant prior to approval of the site plan that includes such improvements by others (“Option C”).

D. Option D. If the Existing Office Buildings, which are anticipated to remain in their existing conditions with the Proposed Development, are redeveloped pursuant to a future zoning application and neither Option A nor Option B nor Option C has been constructed by others, the Applicant shall extend Results Road, as shown on the CDP/FDP (“Option D”). In such event, the Applicant’s obligations with regard to Proffer 21(B) and (C) herein, are deemed null and void and of no further force or effect.

22. Contributions for the Extension of Results Road and Summit Street

A. Contribution for the Extension of Results Road. Prior to issuance of the first initial RUP for the first Residential Building, the Applicant shall escrow \$665,000.00 (Six Hundred and Sixty-Five Thousand Dollars) with the County for the extension of Results Road by others. However, in the event the Applicant constructs Option D as described in Proffer 21(D) above, it shall be permitted to use the funds escrowed pursuant to this Proffer 22 for that improvement.

B. Contribution for the Extension of Summit Street. Prior to issuance of the first initial RUP for the second Residential Building, the Applicant shall escrow \$58,000.00 (Fifty-Eight Thousand Dollars) with the County for the extension of Summit Street by others from the northern curb line of Results Road to the Property line.

23. VDOT Acceptance and Dedication. With the exception of Park Place, which shall be constructed as a private street, all streets within the limits of the Property will be designed and constructed as public streets in accordance with the *Transportation Design Standards for the Tysons Corner Urban Center* dated September 13, 2011, as may be amended, and the following:

A. Results Road. Results Road shall be constructed to public street standards but will be privately maintained until any of Options A, B or C (as defined in Proffer 21(A), (B) and (C), above) has been constructed by others; or, the Applicant has constructed Option D (as defined in Proffer 21(D) above); or, Results Road has been extended to International Drive, and VDOT has accepted it into the State system for maintenance. At such time as the foregoing conditions are met and unless the following has previously occurred, the Applicant shall, without the need for a PCA, CDPA or FDPA,

- i. Remove the eleven (11) head-in surface parking spaces along the north side of the existing 8200 Greensboro Drive Existing Office Building;
- ii. Convert the twenty-three (23) surface parking spaces on top of the Existing Parking Structure to landscaping; and,
- iii. Dedicate and convey upon demand by Fairfax County the necessary right-of-way and/or ancillary easements necessary so that the owners of the Adjacent Properties can complete Results Road and pursue acceptance by

VDOT of Results Road together with all related improvements, to be maintained by VDOT.

- B. Summit Street. Summit Street shall be constructed to public street standards but remain private until (i) construction of the Proposed Development has been completed; (ii) the Adjacent Properties redevelop and include a roadway that could be connected to Summit Street; and (iii) the Board of Supervisors approves a petition to add Summit Street to the secondary system of state highways. At such time as the foregoing conditions are met and without the need for a PCA, CDPA or FDPA, the Applicant shall:
- i. Construct the nine (9) parallel surface parking spaces along Summit Street; and,
 - ii. Dedicate and convey upon demand by Fairfax County the necessary right-of-way and/or ancillary easements necessary so that the owners of the Adjacent Properties can complete Summit Street, which may include construction and/or modification to Summit Street as necessary to meet VDOT standards, and pursue acceptance by VDOT of Summit Street, together with all related improvements, to be maintained by VDOT.
24. Tysons Grid Fund Contributions. At the time of issuance of the first RUP for each new Residential Building, a contribution shall be made to the Tysons Grid Fund in the amount of \$1,000 per residential unit in accordance with the Board of Supervisors' policy adopted on January 8, 2013. In addition, the Applicant shall contribute \$6.44 for each new square foot of retail uses in the Residential Buildings; it shall provide 25% of that contribution prior to site plan approval for the Residential Buildings, and the remaining 75% prior to issuance of a building permit for the first new retail use. Credits shall be allowed against such contributions for the costs of the qualifying off-site intersection improvements. These contributions shall not apply to the Public Facility described in Proffer 43 below, or to the Existing Office Buildings. These payments may be made earlier than required pursuant to this Paragraph.
25. Tysons-wide Transportation Contributions for Table 7 Improvements. The Applicant shall contribute to the Tysons Area-Wide Fund the sum of \$1,000 for each new residential unit constructed in the Proposed Development and \$5.63 per square foot for all new retail uses in the Residential Buildings in accordance with the Board of Supervisor's policy adopted on January 8, 2013. The contribution associated with each building shall be paid in a lump sum, based on the actual gross floor area of non-residential space and/or the actual number of residential units in the building, with payment to occur prior to the issuance of the first RUP or Non-RUP for each building. These contributions shall not apply to the Public Facility described in Proffer 43 below, or to the Existing Office Buildings. These payments may be made earlier than required pursuant to this paragraph.
26. Bus Shelter. If requested and approved by WMATA and/or FCDOT at the time of site plan and prior to issuance of the first initial RUP for the first Residential Building, the

Applicant shall relocate the existing bus stop and construct a new bus shelter (but not a bus pull out) at the new location generally depicted on the CDP/FDP (the "Bus Shelter"), at a cost of no more than One and One-Fifteenth percent (1.15%) of the cost of an average bus shelter based on the County's Unit Pricing Schedule in effect at the time the Bus Shelter is installed.

27. Congestion Management Plan. The Applicant shall engage a qualified professional to prepare and submit in connection with the VDOT permit for construction of the Proposed Development on the Property, a construction congestion management plan for use during construction of the two Residential Buildings, as appropriate, so as to provide safe and efficient pedestrian and vehicle circulation at all times on the Property and on the public roadways adjoining the Property (the "Congestion Management Plan"). The Congestion Management Plan shall identify anticipated construction entrances, construction staging areas and construction vehicle routes. The Applicant shall coordinate its construction activities, including construction material deliveries, lane closures, and/or other related activities with FCDOT and VDOT, and procedures for such coordination shall be included in the Congestion Management Plan.
28. Notification Letter. At the time of filing the first site plan for the Residential Buildings, the Applicant shall send a notification letter to the Director of FCDOT. The purpose of this letter is to facilitate coordination with DPWES to ensure site plans are consistent with the Transportation Design Standards for Tysons Corner.

BICYCLES

29. Bicycle Parking. Bicycle racks, bike lockers, and/or bike storage areas shall be generally provided as shown the CDP/FDP, with the specific amounts and locations determined at site plan. Bicycle racks shall be inverted U-style racks or other design approved by FCDOT. The total number of bike parking/storage spaces provided will be generally consistent with the Fairfax County Policy and Guidelines for Bicycle Parking for the Residential Buildings, and shall be generally located as reflected on the CDP/FDP. Signage shall be posted on the exterior side of the Residential Buildings near the entrances to the bike parking/storage space to indicate their presence.
30. Bicycle Lanes. Concurrent with construction of the streetscape improvements identified in Proffer 19(A) and (B) and if approved by VDOT, the Applicant shall provide pavement and striping for on-road bicycle lanes along the Property's frontage on Greensboro Drive, as shown on the CDP/FDP. Such lanes shall typically be four (4) to six (6) feet in width as shown on the CDP/FDP with the final dimension determined at the time of site plan approval.

PARKING

31. Parking. Upon completion of the Residential Buildings, parking for the Proposed Development shall be provided as shown on the CDP/FDP and in accordance with Section 6-509 and Article 11 of the Zoning Ordinance, as qualified by the following:

- A. The exact number of parking spaces for the Existing Office Buildings and the Residential Buildings shall be determined at the time of site plan approval in accordance with the parking requirements for the PTC district, based on the final number and type of residential units provided, including any new or proposed uses in the Existing Office Buildings. However, in no event shall the Applicant be permitted to establish more than One Hundred (100) surface parking spaces on the Property to serve the Existing Office Buildings and Residential Buildings, exclusive of the nine (9) surface parking spaces along Summit Street (which will ultimately be a public street), five (5) surface parking spaces along Park Place (which serve the pocket parks described in Proffer 39 herein), and thirty-four (34) parking spaces located along the future extension of Results Road to International Drive, as shown on the CDP/FDP (the “Results Road Spaces”).
 - B. Upon (a) the extension of Results Road to International Drive (in accordance with Options B, C or D as described in Proffer 21 herein, and shown on the CDP/FDP); or (b) July 1, 2025, whichever is first, the Applicant shall remove the Results Road Spaces and, after submission and receipt of approval from UFMD of a landscaping plan showing the same, convert them to landscaping in accordance with the CDP/FDP.
 - C. As described in Proffer 36(D) below, the Applicant shall annually submit to FCDOT a parking summary that demonstrates compliance with the parking commitments described herein and shown on the CDP/FDP.
 - D. The Applicant may adjust the allocation of parking spaces between the Existing Office Buildings and the Residential Buildings as shown on the CDP/FDP with an FDPA, and without the need for a PCA or CDPA, provided that the overall parking rates for the Proposed Development meet the rates provided in Section 6-509 and Article 11 of the Zoning Ordinance as required under this Proffer 31.
 - E. Following approval of this Rezoning, the Applicant shall manage its future leases for the Existing Office Buildings in a manner that permits it to achieve, on a cumulative basis, the parking requirements set forth in this Proffer.
- 32. Unbundled Parking for Residential Uses. All for-sale residential units shall be offered exclusive of parking (i.e. at a separate cost). All leases for residential units shall be offered exclusive of parking (i.e. at a separate cost).
 - 33. Parking for Non-Residential Uses. The Applicant may, but shall not be required to, charge for parking on the Property on a per-space basis, at rates that the Applicant determines to be market-competitive, and valet parking shall be permitted.

TRANSPORTATION DEMAND MANAGEMENT

- 34. Tyson's Transportation Management Association. The Applicant shall contribute towards the establishment of a future transportation management association (the “TMA”), which may be established for the Tysons Corner Urban Center and to which all other Tysons property owners will be required to contribute.

- A. The Applicant shall make a one-time contribution for the establishment of this future TMA based on a participation rate of \$0.05 per gross square foot of new residential uses to be constructed on the Property, which sum shall be payable to the Tysons Partnership Transportation Council.
 - B. Fifty percent (50%) of the total contribution to the TMA shall be paid upon site plan approval of the first new Residential Building to be constructed on the Property. The remaining fifty percent (50%) of the total contribution shall be paid prior to issuance of the first initial RUP for the first Residential Building. In any event the full contribution shall be paid no later than ten (10) years from the date of this Rezoning approval.
 - C. If subsequent to the approval of this Rezoning, FCDOT approves the TMA as the administrator of TDM programs for the Tysons Corner Urban Center, then the Applicant may, in its sole discretion, join or otherwise become associated with such entity and transfer some functions of this TDM Program to the TMA.
 - D. If the TMA has not been established within three (3) years after the approval of this Rezoning, this Proffer shall be null and void with no further effect on the Property. Further, any funds contributed by the Applicant to the TMA shall then be returned.
35. Transportation Demand Management Plan for the Residential Buildings. The proffered elements of the TDM Program as set forth below are more fully described in the *Greensboro Park Place TDM Plan* prepared by Wells + Associates, Inc. dated October 22, 2012, as may be amended (the "TDM Plan"). It is the intent of this Proffer that the TDM Plan will adapt over time to respond to the changing transportation related circumstances of the Property, the surrounding community and the region, as well as to technological and/or other improvements, all with the objective of meeting the trip reduction goals as set forth in these Proffers. Accordingly, modifications, revisions, and supplements to the TDM Plan as coordinated with FCDOT can be made without the need for a PCA provided that the TDM Plan continues to reflect the proffered elements of the TDM Program as set forth below.
- A. Definitions. For purposes of this Proffer, "Stabilization" shall be deemed to occur one-year following issuance of the final initial RUP for the second new Residential Building to be constructed on the Property. "Pre-stabilization" shall be deemed to occur any time prior to Stabilization.
 - B. Trip Reduction Objective. The objective of this TDM Program shall be to reduce the vehicle trips generated by residents of the Property (i.e., not including trips from existing office and new retail uses), during weekday peak hours associated with the adjacent streets as more fully described in the TDM Plan, by meeting the percentage vehicle trip reductions established by the Comprehensive Plan as set forth below. These trip reduction percentages shall be multiplied by the total number of residential vehicle trips that would be expected to be generated by the uses developed on the Property as determined by the application of the Institute of

Traffic Engineers, 8th Edition, Trip Generation rates and/or equations (the “ITE Trip Generation”), and the number of trips determined by the product of such equation shall be referred to herein as the “Maximum Trips After Reduction.” For purposes of this calculation, the maximum number of dwelling units proposed to be constructed in each new Residential Building on the Property, as determined at the time of site plan approval for each new building, shall be applied to the calculation described in the preceding sentence. The target reductions shall be as follows:

<u>Development Levels</u>	<u>Percentage Vehicle Trip Reduction</u>
Up to 65 million GSF	35%
65 million GSF	40%
84 million GSF	45%
90 million GSF	48%
96 million GSF	50%
105 million GSF	53%
113 million GSF	55%

The trip reduction goals outlined above are predicated on the achievement of specific development levels within the Tysons Corner Urban Center as anticipated in the Comprehensive Plan. Prior to undertaking trip measurements, the TPM shall, in consultation and coordination with the County, provide a summary of the then existing development levels in Tysons Corner (based on RUPs and Non-RUPS issued) in order to determine the appropriate vehicle trip reduction goal.

If through an amendment to the Comprehensive Plan, the Board of Supervisors should subsequently adopt a goal for trip reductions that is lower than that committed to in this Proffer, then the provisions of this Proffer shall be adjusted accordingly without requiring a PCA.

C. TDM Program Components. The TDM Program shall include, but not necessarily be limited to, the following components, each of which is more fully described in the TDM Plan:

- i. TDM Program Management;
- ii. TDM Program Branding;
- iii. Transportation Program Web Site;
- iv. Promotion of Real Time Transit Information;
- v. Site Specific Transportation Access Guide;
- vi. Bicycle Accommodations; and,

vii. Vehicle Parking Management.

D. Process of Implementation. The TDM Program shall be implemented as follows, provided that modifications, revisions, and supplements to the implementation process as set forth herein and as coordinated with FCDOT can be made without requiring a PCA.

- i. TDM Program Manager. The Applicant shall appoint and continuously employ, or cause to be employed, a TDM Program Manager (TPM) for Greensboro Park Place. The TPM shall be appointed by the Applicant no later than sixty (60) days after the issuance of the first building permit (core and shell) for the first new Residential Building on the Property. The TPM duties may be part of other duties associated with the appointee. The Applicant shall notify FCDOT and the District Supervisor in writing within 10 days of the appointment of the TPM. Thereafter the Applicant shall do the same within ten (10) days of any change in such appointment.
- ii. TDM Annual Report and Budget. If not already effectuated for the then-current calendar year, the TPM shall prepare and submit to FCDOT an Annual Report and Budget no later than 180 days after issuance of the first building permit (core and shell) for the first new Residential Building on the Property. If an Annual Report has already been submitted for the then-current calendar year, the TPM shall revise the Annual Report with the following year's submission to incorporate any new construction on the Property. The Annual Report shall include, at a minimum:
 - a) Details as to the start-up components of the TDM plan that will be put into action effective with the first new residential building on the Property;
 - b) The budget needed to implement the TDM plan (the "TDM Budget") for the coming calendar year;
 - c) A summary of the then-existing development levels in the Tysons Corner Urban Center;
 - d) A determination of the applicable Maximum Trips After Reduction for the Property;
 - e) Provision of the specific details associated with the monitoring and reporting requirements of the TDM program in accordance with the TDM plan;
 - f) Submission of the results of any Person Surveys and Vehicular Traffic Counts conducted on the Property; and,

- g) Submission of an annual report to FCDOT by February 1st of each year beginning with the first calendar year following the submission of the first Annual Report and Budget.

The Annual Report shall be reviewed by FCDOT. If FCDOT has not responded with any comments within sixty (60) days after submission, then the Annual Report shall be deemed accepted and the TDM plan shall be implemented. If FCDOT responds with comments on the Annual Report, then the TPM will meet with FCDOT staff within fifteen (15) days of receipt of the County's comments. Thereafter but in any event, no later than thirty (30) days after the meeting, the TPM shall submit such revisions to the Annual Report and/or Budget as discussed and agreed to with FCDOT and begin implementation of the approved program and fund the approved TDM Budget. Thereafter the TPM, in conjunction with each Annual Report summarizing the results of the TDM Program to be submitted no later than February 1st (the "Annual Report"), shall update the TDM plan and Budget for each succeeding calendar year, modify or enhance program elements and establish a budget to cover the costs of implementation of the TDM plan for such year. The expected annual amounts of the TDM Budget are further described in the TDM Plan.

- iii. TDM Account. The Applicant, through the TPM, shall establish a separate interest bearing account with a bank or other financial institution qualified to do business in Virginia (the "TDM Account") within 30 days after approval of the Annual Report and Budget. All interest earned on the principal shall remain in the TDM Account and shall be used by the TPM for TDM purposes. The TDM Account shall be funded by the Applicant, through the TPM. The TDM Account shall not be eliminated as a line item in any governing budget associated with the Property and that funds in the TDM Account shall not be utilized for purposes other than to fund TDM strategies/programs and/or specific infrastructure needs, as may be approved in consultation with FCDOT.

Funding of the TDM Account shall be in accordance with the budget for the TDM Program elements to be implemented in a given year. In no event shall the baseline TDM Budget exceed \$63,500 (this amount shall be adjusted annually from the date of Rezoning approval for the Subject Property (the "Base Year")) and shall be adjusted on each anniversary thereafter of the Base Year as permitted by VA. Code Ann. Section 15.2-2303.3. The TPM shall provide written documentation to FCDOT demonstrating the establishment of the TDM Account within ten (10) days of its establishment. The TDM Account shall be replenished annually thereafter following the establishment of each year's TDM Budget. The TDM Account shall be managed by the TPM.

- iv. TDM Remedy Fund. At the same time the TPM creates and funds the

TDM Account, the TPM shall establish a separate interest bearing account (referred to as the "TDM Remedy Fund") with a bank or other financial institution qualified to do business in Virginia. Funding of the TDM Remedy Fund shall be made one time, and prior to the issuance of the first initial RUP for each Residential Building at a rate of \$0.30 per gross square foot of new residential uses on the Property. Funding shall be provided by the building owners prior to the issuance of the first initial RUP for each new Residential Building. This amount shall be adjusted annually from the date of Rezoning approval of the Property (the "Base Year") and shall be adjusted on each anniversary thereafter of the Base Year as permitted by VA. Code Ann. Section 15.2-2303.3. Funds from the TDM Remedy Fund shall be drawn upon only for purposes of immediate need for TDM funding and may be drawn on prior to any TDM Budget adjustments as may be required.

- v. TDM Incentive Fund. The "TDM Incentive Fund" is an account into which the Applicant, through the TPM, shall deposit contributions to fund a multi-modal incentive program for initial purchasers/lessees within Greensboro Park Place. Such contributions shall be made one time, and prior to the issuance of the first initial RUP for each Residential Building at a rate of \$0.02 per gross square foot of new residential uses on the Property.
- vi. TDM Penalty Fund. The "TDM Penalty Fund" is an account into which the Applicant shall, through the TPM, deposit penalty payments as may be required to be paid pursuant to this Proffer for non-attainment of trip reduction goals. The County may withdraw funds from the TDM Penalty Fund for the implementation of additional TDM Program elements/incentives and/or congestion management associated with the Property. To secure the Applicant's obligations to make payments into the TDM Penalty Fund, the Applicant shall provide the County with a letter of credit or a cash escrow as further described below.

Prior to the issuance of the first RUP for each new Residential Building on the Property, the Applicant shall:

- a) Establish the TDM Penalty Fund, if not previously established by the TPM, and/or
- b) Deliver to the County a clean, irrevocable letter of credit issued by a banking institution approved by the County or escrow cash in an interest-bearing account with an escrow agent acceptable to DPWES to secure the Applicant's obligations to make payments into the TDM Penalty Fund (the "Letter(s) of Credit or Cash Escrow(s)"). The Letter(s) of Credit or Cash Escrow(s) shall be issued in an amount equal to \$0.05 for each square foot of new residential GFA shown on the approved site plan for each new

residential building on the Property. Until the Letter(s) of Credit or Cash Escrow(s) has been posted, the figures in the preceding sentence shall be adjusted annually from the first day of the calendar month following the date on which the first RUP for the first new Residential Building on the Property has been issued as permitted by VA. Code Ann. Section 15.2-2303.3. using the date of rezoning approval as the base year. Once the Letter(s) of Credit or Cash Escrow(s) has been posted, there shall be no further adjustments or increases in the amount thereof. The Letter(s) of Credit or Cash Escrow(s) shall name the County as the beneficiary and shall permit partial draws or a full draw. The foregoing stated amount(s) of the Letter(s) of Credit or Cash Escrow(s) shall be reduced by the sum of any and all previous draws under the Letter(s) of Credit or Cash Escrow(s) and payments by the Applicant (or the TPM) into the TDM Penalty Fund as provided below.

- vii. Monitoring. The TPM shall verify that the proffered trip reduction goals are being met through the completion of Person Surveys, Vehicular Traffic Counts of residential uses and/or other such methods as may be reviewed and approved by FCDOT. The results of such Person Surveys and Vehicular Traffic Counts shall be provided to FCDOT as part of the Annual Reporting process. Person Surveys and Vehicular Traffic Counts shall be conducted for the Property beginning one year following issuance of the final initial RUP for the first new Residential Building to be constructed on the Property. Thereafter, Person Surveys shall be conducted every three years and Vehicular Traffic Counts shall be collected annually until the results of three (3) consecutive annual traffic counts conducted upon Stabilization show that the applicable trip reduction goals for the Property have been met. At such time and notwithstanding Paragraph F below, Person Surveys and Vehicular Traffic Counts shall thereafter be provided every five (5) years. Notwithstanding the above, FCDOT may suspend such Person Surveys and/or Vehicular Traffic Counts if conditions warrant.

E. Remedies and Penalties.

- i. Pre-Stabilization. If the Maximum Trips After Reduction for the Property is exceeded as evidenced by the Vehicular Traffic Counts outlined above, then the TPM shall meet and coordinate with FCDOT to address, develop and implement such remedial measures as may be identified in the TDM Plan and Annual Report.
 - a) Such remedial measures shall be funded by the Remedy Fund, as may be necessary, and based on the expenditure program that follows:

<u>Maximum Trips Exceeded</u>	<u>Expenditure</u>
Up to 1%	No Remedy needed
1.1% to 3%	1% of Remedy Fund
3.1% to 6%	2% of Remedy Fund

6.1% to 10%
Over 10%

4% of Remedy Fund
8% of Remedy Fund

- b) If the results of the traffic counts conducted during Pre-Stabilization show that the trip reduction goals have been met site-wide for three (3) consecutive years in accordance with the goals outlined on the table below, then a portion of the Remedy Fund as outlined in the same table below shall be released back to the Applicant through the TPM. Any funds remaining in the Remedy Fund after such release will be carried over to the next consecutive three (3) year period.

Up to 65,000,000 Square Feet of GFA in Tysons	
Meet or Exceed Trip Goal for 3 Years By:	Cumulative % Remedy Fund Returned
0.0% - 4.9%	30%
5% - 10%	50%
10.1% - 15%	65%
15.1% - 18%	80%
18.1% - 20 %	90%
>20%	100%

65-84,000,000 Square Feet of GFA in Tysons	
Meet or Exceed Trip Goal for 3 Years By:	Cumulative % Remedy Fund Returned
0.0% - 4.9%	50%
5% - 10%	65%
10.1% - 13%	80%
13.1% - 15%	90%
>15%	100%

84-90,000,000 Square Feet of GFA in Tysons	
Meet or Exceed Trip Goal for 3 Years By:	Cumulative % Remedy Fund Returned
0.0% - 4.9%	65%
5% - 8%	80%
8.1% - 10%	90%
>10%	100%

90-96,000,000 Square Feet of GFA in Tysons	
Meet or Exceed Trip Goal for 3 Years By:	Cumulative % Remedy Fund Returned
0.0% - 4.9%	80%
5% - 8%	90%
>8%	100%

96-113,000,000 Square Feet of GFA in Tysons	
Meet or Exceed Trip Goal for 3 Years By:	Cumulative % Remedy Fund Returned
0.0% - 4.9%	90%
>5%	100%

113,000,000+ Square Feet of GFA in Tysons	
Meet or Exceed Trip Goal for 3 Years By:	Cumulative % Remedy Fund Returned
>0%	100%

- c) There is no requirement to replenish the TDM Remedy Fund at any time. Any cash left in the Remedy Fund will be released to the TPM for final distribution to the Applicant once three consecutive annual Traffic Counts conducted upon Stabilization show that the trip reduction goals have been met.

ii. Upon Stabilization

- a) If the TDM Program monitoring, as evidenced by the Vehicular Traffic Counts outlined above, reveals that the Maximum Trips After Reduction for the Property is exceeded, then the TPM shall meet and coordinate with FCDOT to address, develop and implement such remedial measures as may be identified in the TDM Plan and Annual Report and funded by the Remedy Fund (if available) as may be necessary, commensurate with the extent of deviation from the Maximum Trips After Reduction goal as set forth in accordance with the expenditure schedule outlined above.
- b) If despite the implementation of remedial efforts, the applicable Maximum Trips After Reduction (based on the existing development levels in the Tysons Corner Urban Center as described in this Proffer 34) are still exceeded after three consecutive years, then, in addition to addressing

further remedial measures as set forth in this Proffer, the TPM shall be assessed a penalty according to the following:

Exceeded Trip Goals	Penalty
Less than 1%	No Penalty Due
1% to 3%	5% of Penalty Due
3.1% to 6%	10% of Penalty Fund
6.1% to 10%	15% of Penalty Fund
Over 10%	20% of Penalty Fund

If the results of the traffic counts conducted upon Stabilization show that the trip reduction goals have been met for three (3) consecutive years in accordance with the goals outlined on the table above, then any remaining Remedy and/or Penalty Funds shall be released back to the Applicant through the TPM.

- c) The Applicant through the TPM shall make the payments required by this Proffer into the TDM Penalty Fund and the County shall be authorized to withdraw the amounts on deposit in the TDM Penalty Fund. If the Applicant fails to make the required penalty payment to the TDM Penalty Fund within thirty (30) days after written demand, the County shall have the ability to withdraw the penalty amount directly from the Letter(s) of Credit or Cash Escrow(s).
 - d) The maximum amount of penalties associated with the Property, and the maximum amount the Applicant shall ever be required to pay pursuant to the penalty provisions of this Proffer, including prior to and after Stabilization, shall not in the aggregate exceed the amount of the Letter(s) of Credit or Cash Escrow(s) determined and computed pursuant to the provisions of the above Proffer. There is no requirement to replenish the TDM Penalty Fund at any time. The Letter(s) of Credit and/or any cash left in the Cash Escrow(s) shall be released to the Applicant once three (3) consecutive counts conducted upon Stabilization show that the Maximum Trips After Reduction have not been exceeded.
- F. Additional Trip Counts. If an Annual Report indicates that a change has occurred that is significant enough to reasonably call into question whether the applicable vehicle trip reduction goals are continuing to be met, then FCDOT may require the TPM to conduct additional Trip Counts (pursuant to the methodology set forth in the TDM Plan) within 90 days to determine whether in fact such objectives are being met. If any such Vehicular Traffic Counts demonstrate that the applicable vehicle trip reduction goals are not being met, then the TPM shall meet with FCDOT to review the TDM strategies in place and to develop modifications to the TDM Plan to address the surplus of trips.

- G. Review of Trip Reduction Goals. At any time and concurrent with remedial actions and/or the payment of penalties as outlined in this Proffer, the TPM may request that FCDOT review the vehicle trip reduction goals established for the Property and set a revised lower goal for the Property consistent with the results of such Person Surveys and Vehicular Traffic Counts provided for by this Proffer. In the event a revised lower goal is established for the Property, the Maximum Trips After Reduction shall be revised accordingly for the subsequent review period without the need for a PCA.
- H. Continuing Implementation. The Applicant and/or its assigns through the TPM shall bear sole responsibility for continuing implementation of the TDM Program and compliance with this Proffer. The TPM shall continue to administer the TDM Program in the ordinary course in accordance with this Proffer including submission of Annual Reports.
- I. Notice to Owners/Tenants. All residential owners and/or tenants of the Property shall be advised of the TDM Program set forth in this Proffer. For owners, the then-current owner shall advise all successor owners and/or developers of their funding obligations pursuant to the requirements of this Proffer prior to purchase and the requirements of the TDM Program, including the annual contribution to the TDM Program (as provided herein), shall be included in all initial and subsequent purchase documents.
- J. Enforcement. If the TPM fails to timely submit a report to FCDOT as required by this Proffer, the TPM will have sixty (60) days within which to cure such violation. If after such sixty (60) day period the TPM has not submitted the delinquent report, then the Applicant shall be subject to a penalty of \$100 per day not to exceed \$36,500 for any one incident. Such penalty shall be payable to Fairfax County to be used for transit, transportation, or congestion management improvements within the vicinity of the Property.
- K. Intelligent Transportation Systems. To optimize safe and efficient travel in Tysons, the Applicant shall incorporate and maintain a system that provides pertinent traffic and transit information that allows residents to make informed travel decisions. This information shall be provided at initial occupancy of each Residential Building. The delivery of this information shall be made convenient for residents, such as via computer, cell phone, monitors, or similar technology. The Applicant shall work with FCDOT and/or the Tysons Partnership to identify sources and facilitate electronic transmittal of data. Furthermore, the Applicant shall participate in efforts to implement any future dynamic traffic management program for the Tysons area.
36. Transportation Demand Management Plan for the Existing Office Buildings. The Applicant shall encourage the employees of the Existing Office Buildings to utilize transit, carpools, walking, biking and other non-SOV modes of transportation to travel

to and from the Property through voluntary participation in the TDM Plan, as supplemented by this Proffer (the "Office TDM Program"). The goal of the Office TDM Program is to reduce by Twenty Percent (20%) the number of vehicle trips that would be expected from office employees working on the Property through promotion and use of non-SOV modes of transportation. Notwithstanding the below, the existing office uses shall not be subject to monitoring nor will remedies or penalties be assessed against the Existing Office Buildings.

A. Components of the Office TDM Program. The Office TDM Program shall include, at a minimum, the components listed below, provided that such components may be subsequently amended from time to time by mutual agreement between the Applicant and FCDOT.

- i. Office Transportation Program Manager. A transportation program manager for the Existing Office Buildings shall be appointed by the Office Building owner(s) ("Office TPM") within Ninety (90) days of the appointment of the TPM for the Residential Buildings. The Office TPM shall coordinate with the TPM for Residential Buildings at least once per year. The Office TPM duties may be part of other duties associated with the appointee. The Applicant shall notify FCDOT and the District Supervisor in writing within 10 days of the initial appointment of the Office TPM. Thereafter the Applicant shall do the same within ten (10) days of any change in such appointment.
- ii. Employee/Tenant Meetings. Within Thirty (30) days of its appointment and at least annually each year thereafter, the Office TPM shall meet with representatives of the tenants of the Existing Office Buildings to review the available transit options, adequacy of bus schedules (including hours of service), changes in transit service and other relevant transit-related topics. The Office TPM shall invite Fairfax County and/or WMATA representatives to these meetings to speak to the group(s) about these and related subjects. After the first three such meetings, the frequency of the same may be reduced to one meeting every three (3) years. Based on these meetings, the Office TPM shall work with Fairfax County and/or WMATA to consider changes to the relevant services, such as changes to bus schedules, if such changes would provide better service to such tenants and their employees.
- iii. Transit Incentives. Utilizing the Office TDM Incentive Fund (described in Proffer 36(B) below), the TPM shall provide financial incentives to office employees to utilize transit. These incentives may include programs such as contests with fare card rewards, mall gift certificates and similar programs (for example, an award could be offered to the transit riding employee of the month/year or the tenant with the highest percentage of employees utilizing non-SOV transport to commute to and from the Property).

- iv. Regional TDM Incentive Programs. The Office TPM shall make information available to the office employees about programs that promote alternative commuting options. This shall include information on vanpools, carpools, guaranteed ride home and other programs offered by organizations in the Washington, D.C. Metropolitan Area. Such information shall be provided in all leasing packages.
 - v. Ridesharing. The Office TPM shall assist office employees in forming carpools or vanpools and in providing convenient parking spaces to carpools or vanpools.
 - vi. Bike Accommodations. The Office TPM shall assist office employees in locating the bicycle accommodations in the Existing Parking Structures and across the Proposed Development (bike storage, lockers and showers), as well as promoting their availability to employees who bicycle to work.
 - vii. Onsite Amenities. The Office TPM shall promote the availability of on-site personal services so that employees who arrive on-site without an automobile can run errands.
- B. Office TDM Budget. At the time the first TDM Budget is approved and funded per Proffer 35(D)(ii) above, the Applicant shall establish an Office TDM Budget for use exclusively by the Applicant for the office employees (the "Office TDM Budget"). The Applicant shall contribute Three Thousand, Five Hundred Dollars (\$3,500.00) per year to the Office TDM Budget for the provision of transit incentives, such as gift certificate awards, fare card contests and/or give-aways, transit fairs specific to the office employees and for similar inducements or incentive activities. Should any tenant of the Existing Office Buildings elect to financially contribute to the Office TDM Program, such contributions shall be utilized in addition to the Applicant's annual contributions (that is, the Applicant's annual contributions shall not be reduced or offset in any way).
- C. Office TDM Program Participation Outreach. The Office TPM shall endeavor in good faith to encourage participation by the office tenants in the Office TDM Program, including the encouragement of a financial participation by such tenants through the direct offering of transit benefit programs and transit incentives to their employees. Actions taken by the Office TPM and Property management in furtherance of this objective may include dissemination of information to, and solicitation of participation from, the tenants' on-site management and executives or officers at their headquarters offices, at appropriate intervals.
- D. Supplement to the Annual Report. The TPM shall submit, with its Annual Report, as described in Proffer 35(D)(ii) above, a parking summary that demonstrates compliance with the parking commitments described in Proffer 31 above and shown on the CDP/FDP.

AFFORDABLE/WORKFORCE HOUSING

37. Affordable Dwelling Units. If required by the provisions of Part 8 of Article 2 of the Zoning Ordinance, the Applicant shall provide Affordable Dwelling Units (“ADUs”), pursuant to such provisions unless modified by the ADU Advisory Board.
38. Workforce Dwelling Units. In addition to any required ADUs, the Applicant shall provide Workforce Dwelling Units (WDUs) on the Property in accordance with the Board of Supervisors’ Tysons Corner Urban Center Workforce Dwelling Unit Administrative Policy Guidelines dated June 22, 2010 (“WDU Policy”). The total number of ADUs, if any, and WDUs provided shall equal twenty percent (20%) of the total residential units constructed on the Property. If ADUs are provided on the Property, both the ADUs and the ADU bonus units shall be deducted from the total number of dwelling units on which the WDU calculation is based.
- A. WDU Specifications. The WDUs generated by each Residential Building shall be provided within such Building, however, the Applicant reserves the right to consolidate the WDUs into Residential Building A, and thereby increase the number of WDUs in Residential Building A beyond twenty percent (20%) with a corresponding decrease in the number of WDUs in Residential Building B. To the extent the Residential Buildings are phased and are constructed separately, a minimum of twenty percent (20%) of the total residential dwelling units in the first Residential Building shall be ADUs or WDUs. The WDUs in each building shall have a bedroom mix similar to that provided in the market rate units in such building. Additionally, in the event that parking spaces are guaranteed to be made available for lease to individual market rate dwelling units, at least one (1) parking space shall be made available for lease by each ADU and/or WDU on the Property.
- B. Agreements. Notwithstanding the foregoing, should the Board’s policies related to WDUs in Tysons Corner be amended, the Applicant reserves the right, at its sole discretion, to opt in to the new policies without the need for a PCA and, if the Applicant so opts into any such new policies, the provisions of this Proffer which relate to the new policies of the Board which Applicant has elected to opt into shall no longer be effective. Furthermore, the Applicant reserves the right to enter into a separate binding written agreement with the appropriate Fairfax County agency as to the terms and conditions of the administration of the WDUs following approval of this Application. Such an agreement shall be on terms mutually acceptable to both the Applicant and the County and may occur after the approval of this Rezoning. Neither the Board nor any other County agency shall be obligated to execute such an agreement. If such an agreement is executed by all applicable parties, then the WDUs shall be administered solely in accordance with such an agreement and the provisions of this Proffer as it applies to WDUs shall become null and void. Such an agreement and any modifications shall be recorded in the Fairfax County land records.

PARK AND RECREATIONAL FACILITIES

39. Publicly-Accessible Parks. The Applicant shall provide publicly-accessible, at-grade, open space areas in general conformance with the concepts, locations and minimum acreages depicted on the CDP/FDP and as further described in these Proffers, provided that such areas and the elements described below may be adjusted at the time of site plan to allow for final engineering and design considerations. While public access easements shall be granted for these areas, the Applicant shall retain them in private ownership and reserves the right to reasonably restrict access for limited times and special events, security maintenance and repairs and/or safety purposes. The Proposed Development includes the following five distinct urban park spaces:
- A. Pocket Park I. Prior to issuance of the first initial RUP for the first Residential Building, the Applicant shall provide an approximately 0.6-acre publicly-accessible pocket park behind the Residential Buildings consisting of one large and several small lawn panels, as shown conceptually on the CDP/FDP ("Pocket Park 1"). The large panel is envisioned as an area for unscheduled recreation; the small lawn panels will provide amenities such as additional seating, game tables, a bocce court and/or climbable art for tots. Bocce equipment for the bocce court in Park I, or in any of the other park spaces detailed below, shall be made available upon request at a readily-identifiable and easily-accessible location on the Property, to be coordinated with the Park Authority.
 - B. Pocket Park II. Prior to issuance of the first initial RUP for the Residential Building identified on the CDP/FDP as Residential Building B, the Applicant shall provide an approximately 0.09-acre publicly-accessible urban plaza located on the opposite corner from Pocket Park I and adjacent to the proposed Public Facility described in Proffer 43 herein, as shown conceptually on the CDP/FDP ("Pocket Park II"). This space is envisioned to be used for a variety of purposes, including but not limited to outdoor programming associated with the recreational facility and use by patrons of the ground-floor retail use.
 - C. Pocket Park III. Prior to issuance of the first initial RUP for the first Residential Building, the Applicant shall provide an approximately 0.24-acre publicly-accessible pocket park along Greensboro Drive at Summit Street, as shown conceptually on the CDP/FDP ("Pocket Park III"). This pocket park is designed with a circle motif to carry the character of the street wall along Greensboro Drive into the site. It is envisioned to have a rain garden, wall seating and general open space for casual use.
 - D. Pocket Park IV. Prior to issuance of the first initial RUP for the second Residential Building, the Applicant shall enhance the existing 0.39-acre publicly-accessible pocket park in between the existing 8200 Greensboro Drive Office Building and Pocket Park I, as shown on the CDP/FDP ("Pocket Park IV").

E. Pocket Park V. Prior to issuance of the first initial RUP for the second Residential Building, the Applicant shall enhance the existing 0.37-acre publically-accessible pocket park in between and around the Existing Office Buildings, as shown on the CDP/FDP (“Pocket Park V”), which is currently used as passive recreation space by the office employees, with amenities such as game tables, seating, planters, and/or way-finding. The enhancement of Pocket Park V shall be consistent with the concepts and characteristics of the other publicly-accessible park spaces described in this Proffer 39.

40. Private Amenities and Recreational Facilities for Residents. The Applicant shall provide on-site recreational facilities for the future residents of the Property, as shown on the CDP/FDP. Recreational facilities such as rooftop amenities and pool facilities may be separately designated for the residents of the individual Residential Buildings; or, more common facilities such as a business or fitness center may be shared between the two. These facilities may but shall not be required to be shared between the residents of two Residential Buildings. Pursuant to Section 6-110 of the Zoning Ordinance, the Applicant shall expend a minimum of \$1,700.00 per market-rate and workforce residential unit on such recreational facilities. Prior to final bond release for the Residential Buildings, the balance of any funds not expended on-site, as determined by DPWES, shall be contributed to the FCPA for the provision of recreational facilities serving Tysons Corner.
41. Athletic Field Contribution. In satisfaction of the Comprehensive Plan’s expectations for the provision of athletic fields to support the Proposed Development (which generates the need for approximately eleven percent (11%) of a full-size field), the Applicant shall contribute funds to the Fairfax County Board of Supervisors in accordance with one of the following options, which it may select in its discretion: (a) contribute Nine Hundred and Eleven Thousand Dollars (\$911,000.00) by December 31, 2015 to be utilized for construction of an athletic field at West*Gate Elementary School (“Option 1”); or (b) contribute One Million, One Hundred and Seventy-Eight Thousand Dollars (\$1,178,000.00) to the Fairfax County Board of Supervisors prior to issuance of the first RUP for the first Residential Building for the future construction of an athletic field that will serve the residents of Tysons Corner (“Option 2”). If the Applicant elects Option 1, its contribution of \$911,000.00 shall be fixed in that amount and shall not be subject to escalation pursuant to Proffer 50 below; if, however, the Applicant elects Option 2, its contribution of \$1,178,000.00 shall be subject to escalation as described further in Proffer 50.

NOISE ATTENUATION

42. Noise Attenuation. The Applicant shall reduce the interior DNL to no more 45 dBA for the Residential Buildings. At the time of building plan application for the full shell building permit for each Residential Building, the Applicant shall submit to the Chief of the Environment and Development Review Branch of DPZ (the “E&D Chief”), for approval, and to DPWES, for information only, an acoustical study prepared by a

qualified acoustical consultant (the "Indoor Noise Study") addressing indoor noise levels, including proposed noise attenuation measures and proposed materials to ensure compliance with the interior DNL limit of 45 dBA. The Applicant shall not obtain full-shell building permits until the E&D Chief has approved the applicable Indoor Noise Study, provided that a failure by the E&D Chief to review and respond to the Applicant within 60 days of receipt of the Indoor Noise Study shall be deemed approval of such study. Prior to the issuance of the first RUP for the Residential Buildings, the Applicant shall demonstrate through testing of noise levels that interior noise does not exceed 45 dBA. The Applicant shall notify potential tenants or purchasers of individual residential units with balconies, either in their leases or sale contracts, that exterior noise levels may exceed 65dBA.

PUBLIC FACILITIES

43. Public Facility. The Applicant shall provide a 3,000 square-foot, warm/dark shell space within the ground floor of Residential Building B as generally shown on the CDP/FDP (the "Public Facility Space"). For purposes of this Proffer, "warm/dark shell" space shall mean a structure with a structural steel or concrete frame and masonry and storefront windows or glass curtain wall skin. While the "warm/dark shell" space shall be temporarily heated, it shall not include interior walls, ceilings, electrical systems, plumbing or finishes. The Public Facility Space shall be constructed concurrently with the Residential Buildings and shall be accessible through a separate entrance on Greensboro Drive.
- A. Public Facility Escrow. Prior to issuance of the first building permit for Residential Building B, the Applicant shall post an escrow in the form of cash or a letter of credit in the amount Two Hundred and Twenty-Five Thousand Dollars (\$225,000.00) for the County's fit-out of the Public Facility Space (the "Public Facility Escrow"), which shall be released to the Fairfax County Board of Supervisors upon demand when the County demonstrates that the funds will be used for the fit-out of the Public Facility Space on the Property. In the alternative, if, pursuant to Proffer 43(C) below, the County opts not to use the Public Facility Space, then the Public Facility Escrow shall be released to the Board of Supervisors upon demand when the County demonstrates that the funds will be used for another public facility in Tysons.
- B. Use. Fairfax County and/or its assigns shall use the Public Facility Space for community and/or recreational programming, or for any other public use permitted by-right in the PTC district, except (a) a conference center or retreat house; (b) a congregate living, group residential or shelter facility; or, (c) a treatment or counseling facility. However, if the County elects to use the Public Facility Space for any public use other than community and/or recreational programming, then the Applicant shall be notified of the same and provided with an opportunity to comment before any such alternative use is established.
- C. Opt Out. Notwithstanding the foregoing, the County may opt not to use the Public Facility Space. In that event and upon notice to the Applicant, the Public

Facility Space shall revert back to the Applicant and may be used for retail, service, accessory or any other use permitted by-right in the PTC district, except residential use, without requiring approval of a PCA, CDPA or FDPA, provided such use is in substantial conformance with the CDP/FDP and these Proffers.

D. Time. The Applicant shall promptly notify the Fairfax County Facilities Management Department, Real Estate Branch (“FMD”) that it has submitted a site plan for the Proposed Development, six (6) months after which the FMD shall either (i) opt in to using the Public Facility Space pursuant to Proffer 43(B) herein or (ii) opt out of using the Public Facility Space pursuant to Proffer 43(C) herein, by notifying the Applicant in writing. If FMD opts in to using the Public Facility Space pursuant to Proffer 43(B), then

- i. The County shall be provided with the opportunity to review the building plans to determine compliance with this Proffer 43, and to comment upon (a) the proposed location of the plumbing (the hook-up to which shall be provided by the Applicant as part of its construction of the warm/dark shell, but the plumbing and the restroom(s) for the Public Facility Space shall be provided by the County within the Public Facility Space and as part of its fit-out thereof, unless otherwise agreed to by all parties), and (b) the proposed location of the entrance to the Public Facility Space from Greensboro Drive; and,
- ii. The County shall fit-out the warm/dark shell space and open it to the public within two (2) years of the Applicant’s delivery to FMD of the Public Facility Space.

E. Lease. Prior to issuance of the first initial RUP for Residential Building B, the Applicant as Landlord (“Landlord”) and Fairfax County as tenant (“Tenant”) shall enter into a Lease Agreement for the lease of the Public Facility Space (the “Lease”) at a rate of One Dollar (\$1.00) per month and in a form approved by the County Attorney. The initial term of the Lease shall be for thirty (30) years, with the Tenant having two options to renew thereafter, each for a term of ten (10) years (the “Renewals”). The Renewals shall be automatic unless the Tenant notifies the Landlord in writing at least six (6) months prior to the start of the new term that it is opting not to renew the Lease. The Lease shall include all commercially-reasonable and industry-standard terms, including but not limited to, the following:

- i. The Tenant shall be required to properly maintain the Public Facility Space and any affiliated spaces, but shall not be required to contribute to Common Area Maintenance (“CAM”), Homeowners Association (“HOA”) or Condominium Owners Association (“COA”) fees;
- ii. The Tenant shall be responsible for utilities to and in the Public Facility Space and shall directly contract with the utility companies for the same unless not separately metered, in which case, Tenant shall reimburse

Landlord on a monthly basis;

- iii. The Tenant may not assign nor sublet the Public Facility Space without the prior written approval of the Landlord, provided that if the Tenant elects to program the Public Facility Space through the Fairfax County Park Authority or a sub-agency thereof, which it may but shall not be required to do, such delegation shall constitute neither an assignment nor a sublease; and,
- iv. Prior to the expiration or termination of this Lease, Tenant shall remove from the Public Facility Space all furniture, trade fixtures, equipment, wiring and cabling (unless Landlord directs Tenant otherwise), and all other personal property installed by Tenant or its assignees or subtenants. Tenant shall repair any damage resulting from such removal and shall restore the Public Facility Space to good order and condition, normal wear and tear excepted.

F. Termination. The Lease shall be terminable by the Tenant at any time during the term, in its sole discretion, with six (6) months written notice to the Landlord, at which time the Public Facility Space shall revert back to the Landlord and may be used as described in Proffer 43(C), above.

F. Subordination and Non-Disturbance. In connection with execution of the Lease, Landlord shall use commercially-reasonable efforts to cause any mortgagee holding a deed of trust for Residential Building B to execute a Subordination and Non-Disturbance Agreement ("SNDA") subordinating the Lease for the Public Facility Space to the loan. There shall be no requirement to subordinate the Lease to any loans on the Property other than for Residential Building B.

44. Public School Contribution. Per the Residential Development Criteria Implementation Motion adopted by the Board of Supervisors on September 9, 2002, and revised July, 2006, the Applicant shall contribute \$9,378 per expected student generated by each Residential Building (based on an assumed rate of 0.11 students per multifamily high-rise unit) to the Fairfax County School Board to be utilized for capital construction and capacity enhancements to schools in the Tysons Corner area that serve the development. The contributions shall be made on or before the issuance of the first RUP for each Residential Building, and shall be based on the actual number of residential units in each building. In the event fewer residential units are built than estimated at the time of payment, the overpayment amount shall be returned to the Applicant. If prior to site plan approval for a Residential Building, the County should increase the accepted ratio of students per subject multifamily unit or the amount of the contribution per student, the amount of the contribution shall be increased for that Residential Building to reflect the current ratio and/or contribution. This contribution is not subject to the escalation provisions of Proffer 50. If the County should decrease the ratio or contribution amount, the amount of the contribution shall be decreased to reflect the current ratio and/or contribution.

STORMWATER MANAGEMENT

45. Stormwater Management. The Applicant shall provide the following:

- A. Stormwater Management Measures. Stormwater Management ("SWM") measures for the Property shall be designed to protect receiving waters downstream of Tysons by reducing runoff from impervious surfaces using a progressive approach. This progressive approach shall, to the maximum extent practicable, strive to retain on-site and/or reuse the first one inch of rainfall. Proposed SWM and Best Management Practice ("BMP") facilities shall follow a tiered approach as identified by DPWES, which may include infiltration facilities (where applicable), rainwater harvesting/detention vaults, runoff reducing facilities and other innovative BMPs.
- B. LID Techniques. The Applicant shall make use of certain Low Impact Development ("LID") techniques that will aid in runoff volume reduction and promote reuse throughout the Property. As a part of the LID techniques proposed, the Applicant shall provide intensive and/or extensive green roofs. Other LID techniques may include, but shall not be limited to, tree box filters, pervious hardscapes/streetscapes, and stormwater reuse for landscape irrigation and air conditioning unit makeup water. Additionally, the SWM facilities shall be designed to accommodate not just the pre-developed (existing) peak release rates, but also strive to preserve and/or improve the pre-developed (existing) runoff volumes as contemplated within current LEED requirements, depending on the existing impervious condition. The above-noted SWM Facilities shall be designed (where applicable) to meet the applicable requirements or stormwater management-related credits of the most current version of the USGBC's applicable LEED rating system for each Residential Building or phase of the development based upon the LEED boundary identified with each such building or phase.
- C. Tree Replacement. As shown on the CDP/FDP, the Applicant is requesting a modification of PFM Section 12-0505.6B to allow for trees located above any proposed percolation trench or bio-retention area to count toward the 10-year tree canopy requirement. In the event that any of the said trees may need to be removed for maintenance or repair of those facilities, the Applicant agrees to replace removed trees as determined by the UFMD to sustain the 10-year canopy.
- D. Calculations at FDPA and Site Plan. If there is an FDPA submission and also at the time of site plan submission, the Applicant shall provide calculations showing the proposed volume reductions and illustrating conformance with the proposed volume reductions shown on the approved FDP. The specific SWM facilities shall be determined at the time of site plan, as may be approved by DPWES.

While it is anticipated that compliance with the goal of retaining and/or reusing the first one inch of rainfall will be confirmed at site plan by utilizing the proposed retention credits identified by Fairfax County as part of their stormwater

spreadsheet, the Applicant reserves the right to utilize any combination of LIDs (existing and future) measures to meet this goal, subject to the review and approval of DPWES; and the goal may be met on an individual building basis or based upon the total area of the Property. Similarly, if all other County suggested stormwater alternatives have been attempted, the Applicant reserves the right to over detain the runoff from a one-inch rainfall to a release rate that mimics that of a good forested condition.

It is understood that seasonal variations in reuse water demand will create fluctuations in the draw down period, and as such, the stormwater system will be designed to the extent practicable to not exceed 10 days of storage. If storage time exceeds 10 days, the Applicant shall have the right to discharge excess volumes off site at release rates approved by the Director of DPWES that will mimic release rates from a good forested condition for a significant majority of rainfall events and/or excess volume should be directed to other facilities using a "treatment train" approach, if possible, as approved by the Director of DPWES.

E. The Existing Office Buildings.

- i. Baseline Requirement. In accordance with Proffer 45(D) above, at the time of site plan submission the Applicant shall provide calculations showing the proposed volume reductions for the portion of the Property improved with the Existing Office Buildings. While the specific SWM facilities may be determined at the time of site plan, the proposed volume reductions shall be in conformance with the calculations shown on the approved FDP, which reflect the retention and/or reuse of 0.39-inch of rainfall for the area of the Property depicted on the CDP/FDP as "Drainage Area B."
- ii. Additional Volume Reduction. Notwithstanding the volume reduction calculations shown on the CDP/FDP, at such time as the Applicant would have otherwise re-asphalted the existing Surface Parking Spaces that will remain after completion of the Proposed Development, but in no event later than July 1, 2025, it shall instead file with the County a minor site plan to install approximately 5,250 square feet of porous pavers in the general vicinity of the Existing Office Buildings with a goal of retaining an additional 0.05-inch of rainfall on the Property. While it is anticipated that the Applicant will meet this goal by installing porous pavers as described above, the Applicant may utilize any combination of techniques, including new or advanced technologies that may become available, so long as it captures a total of 0.44-inch of rainfall for the area of the Property depicted on the CDP/FDP as "Drainage Area B."

TREE PRESERVATION

46. Tree Preservation. A tree preservation plan and narrative shall be submitted as part of the first site plan submission for the Proposed Development ("Tree Preservation Plan"). The

Tree Preservation Plan shall (i) be prepared by a Certified Arborist or a Registered Consulting Arborist, and shall be subject to the review and approval of the UFMD; (ii) include a tree inventory that identifies the location, species, critical root zone, size, crown spread and condition analysis percentage rating for all individual trees that are located within 25 feet outside of the limits of clearing (LOC) and 10 feet inside of the LOC, and have trunks 12 inches in diameter and greater (measured at 4 ½ -feet from the base of the trunk or as otherwise allowed in the latest edition of the Guide for Plant Appraisal published by the International Society of Arboriculture), whether on-site or off-site or living or dead; (iii) provide for the preservation of those areas shown for tree preservation, those areas outside of the limits of clearing and grading shown on the CDP and those additional areas in which trees can be preserved as a result of final engineering; (iv) include all items specified in PFM 12-0507 and 12-0509; and (v) include specific tree preservation activities that will maximize the survivability of any tree identified to be preserved, such as crown pruning, root pruning, mulching and fertilization.

- A. Tree Preservation Walk-Through. The services of a certified arborist or Registered Consulting Arborist shall be retained and the limits of clearing and grading shall be marked with a continuous line of flagging prior to a pre-construction walk-through meeting. During the tree preservation pre-construction walk-through meeting, the certified arborist or landscape architect shall walk the limits of clearing and grading with a UFMD representative to determine where adjustments to the clearing limits can be made to increase the area of tree preservation without adversely impacting the buildings and related improvements and/or to increase the survivability of trees at the edge of the limits of clearing and grading, and such adjustment shall be implemented. Trees that are identified as dead or dying may be removed as part of the clearing operation. Any tree that is so designated shall be removed using a chain saw and such removal shall be accomplished in a manner that avoids damage to surrounding trees and associated understory vegetation. If a stump must be removed, this shall be done using a stump-grinding machine in a manner causing as little disturbance as possible to adjacent trees and associated understory vegetation and soil conditions.
- B. Limits of Clearing and Grading. Construction shall conform with the limits of clearing and grading as shown on the CDP, subject to allowances provided in these Proffers and for the installation of utilities and/or public improvements (i.e. roads, streetscapes, entrances, sidewalks, degraded soil and slope conditions), as determined necessary by the Director of DPWES. If it is determined necessary to install utilities in areas beyond the limits of clearing and grading as shown on the CDP, they shall be located in the least disruptive manner necessary as determined by the UFMD. A replanting plan shall be developed and implemented, subject to approval by the UFMD, for any areas beyond the limits of clearing and grading that must be disturbed for such utilities, roads or similar uses, if any such areas are identified at the time of site plan.
- C. Tree Preservation Fencing. All trees shown to be preserved on the tree preservation plan shall be protected by tree protection fencing. Tree protection fencing in the form of four (4) foot high, fourteen (14) gauge welded wire

attached to six (6) foot steel posts driven eighteen (18) inches into the ground and placed no further than ten (10) feet apart or, super silt fence to the extent that required trenching for super silt fence does not sever or wound compression roots which can lead to structural failure and/or uprooting of trees, shall be erected at the limits of clearing and grading as shown on the demolition, and phase I & II erosion and sediment control sheets, as may be modified by the "Root Pruning" Proffer below. Tree protection fencing shall be installed after the tree preservation walk-through meeting but prior to any clearing and grading activities, including the demolition of any existing structures. The installation of all tree protection fencing shall be performed under the supervision of a certified arborist, and accomplished in a manner that does not harm existing vegetation that is to be preserved. Three (3) days prior to the commencement of any clearing, grading or demolition activities, but subsequent to the installation of the tree protection devices, the UFMD shall be notified and given the opportunity to inspect the site to ensure that all tree protection devices have been correctly installed. If it is determined that the fencing has not been installed correctly, no grading or construction activities shall occur until the fencing is installed correctly, as determined by the UFMD.

- D. Root Pruning. Root pruning, as needed to comply with the tree preservation requirements applicable, shall be performed. All treatments shall be clearly identified, labeled, and detailed on the erosion and sediment control sheets of the site plan submission. The details for these treatments shall be reviewed and approved by the UFMD, accomplished in a manner that protects affected and adjacent vegetation to be preserved, and may include, but are not limited to, the following:
- i. Root pruning shall be done with a trencher or vibratory plow to a depth of 18 inches;
 - ii. Root pruning shall take place prior to any clearing and grading, or demolition of structures;
 - iii. Root pruning shall be conducted under the supervision of a certified arborist; and,
 - iv. A UFMD representative shall be informed when all root pruning and tree protection fence installation is completed.
- E. Tree Appraisal. The Applicant shall retain a professional arborist with experience in plant appraisal, to determine the replacement value of all trees 12 inches in diameter or greater located within twenty-five (25) feet of the outer limits of disturbance that are shown to be saved on the Tree Preservation Plan. These trees and their value shall be identified on the Tree Preservation Plan at the time of the first site plan submission for the Proposed Development. The replacement value shall take into consideration the age, size and condition of these trees and shall be determined by the so-called "Trunk Formula

Method” contained in the latest edition of the Guide for Plan Appraisal published by the International Society of Arboriculture, subject to review and approval by UFMD.

At the time of site plan approval, the Applicant shall post a cash bond, a letter of credit payable to the County of Fairfax or a surety bond from a financial institution licensed to do business in Virginia (the “Tree Bonds”), to ensure preservation and/or replacement of the trees for which a tree value has been determined in accordance with the paragraph above (the “Bonded Trees”) that die or are dying due to unauthorized construction activities. The letter of credit, cash deposit or surety bond shall be equal to 50% of the replacement value of the Bonded Trees. At any time prior to final bond release for the Proposed Development, if any Bonded Trees die, are removed, or are determined to be dying by UFMD due to unauthorized construction activities, the Applicant shall replace such trees at its expense. The replacement trees shall be a minimum three (3) inch caliper in size, and equivalent species and/or canopy cover as approved by UFMD. In addition to this replacement obligation, the Applicant shall also make a payment equal to the value of any Bonded Tree that is dead or dying or improperly removed due to unauthorized construction activity. This payment shall be determined based on the Trunk Formula Method and paid to a fund established by the County for furtherance of tree preservation objectives. Upon bond release for the Proposed Development, any amount of monies remaining in the Tree Bonds shall be returned/released to the Applicant.

F. Site Monitoring. The Applicant or its agent shall be present during any clearing or tree/vegetation removal within the tree preservation area to monitor the process and ensure that the activities are conducted in accordance with these Proffers. The services of a certified arborist or Registered Consulting Arborist shall be retained to monitor all construction and demolition work and tree preservation efforts in order to ensure conformance with these Proffers and the UFMD approvals. The monitoring schedule shall be described in the Tree Preservation Plan, and reviewed and approved by the UFMD.

47. Planting Fund Contribution. To promote enhancement of the Fairfax County Tree Canopy through growth of trees on private and public land, the Applicant shall make a one-time, total contribution payable at the time of the first site plan approval in the amount of \$.002 (two tenths of a cent) per square foot of new GFA to the Fairfax County Tree Preservation and Planting Fund (“TPPF”). This donation to the TPPF shall supply tree saplings, volunteer support, and information to landowners with which they can enhance tree canopy on their property. Additionally, this donation shall enable educational activities in Fairfax County Public Schools, should they choose to participate.

MISCELLANEOUS

48. Umbrella Owners’ Association or Equivalent. Prior to issuance of the first RUP for the first Residential Building, the Applicant shall cause the recordation of an umbrella owners association (“UOA”) for the Property, or the equivalent in the form of one or more reciprocal easement and/or joint maintenance and/or joint development agreements, and/or other governance documents as necessary (collectively referred to as “UOA or equivalent”), to provide for various proffer and maintenance obligations, including but

not limited to, implementation of the TDM program, maintenance of the private streets and Pedestrian Realm and publicly-accessible park areas.

49. Metrorail Tax District Buyout for Certain Residential Uses. At least sixty days prior to recording residential condominium documents for any portion of the Property located within the Phase I Dulles Rail Transportation Improvement District (the "Phase I District"), the Applicant shall provide a written notice to the Director of the Real Estate Division of the Fairfax County Department of Tax Administration advising that the Applicant intends to record condominium documents for that portion of the Property. Prior to recording the condominium documents, the Applicant shall pay to Fairfax County a sum equal to the then-present value of Phase I District taxes that will be lost as a result of recording the condominium documents, in accordance with a formula approved by the Fairfax County Board of Supervisors.
50. Escalation in Contribution Amounts. Except for the Public School Contribution discussed in Proffer 44 herein and Option 1 for the Athletic Field Contribution described in Proffer 41 herein, all monetary contributions specified in these Proffers shall be adjusted on a yearly basis from the base month of January 2014 and change effective each January 1 thereafter, as permitted by Section 15.2-2303.3 of the Code of Virginia, as amended.
51. Density Credit. All intensity/density attributable to land areas dedicated and/or conveyed at no cost to the Board or any other public entity pursuant to these Proffers shall be subject to the provisions of Paragraph 4 of Section 2-308 of the Zoning Ordinance and is hereby reserved to the residue of the parcel of land from which it came.
52. Tyson's Partnership. The Applicant and its respective successors and assigns, shall become members of the Tyson's Partnership or its residential equivalent.
53. Condemnation. To the extent off-site right-of-way and/or easements are required to construct any of the improvements described in these Proffers, and the Applicant has not been able to acquire such right-of-way or easements after documented, reasonable efforts to do so, the obligation of the Applicant to construct such improvements for which right-of-way is not available shall be contingent upon the Board acquiring such right-of-way and/or easements through its powers of eminent domain after being requested to do so by the Applicant, in writing. In the event the County elects not to use its power of condemnation to acquire those off-site rights-of-way and/or easements necessary for construction of any of the improvements described in these Proffers, then the Applicant shall escrow the costs of those improvements with the County for future implementation by FCDOT, VDOT and/or others. The Applicant shall not be prevented from obtaining any land use approval (including, without limitation, PCA, CDPA, FDP, FDPA, site plan, subdivision, grading permit, building permit, or RUP permits) for the Proposed Development nor from commencing construction of the Proposed Development, during the pendency of any eminent domain proceedings initiated pursuant to this Proffer, nor any deferral of the County's exercise of eminent domain pursuant to this Proffer, provided that all other prerequisites for obtaining such approvals and commencing such construction provided in these Proffers have been met.

54. Delay. Notwithstanding anything in these Proffers to the contrary, upon demonstration that, despite diligent efforts or due to factors beyond an Applicant's control, proffered improvements such as, but not limited to, the Retaining Wall Project, the required transportation improvements or the publicly-accessible park areas, have been delayed beyond the timeframes specified herein, the Zoning Administrator may agree to a later date for completion of such improvements.

If, while attempting to remove the retaining wall described in Proffer 19(A)(i) herein, the Applicant determines that it is unable to complete the Retaining Wall Project as planned, it shall immediately:

- A. Request DPWES or its designee to inspect the Retaining Wall Project and confirm that completion of the Retaining Wall Project may unacceptably compromise the structural integrity of the Existing Office Buildings or Existing Parking Structures;
 - B. Request the Zoning Administrator grant additional time in which to complete the Retaining Wall Project; and,
 - C. Submit to DPWES, DPZ and OCR for review and approval a plan for addressing the issues identified and a schedule for completing the Retaining Wall Project.
 - D. So long as the Zoning Administrator authorizes a delay and DPWES, DPZ and OCR approve a plan and schedule, completion of the Retaining Wall Project shall not be a precondition to issuance of RUPs for the Residential Buildings provided the plan is completed in accordance with the new schedule described above.
55. Severability. Pursuant to Section 18-204 of the Zoning Ordinance, any portion of the Property may be the subject of a CDPA, FDP, FDPA, PCA, SE and/or SP without joinder and/or consent of the owners of the other portion(s) of the Property, provided that such CDPA, FDP, FDPA, PCA, SE or SP does not materially adversely affect the other portion(s) of the Property.
56. Binding Effect. These Proffers will bind and inure to the benefit of the Applicant and its successors and assigns. If any portion of the Property is sold or otherwise transferred, the associated Proffers become the obligation of the purchaser or other transferee and shall no longer be binding on the seller or other transferor.
57. Counterparts. These Proffers may be executed in one or more counterparts, each of which when so executed and delivered shall be deemed an original, and all of which taken together shall constitute but one and the same instrument.

[SIGNATURES ON FOLLOWING PAGES]

APPLICANT:

Greensboro Park Property Owner LLC

By:  _____

Name: Jeffrey L. Kovach

Title: Managing Director

GREENSBORO PARK PLACE

CONCEPTUAL / FINAL DEVELOPMENT PLAN

RZ / FDP 2012-PR-002

PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA

NOVEMBER 22, 2011
FEBRUARY 03, 2012
SEPTEMBER 11, 2012
JANUARY 15, 2013
APRIL 16, 2013
MAY 20, 2013
SEPTEMBER 3, 2013
NOVEMBER 8, 2013
DECEMBER 16, 2013

JANUARY 16, 2014



TAX MAP/VICINITY MAP
SCALE - 1" = 500'

APPLICANT:
GREENSBORO PARK PROPERTY OWNER, LLC
1655 N. FORT MYER DRIVE, SUITE 650
ARLINGTON, VIRGINIA 22209
KAREN GENTRY (703) 894-5262

ATTORNEY:
COOLEY LLP
1 FREEDOM SQUARE, RESTON TOWN CENTER
11951 FREEDOM DRIVE
RESTON, VIRGINIA 20190-5656
JILL SWITKIN PARKS (703) 456-8000

ARCHITECT:
WDG ARCHITECTURE, PLLC
1025 CONNECTICUT AVE, NW, SUITE 300
WASHINGTON, DC 20036
RICK HAMMANN (202) 857-8300

ENGINEER:
VIKA INCORPORATED
VIKA VIRGINIA, LLC
8180 GREENSBORO DRIVE, SUITE 200
TYSONS CORNER, VIRGINIA 22102
ROBERT COCHRAN L.S. (703) 442-7800

LANDSCAPE ARCHITECT:
LSG LANDSCAPE ARCHITECTURE
1919 GALLOWAY ROAD, SUITE 110
VIENNA, VIRGINIA 22182
MARK LEWIS (703) 821-2045

TRANSPORTATION:
WELLS + ASSOCIATES, INC.
1420 SPRING HILL ROAD, SUITE 610
TYSONS, VIRGINIA 22102
ROBIN ANTONUCCI (703) 917-6620

SHEET INDEX:

- C-1 COVER SHEET
- C-2 NOTES AND TABULATIONS
- C-3 EXISTING CONDITIONS PLAN
- C-4 EXISTING VEGETATION MAP AND CALCULATIONS
- C-5 CONCEPTUAL/FINAL DEVELOPMENT PLAN
- C-6 PRELIMINARY RIGHT OF WAY PLAN
- C-7 ROADWAY PHASING EXHIBITS
- C-8 PRELIMINARY PROPOSED UTILITY LAYOUT
- C-9 PARKING PLAN
- C-10 TRAFFIC CIRCULATION & SIGHT DISTANCE PLAN
- C-11 AUTO-TURN EXHIBIT
- C-12 SHADOW BAND ANALYSIS EXHIBIT
- C-13 EXISTING & PROPOSED STREET SECTIONS
- C-14 EXISTING & PROPOSED STREET SECTIONS
- C-15 AREA AND METRO CONTEXT PLAN - GREENSBORO STATION
- C-15A AREA AND METRO CONTEXT PLAN - TYSONS CORNER STATION
- C-15B DETAILED STREET GRID PLAN
- C-16 LEED/FEM STORM WATER MANAGEMENT COMPUTATIONS
- C-17 STORM WATER MANAGEMENT GOAL, ILL AND SUPPORTING DATA
- C-18 STORM WATER MANAGEMENT DETAILS
- C-19 STORM WATER MANAGEMENT MAP
- C-20 LAND COVER MAP
- C-21 ADEQUATE OUTFALL
- C-22 STORM WATER MANAGEMENT CHECKLIST NARRATIVE
- C-23 AVERAGE GRADE CALCULATION EXHIBIT

- A-01 FLOOR PLANS
- A-02 FLOOR PLANS
- A-03a EXISTING BUILDING SECTIONS
- A-03b PROPOSED BUILDING SECTIONS
- A-04 SHADOW ANALYSIS
- A-05 ELEVATIONS
- A-06 ENLARGED ELEVATIONS
- A-07 PERSPECTIVES
- A-08 PERSPECTIVES
- A-09 PERSPECTIVES
- A-10 PERSPECTIVES
- A-11 PERSPECTIVES
- A-12 PERSPECTIVES
- A-13 PERSPECTIVES
- A-14 PERSPECTIVES
- A-15 MODEL PHOTOS

- L-1 PEDESTRIAN CIRCULATION PLAN
- L-2a LANDSCAPE PLANTING PLAN
- L-2b TREE CANOPY COMPUTATIONS
- L-3 PUBLICLY ACCESSIBLE PARK SPACE CALCULATION
- L-4 ILLUSTRATIVE RENDERED PLAN
- L-5 TYPICAL SITE STREETScape SECTIONS
- L-6a POCKET PARK 1
- L-6b POCKET PARK 2 & 3
- L-6c POCKET PARK 4
- L-6d POCKET PARK 5
- L-6e CONCEPTUAL PEDESTRIAN CONNECTIONS
- L-6f PRIVATE ROOF TERRACE
- L-7a TYPICAL STREET TREE DETAILS
- L-7b TYPICAL BIO-RETENTION TREE DETAILS
- L-8 STREETScape FURNISHINGS & MATERIALS IMAGES

- S-1 RESULTS ROAD, ALTERNATIVE LAYOUT
- S-2 METRO ACCESS EXHIBIT
- S-3 FIRE ACCESS EXHIBIT
- S-4 TYSONS DESIGN STANDARDS - WAIVERS & EXCEPTIONS
- S-5 TYSONS DESIGN STANDARDS - WAIVERS & EXCEPTIONS - KEY MAP



ILLUSTRATIVE DEVELOPMENT PERSPECTIVE

TAX MAP NOS.
29-3 ((15)) PARCEL 12A & 29-4 ((9)) PARCEL 12B



VIVA
 LANDSCAPE ARCHITECTS & SUSTAINABLE DESIGN
 1100 GREENSBORO DRIVE SUITE 200 FAYETTEVILLE, VIRGINIA 22728
 (540) 347-1800 FAX (540) 347-1137
 WWW.VIVA-VA.COM

GREENSBORO PARK PLACE
 PROPOSED DISTRICT
 FAYETTE COUNTY, VIRGINIA

EXISTING VEGETATION MAP & CALCULATIONS

SUBMISSIONS

NO.	DATE	REVISIONS
10	08/26/2014	08/26/2014
9	08/19/2014	08/19/2014
8	08/11/2014	08/11/2014
7	08/05/2014	08/05/2014
6	08/05/2014	08/05/2014
5	08/05/2014	08/05/2014
4	08/05/2014	08/05/2014
3	08/05/2014	08/05/2014
2	08/05/2014	08/05/2014
1	08/05/2014	08/05/2014

DATE: NOVEMBER 2011

DRAWN BY: GML
 CHECKED BY: NPK

SCALE: AS SHOWN

PROJECT/TITLE NO. V20104

SHEET NO. C-4

Table 12.5 Tree Preservation Target Calculations and Statements

Step	Statement	Value	Reference
A. Tree Preservation Target Calculations and Statements			
A	Pre-development area of existing tree canopy (non-existing vegetation map) (SF) *	98,024	See S 12-006.2
B	Percentage of gross site area covered by existing tree canopy *	23%	
C	Percentage of 10-year tree canopy desired for site *	30%	See PFM Table 12.4
D	Percentage of the 10-year tree canopy requirement that should be met through tree preservation *	23%	
E	Proposed percentage of canopy requirement that will be met through tree preservation *	77%	
F	Has the Tree Preservation Target minimum been met?	Yes	Provide Yes or No
G	If No to line A, G, then a request to deviate from the Tree Preservation Target shall be provided on the site plan that states one or more of the justifications listed in S 12-006.2 along with a narrative that provides a site-specific explanation of why No?	N/A	Provide sheet number (see S 12-006.3)
H	Has a 17 square foot canopy * been met in accordance with S 12-006.4	N/A	See S 12-006.4
* DATA SOURCE: 2009-2010 GIS Tree Canopy Data (2014.8.13.10.43.30) (see 12)			

VEGETATION COVER TYPES

- | | |
|-------------------------------------|---|
| Acer palmatum-Japanese Maple | Quercus rubrum-Red Oak |
| Amygdalchier condensata-Shadblow | Picea abies-Norway Spruce |
| Serviceberry | Pinus nigra-Australian Pine |
| Betula nigra-River Birch | Pinus strobus-White Pine |
| Gleditsia tricanthos-Honeylocust | Platanus occidentalis-American Sycamore |
| Ilex opaca-American Holly | Pyrus catteriana-Colleary Pear |
| Cornus kousa-Kousa Dogwood | Quercus alba-White Oak |
| Quercus phellos-Pin Oak | Taxodium distichum-Baldcypress |
| Quercus muehlenbergii-Chinkapin Oak | Tilia cordata-Littleleaf Linden |

EVM NARRATIVE


THE SUBJECT SITE HAS BEEN DEVELOPED WITH TWO EXISTING MID-RISE OFFICE BUILDINGS. 74% OF THE DEVELOPMENT ACCOUNTS FOR THE BUILDING FOOT PRINT AREA AND SURFACE ASPHALT PARKING LOT. THE USE OF REMAINING 26% OF THE SITE AREA IS LANDSCAPED PLANTINGS WITHIN, AND THROUGH THE PARKING AREA AND SURROUNDING THE BUILDINGS. EXISTING VEGETATION IS AT THE PERIPHERY OF THE SITE AND WITHIN INTERACTIVE INTERNAL PEDESTRIAN AREAS. NONE OF THE EXISTING VEGETATION APPEARS TO HAVE BEEN PRESERVED FROM THE TIME THE INITIAL DEVELOPMENT. ALL OF THE VEGETATION IS INSTALLED LANDSCAPE PLANT MATERIAL WHICH IS PRIMARILY MATURE AND SUB-MATURE VEGETATION.

THE GENERAL HEALTH AND CONDITION OF THIS VEGETATION IS GOOD AND GENERALLY SHOWS GOOD VIGOR AND VITALITY. THIS VEGETATION IS MAINTAINED THROUGH THE YEAR.

THIS SITE IS CURRENTLY ZONED C-4 AND SC. WITH THIS APPLICATION THE PROPOSED ZONING WILL BE PTC. THIS SITE IS SPECIFIED FOR SIGNIFICANT REDEVELOPMENT WHERE A SIGNIFICANT PORTION OF THE SURFACE PARKING AND LANDSCAPING WILL BE REMOVED AND REPLACED AND REDEVELOPED FOR RESIDENTIAL USE AND LANDSCAPED PEDESTRIAN PARK PLAZA COMPONENTS. THE TWO EXISTING BUILDINGS ARE TO REMAIN.

TREE PRESERVATION NARRATIVE

THIS EXISTING VEGETATION MAP (EVM) HAS BEEN PREPARED AS REQUIRED PER PFM 12-0505. THE PRIMARY ON-SITE SPECIES HAVE BEEN IDENTIFIED AND THE GENERAL HEALTH OF THAT VEGETATION PROVIDED. THIS EVM ALSO DEPICTS THE EXISTING VEGETATION WHICH IS SPECIFIED TO BE PRESERVED AND TO BE REMOVED. ADDITIONALLY, PORTIONS OF THE CANOPY WHICH IS SHOWN TO BE PRESERVED IS TO BE CREDITED TOWARDS THE OVERALL CANOPY REQUIREMENTS, WHILE ANOTHER PORTION OF THE PRESERVED CANOPY WILL NOT BE FACTORED IN AS PROVIDING PART OF THE FINAL CANOPY REQUIREMENTS. ALSO INDICATED WITH THIS EVM IS THE DESIGN CONCEPT FOR THE DEVICES WHICH WILL PROVIDE PROTECTION TO THOSE TREE SPECIFIED FOR PRESERVATION, CREDIT OR NON-CREDIT. THE TREE PRESERVATION DEVICES SPECIFIED IN THIS PLAN IS TREE PRESERVATION FENCING. HOWEVER, SHOULD IT BE DETERMINED AS THE SITE PLAN IS DESIGNED THAT ADDITIONAL TREE PRESERVATION MEASURES ARE REQUIRED TO ENSURE PROPER EFFECTIVENESS OF THE TREE PRESERVATION MEASURES, THOSE ADDITIONAL PRESERVE DEVICES WILL BE SPECIFIED AS REQUIRED. THESE DEVICES MAY INCLUDE BUT NOT LIMITED TO, ROOT PRUNING, TREE TRUNK BURLAP AND 2x4 BOARD PROTECTION WRAP, TREE PROTECTION MATTING SUCH AS A BLANKET OF SHREDED MULCH AND / OR ALURNAMATS®, TEXIAX TENDRAN 77D/2 (HIGHLOAD)®, OR EQUIVALENT MANUFACTURE MATTING.





LEGEND

- EXISTING TREE CANOPY TO BE PRESERVED WITH CANOPY CREDIT
- EXISTING TREE CANOPY TO BE PRESERVED WITH NO CANOPY CREDIT
- EXISTING TREE TO BE REMOVED
- TREE PRESERVATION FENCE

EVM INDEX	COVER TYPE	SUCCESSIONAL STAGE	AREA	COVER CONDITION	PRIMARY SPECIES	COMMENTS
A	DEVELOPED LAND	N/A	42,818 SF	N/A	N/A	DEVELOPED BUILDING
B	DEVELOPED LAND	N/A	182,127 SF	N/A	N/A	DEVELOPED PARKING AREA
C	LANDSCAPED TREE CANOPY	SUB-CLIMAX	79,020 SF	GOOD	SEE "VEGETATION COVER TYPES" TABLE, THIS SHEET	LANDSCAPE & PEDESTRIAN AREA
			TOTAL AREA	*303,965 SF	*DOES NOT INCLUDE AREAS OF STREET DEDICATION OR DENSITY CREDIT	
				6.97808 AC		


PLAN PREPARED BY: NELSON P. WIRCHNER, RLA
 ISA CERTIFIED ARBORIST NO. WA-4720AM
 SIGNATURE: *Nelson P. Wirchner* DATE: 08/14/14





IT IS THE INTENT OF THIS DESIGN TO PRESERVE THE EXISTING TREES ALONG GREENSBORO DRIVE, AS SHOWN. HOWEVER, SHOULD THEIR LONG-TERM ViABILITY BECOME QUESTIONABLE DURING DEVELOPMENT OF THE FINAL DETAILED SITE PLAN, THE APPLICANT WILL WORK CLOSELY WITH FAIRFAX COUNTY URBAN FOREST MANAGEMENT TO DEVELOP AND IMPLEMENT A PLAN WHICH REPLACES THE TREES IN-KIND, AND IN THE SAME (OR ALTERNATIVE) LOCATION.

NOTE:
 1. THE ULTIMATE ALIGNMENT OF THE STREETS SHOWN HEREON IS CONCEPTUAL ONLY AND IS SUBJECT TO FURTHER RETINEMENT BY THE OWNERS OF THE ADJACENT PROPERTIES OR THEIR AGENTS AS PART OF FUTURE CONCEPTUAL / FINAL DEVELOPMENT PLANS AND SITE PLANS. SIMILARLY, ALL ROAD DESIGNS ARE SUBJECT TO LIMITATIONS IMPOSED BY THE EXISTING RETAINING WALLS BETWEEN 8183 / 8200 AND THE ADJACENT PROPERTIES.
 2. FOR PRELIMINARY UTILITIES AND GRADING, SEE SHEET C-8



VIVA
 CONSULTING ENGINEERS, ARCHITECTS, AND LANDSCAPE ARCHITECTS
 10000 WOODBRIDGE DRIVE, SUITE 100, FAIRFAX COUNTY, VIRGINIA 22030
 TEL: 703-441-1111 FAX: 703-441-1112 WWW.VIVACONSULTANTS.COM


PROJ. NO. 15-0001
DATE: NOVEMBER 2011

CONCEPTUAL / FINAL DEVELOPMENT PLAN
GREENSBORO PARK PLACE
 PROVIDENCE DISTRICT
 FAIRFAX COUNTY, VIRGINIA

SUBMISSIONS

NO.	DATE	TYPE
13	03/27/2014	CDP/UDP 1/18/2014
12	03/27/2014	ADDC CHANGES 1/10/14
11	03/27/2014	CDP/UDP 12/18/2013
10	03/27/2014	ADDRESS TOWNHOMES 12/03/2013
9	03/27/2014	CDP/UDP 11/08/2013
8	03/27/2014	CDP/UDP 9/03/2013
7	03/27/2014	DRY-RETAINING WALLS 6/29/2013
6	03/27/2014	CDP/UDP 5/20/2013
5	03/27/2014	CDP/UDP 4/16/2013
4	03/27/2014	CDP/UDP 1/15/2013
3	03/27/2014	CDP 09/11/2012
2	03/27/2014	FIRE MARSHAL 7.17.2012
1	03/27/2014	CDP 11/22/2011

SCALE: AS SHOWN
 PROJECT FILE NO: V5050K
 SHEET NO: C-5




- LEGEND:**
- ☐ TOWER
 - ☐ ABOVE GRADE BUILDING BASE
 - ☐ TREE PITS
-
- LEGEND:**
- PATHWAY CHANGE
 - PROPOSED CHANGE
 - ROAD TO LINE
 - ⊙ TRAFFIC SIGNAL
 - ▲ PEDESTRIAN ENTRANCE
 - △ LOADING ENTRANCE
 - ▽ PARKING ENTRANCE
 - ♠ BIKE LANE

INTERNATIONAL DRIVE
AT POST ROAD VARIATION




<p>PRELIMINARY RIGHT-OF-WAY PLAN</p> <p>GREENSBORO PARK PLACE PROVIDENCE DISTRICT FAIRFAX COUNTY, VIRGINIA</p>		<p>PROJECT TEAM</p> <p>OWNER: GREENSBORO PARK PROPERTY OWNER LLC</p> <p>ATTORNEY: COOLE LLP</p> <p>ARCHITECT: HOD ARCHITECTURE</p> <p>LANDSCAPE ARCHITECT: LSC LANDSCAPE ARCHITECTURE</p> <p>TRANSPORTATION: MELLIS & ASSOCIATES, INC.</p>		<p>VIA</p> <p>PLANNERS & PLANNERS • LANDSCAPE ARCHITECTS • SURVEYORS • SUSTAINABLE DESIGN</p> <p>VIA VIRGINIA LLC 6100 GREENSBORO DRIVE - SUITE 200 • TYSONS CORNER, VIRGINIA 22102 (703) 442-1000 • FAX (703) 442-1392 WWW.VIA.COM</p>	
NO.	DATE	DESCRIPTION	BY	CHECKED	APPROVED
1	12/13/2011	ISSUED FOR PERMIT	J. SMITH		
2	01/10/2012	REVISED PER COMMENTS	J. SMITH		
3	01/10/2012	REVISED PER COMMENTS	J. SMITH		
4	01/10/2012	REVISED PER COMMENTS	J. SMITH		
5	01/10/2012	REVISED PER COMMENTS	J. SMITH		
6	01/10/2012	REVISED PER COMMENTS	J. SMITH		
7	01/10/2012	REVISED PER COMMENTS	J. SMITH		
8	01/10/2012	REVISED PER COMMENTS	J. SMITH		
9	01/10/2012	REVISED PER COMMENTS	J. SMITH		
10	01/10/2012	REVISED PER COMMENTS	J. SMITH		
11	01/10/2012	REVISED PER COMMENTS	J. SMITH		
12	01/10/2012	REVISED PER COMMENTS	J. SMITH		
13	01/10/2012	REVISED PER COMMENTS	J. SMITH		
14	01/10/2012	REVISED PER COMMENTS	J. SMITH		
15	01/10/2012	REVISED PER COMMENTS	J. SMITH		
16	01/10/2012	REVISED PER COMMENTS	J. SMITH		
17	01/10/2012	REVISED PER COMMENTS	J. SMITH		
18	01/10/2012	REVISED PER COMMENTS	J. SMITH		
19	01/10/2012	REVISED PER COMMENTS	J. SMITH		
20	01/10/2012	REVISED PER COMMENTS	J. SMITH		
21	01/10/2012	REVISED PER COMMENTS	J. SMITH		
22	01/10/2012	REVISED PER COMMENTS	J. SMITH		
23	01/10/2012	REVISED PER COMMENTS	J. SMITH		
24	01/10/2012	REVISED PER COMMENTS	J. SMITH		
25	01/10/2012	REVISED PER COMMENTS	J. SMITH		
26	01/10/2012	REVISED PER COMMENTS	J. SMITH		
27	01/10/2012	REVISED PER COMMENTS	J. SMITH		
28	01/10/2012	REVISED PER COMMENTS	J. SMITH		
29	01/10/2012	REVISED PER COMMENTS	J. SMITH		
30	01/10/2012	REVISED PER COMMENTS	J. SMITH		
31	01/10/2012	REVISED PER COMMENTS	J. SMITH		
32	01/10/2012	REVISED PER COMMENTS	J. SMITH		
33	01/10/2012	REVISED PER COMMENTS	J. SMITH		
34	01/10/2012	REVISED PER COMMENTS	J. SMITH		
35	01/10/2012	REVISED PER COMMENTS	J. SMITH		
36	01/10/2012	REVISED PER COMMENTS	J. SMITH		
37	01/10/2012	REVISED PER COMMENTS	J. SMITH		
38	01/10/2012	REVISED PER COMMENTS	J. SMITH		
39	01/10/2012	REVISED PER COMMENTS	J. SMITH		
40	01/10/2012	REVISED PER COMMENTS	J. SMITH		
41	01/10/2012	REVISED PER COMMENTS	J. SMITH		
42	01/10/2012	REVISED PER COMMENTS	J. SMITH		
43	01/10/2012	REVISED PER COMMENTS	J. SMITH		
44	01/10/2012	REVISED PER COMMENTS	J. SMITH		
45	01/10/2012	REVISED PER COMMENTS	J. SMITH		
46	01/10/2012	REVISED PER COMMENTS	J. SMITH		
47	01/10/2012	REVISED PER COMMENTS	J. SMITH		
48	01/10/2012	REVISED PER COMMENTS	J. SMITH		
49	01/10/2012	REVISED PER COMMENTS	J. SMITH		
50	01/10/2012	REVISED PER COMMENTS	J. SMITH		


OPTIONS FOR COMPLETION OF RESULTS ROAD (BY OTHERS)




OPTION A (Assumes Parcel 29-3 ((15)) 11A2 is redeveloped)
 The Applicant has designed the further expansion of Results Road at its southwest end in anticipation of it being constructed by others as such time as the property identified on the 2013 Fairfax County Tax Map 29-3 ((15)) 11A2 becomes the subject of a zoning application and is redeveloped. Head-in pkg north of existing 8200 building will remain.



OPTION C (Assumes BOTH Parcels 29-3 ((15)) 11B3 & 29-3 ((15)) 11A2 are redeveloped)
 The Applicant has designed the ultimate condition of Results Road in anticipation of it being completed by others at such time as the property identified on the 2013 Fairfax County Tax Map as 29-3 ((15)) 11B3 becomes the subject of a zoning application ("Ultimate B").



OPTION B (Assumes Parcel 29-3 ((15)) 11B3 is redeveloped)
 The Applicant has designed the ultimate condition of Results Road in anticipation of it being completed by others at such time as the property identified on the 2013 Fairfax County Tax Map as 29-3 ((15)) 11B3 becomes the subject of a zoning application ("Ultimate B").



OPTION D (Assumes both existing office buildings (8180 & 8200) redevelop)
 As an alternative to Ultimate B as described above, if the Existing Office Buildings, which are anticipated to remain in their existing conditions with the Proposed Development, are redeveloped pursuant to a future zoning application; and, Ultimate B has not yet been constructed by others, the Applicant shall construct an alternative ultimate condition of Results Road.

CONSULTING ENGINEERS & ARCHITECTS IN CIVIL, MECHANICAL & ELECTRICAL ENGINEERING
 1000 WEST LEE AVENUE, SUITE 200, ARLINGTON, VIRGINIA 22202
 (703) 261-1111 FAX (703) 261-1112

OWNER: GREENSBORO PARK
 ARCHITECT: LOBBETT LLP
 ARCHITECT AND ARCHITECTIVE
 ENGINEER: JACOBS
 LANDSCAPE ARCHITECTURE
 ENGINEER: TRANSPORTATION, INC.

GREENSBORO PARK PLACE
 PROMISE DISTRICT
 FAIRFAX COUNTY, VIRGINIA

EXTENSION OF RESULTS ROAD (BY OTHERS)

SUBMISSIONS

NO.	DATE	DESCRIPTION
1	01/16/2014	PRELIMINARY SUBMISSION
2	02/12/2014	REVISIONS
3	03/11/2014	REVISIONS
4	04/01/2014	REVISIONS
5	04/22/2014	REVISIONS
6	05/07/2014	REVISIONS
7	05/20/2014	REVISIONS
8	06/02/2014	REVISIONS
9	06/18/2014	REVISIONS
10	07/01/2014	REVISIONS
11	07/15/2014	REVISIONS
12	07/29/2014	REVISIONS
13	08/12/2014	REVISIONS
14	08/26/2014	REVISIONS
15	09/09/2014	REVISIONS
16	09/23/2014	REVISIONS
17	10/07/2014	REVISIONS
18	10/21/2014	REVISIONS
19	11/04/2014	REVISIONS
20	11/18/2014	REVISIONS
21	12/02/2014	REVISIONS
22	12/16/2014	REVISIONS
23	12/30/2014	REVISIONS
24	01/13/2015	REVISIONS
25	01/27/2015	REVISIONS
26	02/10/2015	REVISIONS
27	02/24/2015	REVISIONS
28	03/10/2015	REVISIONS
29	03/24/2015	REVISIONS
30	04/07/2015	REVISIONS
31	04/21/2015	REVISIONS
32	05/05/2015	REVISIONS
33	05/19/2015	REVISIONS
34	06/02/2015	REVISIONS
35	06/16/2015	REVISIONS
36	06/30/2015	REVISIONS
37	07/14/2015	REVISIONS
38	07/28/2015	REVISIONS
39	08/11/2015	REVISIONS
40	08/25/2015	REVISIONS
41	09/08/2015	REVISIONS
42	09/22/2015	REVISIONS
43	10/06/2015	REVISIONS
44	10/20/2015	REVISIONS
45	11/03/2015	REVISIONS
46	11/17/2015	REVISIONS
47	11/30/2015	REVISIONS
48	12/14/2015	REVISIONS
49	12/28/2015	REVISIONS
50	01/11/2016	REVISIONS
51	01/25/2016	REVISIONS
52	02/08/2016	REVISIONS
53	02/22/2016	REVISIONS
54	03/08/2016	REVISIONS
55	03/22/2016	REVISIONS
56	04/05/2016	REVISIONS
57	04/19/2016	REVISIONS
58	05/03/2016	REVISIONS
59	05/17/2016	REVISIONS
60	05/31/2016	REVISIONS
61	06/14/2016	REVISIONS
62	06/28/2016	REVISIONS
63	07/12/2016	REVISIONS
64	07/26/2016	REVISIONS
65	08/09/2016	REVISIONS
66	08/23/2016	REVISIONS
67	09/06/2016	REVISIONS
68	09/20/2016	REVISIONS
69	10/04/2016	REVISIONS
70	10/18/2016	REVISIONS
71	11/01/2016	REVISIONS
72	11/15/2016	REVISIONS
73	11/29/2016	REVISIONS
74	12/13/2016	REVISIONS
75	12/27/2016	REVISIONS
76	01/10/2017	REVISIONS
77	01/24/2017	REVISIONS
78	02/07/2017	REVISIONS
79	02/21/2017	REVISIONS
80	03/07/2017	REVISIONS
81	03/21/2017	REVISIONS
82	04/04/2017	REVISIONS
83	04/18/2017	REVISIONS
84	05/02/2017	REVISIONS
85	05/16/2017	REVISIONS
86	05/30/2017	REVISIONS
87	06/13/2017	REVISIONS
88	06/27/2017	REVISIONS
89	07/11/2017	REVISIONS
90	07/25/2017	REVISIONS
91	08/08/2017	REVISIONS
92	08/22/2017	REVISIONS
93	09/05/2017	REVISIONS
94	09/19/2017	REVISIONS
95	10/03/2017	REVISIONS
96	10/17/2017	REVISIONS
97	10/31/2017	REVISIONS
98	11/14/2017	REVISIONS
99	11/28/2017	REVISIONS
100	12/12/2017	REVISIONS
101	12/26/2017	REVISIONS
102	01/09/2018	REVISIONS
103	01/23/2018	REVISIONS
104	02/06/2018	REVISIONS
105	02/20/2018	REVISIONS
106	03/06/2018	REVISIONS
107	03/20/2018	REVISIONS
108	04/03/2018	REVISIONS
109	04/17/2018	REVISIONS
110	04/30/2018	REVISIONS
111	05/14/2018	REVISIONS
112	05/28/2018	REVISIONS
113	06/11/2018	REVISIONS
114	06/25/2018	REVISIONS
115	07/09/2018	REVISIONS
116	07/23/2018	REVISIONS
117	08/06/2018	REVISIONS
118	08/20/2018	REVISIONS
119	09/03/2018	REVISIONS
120	09/17/2018	REVISIONS
121	09/30/2018	REVISIONS
122	10/14/2018	REVISIONS
123	10/28/2018	REVISIONS
124	11/11/2018	REVISIONS
125	11/25/2018	REVISIONS
126	12/09/2018	REVISIONS
127	12/23/2018	REVISIONS
128	01/06/2019	REVISIONS
129	01/20/2019	REVISIONS
130	02/03/2019	REVISIONS
131	02/17/2019	REVISIONS
132	03/03/2019	REVISIONS
133	03/17/2019	REVISIONS
134	03/31/2019	REVISIONS
135	04/14/2019	REVISIONS
136	04/28/2019	REVISIONS
137	05/12/2019	REVISIONS
138	05/26/2019	REVISIONS
139	06/09/2019	REVISIONS
140	06/23/2019	REVISIONS
141	07/07/2019	REVISIONS
142	07/21/2019	REVISIONS
143	08/04/2019	REVISIONS
144	08/18/2019	REVISIONS
145	08/31/2019	REVISIONS
146	09/14/2019	REVISIONS
147	09/28/2019	REVISIONS
148	10/12/2019	REVISIONS
149	10/26/2019	REVISIONS
150	11/09/2019	REVISIONS
151	11/23/2019	REVISIONS
152	12/07/2019	REVISIONS
153	12/21/2019	REVISIONS
154	01/04/2020	REVISIONS
155	01/18/2020	REVISIONS
156	02/01/2020	REVISIONS
157	02/15/2020	REVISIONS
158	02/29/2020	REVISIONS
159	03/14/2020	REVISIONS
160	03/28/2020	REVISIONS
161	04/11/2020	REVISIONS
162	04/25/2020	REVISIONS
163	05/09/2020	REVISIONS
164	05/23/2020	REVISIONS
165	06/06/2020	REVISIONS
166	06/20/2020	REVISIONS
167	07/04/2020	REVISIONS
168	07/18/2020	REVISIONS
169	07/31/2020	REVISIONS
170	08/14/2020	REVISIONS
171	08/28/2020	REVISIONS
172	09/11/2020	REVISIONS
173	09/25/2020	REVISIONS
174	10/09/2020	REVISIONS
175	10/23/2020	REVISIONS
176	11/06/2020	REVISIONS
177	11/20/2020	REVISIONS
178	12/04/2020	REVISIONS
179	12/18/2020	REVISIONS
180	12/31/2020	REVISIONS
181	01/14/2021	REVISIONS
182	01/28/2021	REVISIONS
183	02/11/2021	REVISIONS
184	02/25/2021	REVISIONS
185	03/11/2021	REVISIONS
186	03/25/2021	REVISIONS
187	04/08/2021	REVISIONS
188	04/22/2021	REVISIONS
189	05/06/2021	REVISIONS
190	05/20/2021	REVISIONS
191	06/03/2021	REVISIONS
192	06/17/2021	REVISIONS
193	06/30/2021	REVISIONS
194	07/14/2021	REVISIONS
195	07/28/2021	REVISIONS
196	08/11/2021	REVISIONS
197	08/25/2021	REVISIONS
198	09/08/2021	REVISIONS
199	09/22/2021	REVISIONS
200	10/06/2021	REVISIONS
201	10/20/2021	REVISIONS
202	11/03/2021	REVISIONS
203	11/17/2021	REVISIONS
204	11/30/2021	REVISIONS
205	12/14/2021	REVISIONS
206	12/28/2021	REVISIONS
207	01/11/2022	REVISIONS
208	01/25/2022	REVISIONS
209	02/08/2022	REVISIONS
210	02/22/2022	REVISIONS
211	03/08/2022	REVISIONS
212	03/22/2022	REVISIONS
213	04/05/2022	REVISIONS
214	04/19/2022	REVISIONS
215	05/03/2022	REVISIONS
216	05/17/2022	REVISIONS
217	05/31/2022	REVISIONS
218	06/14/2022	REVISIONS
219	06/28/2022	REVISIONS
220	07/12/2022	REVISIONS
221	07/26/2022	REVISIONS
222	08/09/2022	REVISIONS
223	08/23/2022	REVISIONS
224	09/06/2022	REVISIONS
225	09/20/2022	REVISIONS
226	10/04/2022	REVISIONS
227	10/18/2022	REVISIONS
228	11/01/2022	REVISIONS
229	11/15/2022	REVISIONS
230	11/29/2022	REVISIONS
231	12/13/2022	REVISIONS
232	12/27/2022	REVISIONS
233	01/10/2023	REVISIONS
234	01/24/2023	REVISIONS
235	02/07/2023	REVISIONS
236	02/21/2023	REVISIONS
237	03/07/2023	REVISIONS
238	03/21/2023	REVISIONS
239	04/04/2023	REVISIONS
240	04/18/2023	REVISIONS
241	05/02/2023	REVISIONS
242	05/16/2023	REVISIONS
243	05/30/2023	REVISIONS
244	06/13/2023	REVISIONS
245	06/27/2023	REVISIONS
246	07/11/2023	REVISIONS
247	07/25/2023	REVISIONS
248	08/08/2023	REVISIONS
249	08/22/2023	REVISIONS
250	09/05/2023	REVISIONS
251	09/19/2023	REVISIONS
252	10/03/2023	REVISIONS
253	10/17/2023	REVISIONS
254	10/31/2023	REVISIONS
255	11/14/2023	REVISIONS
256	11/28/2023	REVISIONS
257	12/12/2023	REVISIONS
258	12/26/2023	REVISIONS
259	01/09/2024	REVISIONS
260	01/23/2024	REVISIONS
261	02/06/2024	REVISIONS
262	02/20/2024	REVISIONS
263	03/06/2024	REVISIONS
264	03/20/2024	REVISIONS
265	04/03/2024	REVISIONS
266	04/17/2024	REVISIONS
267	05/01/2024	REVISIONS
268	05/15/2024	REVISIONS
269	05/29/2024	REVISIONS
270	06/12/2024	REVISIONS
271	06/26/2024	REVISIONS
272	07/10/2024	REVISIONS
273	07/24/2024	REVISIONS
274	08/07/2024	REVISIONS
275	08/21/2024	REVISIONS
276	09/04/2024	REVISIONS
277	09/18/2024	REVISIONS
278	10/02/2024	REVISIONS
279	10/16/2024	REVISIONS
280	10/30/2024	REVISIONS
281	11/13/2024	REVISIONS
282	11/27/2024	REVISIONS
283	12/11/2024	REVISIONS
284	12/25/2024	REVISIONS
285	01/08/2025	REVISIONS
286	01/22/2025	REVISIONS
287	02/05/2025	REVISIONS
288	02/19/2025	REVISIONS
289	03/05/2025	REVISIONS
290	03/19/2025	REVISIONS
291	04/02/2025	REVISIONS
292	04/16/2025	REVISIONS
293	05/01/2025	REVISIONS
294	05/15/2025	REVISIONS
295	05/29/2025	REVISIONS
296	06/12/2025	REVISIONS
297	06/26/2025	REVISIONS
298	07/10/2025	REVISIONS
299	07/24/2025	REVISIONS
300	08/07/2025	REVISIONS
301	08/21/2025	REVISIONS
302	09/04/2025	REVISIONS
303	09/18/2025	REVISIONS



VI

COLLECTOR TEAM
OWNER: GREENSBORO PARK
PROPERTY OWNER LLC
ARCHITECT: BEC ARCHITECTURE
LANDSCAPE ARCHITECTURE
US LANDSCAPE ARCHITECTURE
P.L.L.C.
1000 W. MAIN ST., SUITE 200
FAIRFAX COUNTY, VA 22031
TEL: 703.441.1111
WWW.BECARCHITECTURE.COM

GREENSBORO PARK PLACE
PRINCEDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA

**PRELIMINARY
PROPOSED UTILITY
LAYOUT**

SUBMISSIONS	
NO.	TYPE
13	CDP / TDP 1/18/2014
12	ADDP CON'TS 1/16/14
11	CDP / TDP 12/18/2013
10 ACCESS COMMENTS	
12/03/2013	
9	CDP / TDP 11/26/2013
8	CDP / TDP 8/03/2013
7	DRAFT REVS 6/19/2013
6	CDP / TDP 5/20/2013
5	CDP / TDP 4/03/2013
4	CDP / TDP 1/15/2013
3	CDP 08/11/2012
2	PAC MEMO 7.11.2012
1	CDP 02/03/2012
1	CDP 11/22/2011
DATE: NOVEMBER 2011	
DES.	DWG.
VIKA	DMV
SCALE: AS SHOWN	
PROJECT/FILE NO V501-SK	
SHEET NO. C-8	



10 SCALE BLOW-UP OF LEED RE-USE VAULT


NOTE:


1. THE ULTIMATE ADJUSTMENT OF THE STREETS SHOWN HEREON IS CONCEPTUAL ONLY AND IS SUBJECT TO FURTHER REFINEMENT BY THE OWNERS OF THE ADJACENT PROPERTIES OR THEIR AGENTS AS PART OF FUTURE CONCEPTUAL / FINAL DEVELOPMENT PLANS AND SITE PLANS. SIMILARLY, ALL ROAD DESIGN ARE SUBJECT TO LIMITATIONS IMPOSED BY THE EXISTING RETAINING WALLS BETWEEN 8900 / 8200 AND THE ADJACENT PROPERTIES.
2. FOR PRELIMINARY UTILITIES AND GRADING, SEE SHEET C-8

LEGEND:

- TOWER
- ABOVE GRADE BUILDING BASE
- TREE PITS

- TRAFFIC SIGNAL
- PEDESTRIAN ENTRANCE
- LOADING ENTRANCE
- PARKING ENTRANCE
- BIKE LANE





LEGEND:

- TOWER
- ABOVE GRADE BUILDING BASE
- TREE PITS

TRAFFIC SIGNAL

PEDESTRIAN ENTRANCE

LOADING ENTRANCE

PARKING ENTRANCE


BIKE LANE

NOTE:

1. ALL WORK SOUTH OF THE GREENSBORO DRIVE CENTERLINE (EAST-BOUND LANES) SHALL BE BY OTHERS, EXCEPT AS SHOWN AT THE GREENSBORO DRIVE/ INTERNATIONAL DRIVE INTERSECTION.
2. ALL PROPOSED ROADWAY IMPROVEMENTS ARE SUBJECT TO FCOTD AND VDOT REVIEW AND APPROVAL.
3. FOR PUBLIC ROAD DEDICATION AND TIMING, SEE PROFFERS.

LEGEND

- AVENUE
- PUBLIC LOCAL STREET
- PRIVATE SERVICE DRIVE
- PROPOSED (FUTURE) ROW



VFA
 PROJECTS IN PLANNING & LANDSCAPE ARCHITECTURE & INTERIOR & SUSTAINABLE DESIGN
 1100 GREENSBORO DRIVE, SUITE 200, FARMINGTON, VIRGINIA 22129
 (703) 836-1100
 WWW.VFA.COM

CONTACT NAME: **OSCAR DELA CRUZ**
 OWNER: GREENSBORO PARK
 PROJECT: COMET LLP
 ARCHITECT: BOB ANDREWS/ETC
 LANDSCAPE ARCHITECT: VFA
 ENGINEER: VFA
 TRANSPORTATION: MELLÉ & ASSOCIATES, INC.

GREENSBORO PARK PLACE
 PROMISE DISTRICT
 FAIRFAX COUNTY, VIRGINIA

TRAFFIC CIRCULATION & SIGHT DISTANCE PLAN

SUBMISSIONS

NO.	DATE	TYPE
17	03/18/2014	CDP/PROP
13	02/18/2013	CDP/PROP
11	03/13/2013	ADDRESS COMMENTS
9	03/20/2013	CDP/PROP
8	03/20/2013	CDP/PROP
7	06/19/2013	DRAFT REVIS
6	06/03/2013	CDP/PROP
5	04/16/2013	CDP/PROP
4	01/15/2013	CDP/PROP
3	09/11/2012	CDP/PROP
2	07/07/2012	TRK W/REVISION
1	11/22/2011	CDP/PROP

DATE REVIEWED: 01/17/2013

DES.	CHK.	APP.

SCALE: AS SHOWN

PROJECT/FILE NO.: V5015K

SHEET NO.: C-10

TREES IN VDOT ROW HAVE BEEN PROPOSED USING THE TYSONS CORNER URBAN STANDARDS


GREENSBORO PARK PLACE
PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA

SHADOW BAND ANALYSIS

SUBMISSIONS

NO.	DATE	TYPE
12	CDP/ADP 01/16/2014	
11	CDP/ADP 12/16/2013	
10	ADDRESS COMMENTS	
9	12/03/2013	
8	CDP/ADP 11/08/2013	
7	CDP/ADP 9/20/2013	
6	SHAFT REV 8/19/2013	
5	CDP/ADP 5/20/2013	
4	CDP/ADP 4/16/2013	
3	CDP/ADP 1/13/2013	
2	CDP/ADP 1/13/2013	
1	JRNL MARSHAL 7/17/2011	
	CDP 02/03/2011	
	LEAD 11/25/2011	

DATE: 10-15-2014
DES: MCA DMK
SCALE: AS SHOWN
PROJECT/FILE NO: V05015K
SHEET NO: C-12



GREENSBORO DRIVE - ROUTE 5063 (AVENUE)
POSTED SPEED = 20 MPH
DESIGN SPEED = 30 MPH

KEY:
- TREE IS WITHIN CORRIDOR SET BY LINE OF CLEAR SIGHT

SHADOW BAND EXCLUSION NOTE:
BASED ON THE TRANSPORTATION DESIGN STANDARDS FOR TYSONS CORNER URBAN CENTER, GENERAL NOTE 5 STATES THAT THE CORRIDOR SET BY THE LIMITS OF CLEAR SIGHT IS A RESTRICTED PLANTING AREA, AND VEGETATION WITHIN THIS CORRIDOR IS SUBJECT TO CERTAIN CRITERIA AS SHOWN ON THIS SHEET, SPECIFICALLY FOR TREES, TRUNK SIZE AND SPACING ARE TO BE IN CONFORMANCE WITH THE TABLE ALSO SHOWN ON THIS SHEET. THE TREES PLANTED WITHIN THE CORRIDOR SET BY THE LIMITS OF CLEAR SIGHT ARE ALL CATEGORIED BY TREE SIZE (LANDSCAPE PLAN) AND HAVE A 7" TRUNK DIAMETER ESTIMATED AT A 10 YEAR LEVEL OF MATURITY BASED ON A 3" CALIPER SIZE AT THE TIME OF PLANTING. THE DESIGN SPEED OF GREENSBORO DRIVE IS 30 MPH, WHICH SETS THE MINIMUM SPACING OF ALL TREES WITHIN THE SUBJECT CORRIDOR TO BE A MINIMUM OF 22 FEET.

SINCE ALL OF THESE TREES HAVE ADEQUATE THIRDMAN SPACING, THEN ACCORDING TO DESIGN NOTE 5, PROOF OF VIEW AND SHADOW RESTRAINTS ARE NOT REQUIRED TO BE DOCUMENTED.

SIGHT DISTANCE NOTE:
PLANTINGS IN THE ROW ALONG THE BUILDING FRONTAGE SHALL BE "LANKED UP" TO A HEIGHT OF 10' TO ENSURE LINE OF SIGHT IS MAINTAINED. SEE THIS SHEET FOR MORE DETAILED INFORMATION REGARDING SPECIFICATIONS FOR VEGETATION WITHIN "CLEAR LINE OF SIGHT" PER NEW TYSONS CORNER URBAN DESIGN STANDARDS.

NOTE:
ROOT LANDSCAPING APPROVAL / PERMIT REQUIRED FOR TREES PLANTED IN ROW

GENERAL NOTES

5. The corridor defined by the limits of clear sight is a restricted planting area. Matters of vegetation on the intersecting roadway and vehicles on the major roadway must be able to see each other clearly throughout the limits of "A and B", if in the Engineer's judgement, indicating interference with the line of sight corridor as described by these elements the Engineer may reorganize, relocate or eliminate plantings. Plants within the restricted areas are limited to selections as follows:



Ground Cover A: Trunked Plants (Separate or Clustered)
Ground Cover: Plant selection of low growing vegetation which at maturity does not attain a height greater than 40" above the signal line status.
For ground cover in combination with trees and palms, the following heights below the signal line status will apply: 24" for trees and palms < 10" dia, and 48" for palm trees < 1 1/2" dia, within Sight Triangles.

Trunked Plants: Plant selection of mature trees diameter 4" or less measured at 4' above the ground. Canopy or High Branches shall never be lower than 5' above the signal line status. These selections shall be spaced no closer than 20'.

Trees: Trees can be used with dense canopy, permeable canopy, bare or wood with dense ground cover or other approved approved methods. The clear sight corridor must be in conformance with the "WINDOW DETAIL" required to ensure the sight requirements stated in "Ground Cover" above. Tree size and spacing must conform to the following table:


Description	Speed (mph)											
	20	25	30	35	40	45	50	55	60	65	70	75
Diameter (inches)	4	4	4	4	4	4	4	4	4	4	4	4
Minimum Spacing (in ft. or 2' min)	22	31	47	49	53	60	66	70	80	82	83	83

Size and spacing are based on the following specifications:
1) A single line of trees in the median parallel to but not necessarily surface with the centerline.
2) A straight approaching roadway, within 1500 feet as described in No. 2 above.
3) Trees may be planted in an alternate planting or vertical or other above listed in a vehicle stopping or slow approach when viewed by vehicles either beginning at distance of 100' SHADOW SIGNATURE DISTANCE.
4) Solid plant with diameter 4" to 10" spaced at intervals providing a 2 second full view of approaching vehicle at 200 feet approach when viewed by multi-lane driving at distance of 100' PERCEPTION DISTANCE, SPACING IS:
1) Trees with diameters 4" to 10" spaced with trees with diameters 4" to 10" are to be spaced based on trees with diameters 4" to 10".
For any other conditions the tree sizes, spacings and locations shall be defined in the plans, see Design Note No. 5.



DESIGN NOTES

- The intersection shown on this plan is to be used for the purpose of clear sight development and maintenance of intersecting highways, roads and streets, and it is intended to be used in a similar roadway and roadway safety project as related to clear sight corridors. An analysis of sight distance should be documented for all intersections.
- Details are based on the AASHTO Policy on Geometric Design of Highways and Streets, 2001, CHAPTER 9, INTERSECTION SIGHT DISTANCE, PAGES 0 and 1, and Department analysis for characterized roadways (see Table for major roadways).
- The minimum driver eye height of 4.5' from the edge of the roadway may be adjusted on any intersection only when justified by a documented, site specific field study of vehicle stopping location and driver eye position.
- For UNCONTROLLED INTERSECTIONS sight distances should be developed based on AASHTO Case 0 - Intersections with Traffic Signal Control. At signalized intersections, the (1st) vehicle stopped on one approach shall be visible to the driver of the first vehicle stopped on each of the other approaches. Left-turning vehicles should have sufficient sight distance to detect an approaching traffic and complete left turns, apart from these sight conditions, there are generally no other approaches or roadway sight triangles required for uncontrolled intersections. However, if the traffic signal is to be placed on two-way flashing operation (i.e., flashing yellow on the major road, stop-and-go and flashing red on the minor road) operations under left turn or alternative conditions, then the appropriate departure sight triangles for Case 4a, b, c, and d, in the table, should be provided for the minor road approaches. In addition, if right turns on a red signature to be permitted from any approach, then the appropriate departure sight triangles in the left for Case 5c should be provided in accordance with the table.
- Where shoulders, encroachments, barriers and/or profiles at other conditions produce the net of stopping free area and spacing, proof of view and stopping requirements must be documented and the size and location of trees to be planted relative to the plan.
- Intersection sight triangles should be provided for passenger vehicles, 50 vehicles and combinations, vehicles, intersection sight triangles based on the Passenger Vehicle is subject for most intersections. Where additional volumes of heavy vehicles enter the major road, such as from rural terminals with slow control or roadways serving rural terminals, the use of trucking vehicle for 50 vehicle or combination vehicles should be considered.




GREENSBORO PARK PLACE
 PROUDLY OWNED BY
 GREENSBORO PARK PLACE
 PROPERTY GROUP LLC
 ATTORNEY: COOKLEY LLP
 ARCHITECT: MCM ARCHITECTURE
 LANDSCAPE ARCHITECTURE
 LLC LANDSCAPE ARCHITECTURE
 TRANSPORTATION
 CONSULTANTS, INC.
 WWW.VIWA.COM


GREENSBORO PARK PLACE
 PROUDLY OWNED BY
 GREENSBORO PARK PLACE
 PROPERTY GROUP LLC
 ATTORNEY: COOKLEY LLP
 ARCHITECT: MCM ARCHITECTURE
 LANDSCAPE ARCHITECTURE
 LLC LANDSCAPE ARCHITECTURE
 TRANSPORTATION
 CONSULTANTS, INC.
 WWW.VIWA.COM

AREA AND METRO
 CONTEXT PLAN
 TYSONS CORNER STATION

SUBMISSIONS
 SHEET NO. C-15A
 PROJECT/FILE NO. 100204
 SCALE AS SHOWN
 GRAPHIC SCALE
 1" = 200'



TYSONS CENTRAL 7 NORTH SUBDISTRICT



VIVA
 PROJECTS & PLANNING & LANDSCAPE ARCHITECTURE & INTERIOR & EXTERIOR DESIGN
 1100 WASHINGTON BLVD. SUITE 4000
 (703) 433-1100 FAX (703) 433-1101
 WWW.VIVA-PA.COM

PROJECT TEAM
 OWNER: METRO SYSTEMS
 ARCHITECT: COLETTI LUP
 ARCHITECT AND INTERIOR ARCHITECTURE
 LANDSCAPE ARCHITECTURE
 TRANSPORTATION
 MOBILITY ASSOCIATES, INC.

GREENSBORO PARK PLACE
 PROVIDENCE DISTRICT
 FAIRFAX COUNTY, VIRGINIA

DETAILED STREET GRID PLAN

SUBMISSIONS	
NO.	DATE
1	01/16/2014
2	12/18/2013
3	11/08/2013
4	10/23/2013
5	10/23/2013
6	10/23/2013
7	10/23/2013
8	10/23/2013
9	10/23/2013
10	10/23/2013
11	10/23/2013
12	10/23/2013
13	10/23/2013
14	10/23/2013
15	10/23/2013
16	10/23/2013
17	10/23/2013
18	10/23/2013
19	10/23/2013
20	10/23/2013
21	10/23/2013
22	10/23/2013
23	10/23/2013
24	10/23/2013
25	10/23/2013
26	10/23/2013
27	10/23/2013
28	10/23/2013
29	10/23/2013
30	10/23/2013
31	10/23/2013
32	10/23/2013
33	10/23/2013
34	10/23/2013
35	10/23/2013
36	10/23/2013
37	10/23/2013
38	10/23/2013
39	10/23/2013
40	10/23/2013
41	10/23/2013
42	10/23/2013
43	10/23/2013
44	10/23/2013
45	10/23/2013
46	10/23/2013
47	10/23/2013
48	10/23/2013
49	10/23/2013
50	10/23/2013
51	10/23/2013
52	10/23/2013
53	10/23/2013
54	10/23/2013
55	10/23/2013
56	10/23/2013
57	10/23/2013
58	10/23/2013
59	10/23/2013
60	10/23/2013
61	10/23/2013
62	10/23/2013
63	10/23/2013
64	10/23/2013
65	10/23/2013
66	10/23/2013
67	10/23/2013
68	10/23/2013
69	10/23/2013
70	10/23/2013
71	10/23/2013
72	10/23/2013
73	10/23/2013
74	10/23/2013
75	10/23/2013
76	10/23/2013
77	10/23/2013
78	10/23/2013
79	10/23/2013
80	10/23/2013
81	10/23/2013
82	10/23/2013
83	10/23/2013
84	10/23/2013
85	10/23/2013
86	10/23/2013
87	10/23/2013
88	10/23/2013
89	10/23/2013
90	10/23/2013
91	10/23/2013
92	10/23/2013
93	10/23/2013
94	10/23/2013
95	10/23/2013
96	10/23/2013
97	10/23/2013
98	10/23/2013
99	10/23/2013
100	10/23/2013

SCALE: 1"=150'
 PROJECT/FILE NO.: 15073M
 SHEET NO.: C-15b

PART I: LEED COMPUTATIONS

WTR-20 Printed Page File Beginning of Input Data List
PR20.out

WTR-20 Version 1.10

8180 CDP
EXISTING CONDITIONS

SUB-AREA:

COP AREA Outlet 0.0356 62. 1

STREAM REACH:

STORM ANALYSIS 2-YR 3.2 Type 1 2

STRUCTURE RATING:

GLOBAL OUTPUT 2 0.05 YYYN YYYNA

Name of printed page file PR20.out

WTR-20 Printed Page File End of Input Data List

8180 CDP
EXISTING CONDITIONS

SUB-AREA:

COP AREA Outlet 0.0356 62. 1

STREAM REACH:

STORM ANALYSIS 2-YR 3.2 Type 1 2

STRUCTURE RATING:

GLOBAL OUTPUT 2 0.05 YYYN YYYNA

Name of printed page file PR20.out

WTR-20 Printed Page File Beginning of Input Data List

8180 CDP
PROPOSED CONDITIONS

SUB-AREA:

COP AREA Outlet 0.0356 62. 1

STREAM REACH:

STORM ANALYSIS 2-YR 3.2 Type 1 2

STRUCTURE RATING:

GLOBAL OUTPUT 2 0.05 YYYN YYYNA

Name of printed page file PR20.out

WTR-20 Printed Page File Beginning of Input Data List

8180 CDP
PROPOSED CONDITIONS

SUB-AREA:

COP AREA Outlet 0.0356 62. 1

STREAM REACH:

STORM ANALYSIS 2-YR 3.2 Type 1 2

STRUCTURE RATING:

GLOBAL OUTPUT 2 0.05 YYYN YYYNA

Name of printed page file PR20.out

WTR-20 Printed Page File End of Input Data List

8180 CDP
PROPOSED CONDITIONS

SUB-AREA:

COP AREA Outlet 0.0356 62. 1

STREAM REACH:

STORM ANALYSIS 2-YR 3.2 Type 1 2

STRUCTURE RATING:

GLOBAL OUTPUT 2 0.05 YYYN YYYNA

Name of printed page file PR20.out

WTR-20 Printed Page File Beginning of Input Data List

8180 CDP
PROPOSED CONDITIONS

SUB-AREA:

COP AREA Outlet 0.0356 62. 1

STREAM REACH:

STORM ANALYSIS 2-YR 3.2 Type 1 2

STRUCTURE RATING:

GLOBAL OUTPUT 2 0.05 YYYN YYYNA

Name of printed page file PR20.out

WTR-20 Printed Page File End of Input Data List

8180 CDP
PROPOSED CONDITIONS

SUB-AREA:

COP AREA Outlet 0.0356 62. 1

STREAM REACH:

STORM ANALYSIS 2-YR 3.2 Type 1 2

STRUCTURE RATING:

GLOBAL OUTPUT 2 0.05 YYYN YYYNA

Name of printed page file PR20.out

WTR-20 Printed Page File Beginning of Input Data List

8180 CDP
PROPOSED CONDITIONS

SUB-AREA:

COP AREA Outlet 0.0356 62. 1

STREAM REACH:

STORM ANALYSIS 2-YR 3.2 Type 1 2

STRUCTURE RATING:

GLOBAL OUTPUT 2 0.05 YYYN YYYNA

Name of printed page file PR20.out

WTR-20 Printed Page File End of Input Data List

8180 CDP
PROPOSED CONDITIONS

SUB-AREA:

COP AREA Outlet 0.0356 62. 1

STREAM REACH:

STORM ANALYSIS 2-YR 3.2 Type 1 2

STRUCTURE RATING:

GLOBAL OUTPUT 2 0.05 YYYN YYYNA

Name of printed page file PR20.out

LEED BOUNDARY IS 2.30 ACRE RESIDENTIAL PORTION OF SITE = 0.00154 SQ MI

2 YR: 2.3 AC x (2.318 IN / 12 IN/FT) x 43,560 SQ FT/AC = 19,353 CF

TOTAL RUNOFF VOLUME (EXISTING CONDITIONS):

2 YR: 2.3 AC x (2.318 IN / 12 IN/FT) x 43,560 SQ FT/AC = 19,353 CF

LEED BOUNDARY IS 2.30 ACRE RESIDENTIAL PORTION OF SITE = 0.00154 SQ MI

2 YR: 2.3 AC x (2.318 IN / 12 IN/FT) x 43,560 SQ FT/AC = 19,353 CF

TOTAL RUNOFF VOLUME (PROPOSED CONDITIONS, WITHOUT SWM CONTROLS):

2 YR: 2.3 AC x (2.318 IN / 12 IN/FT) x 43,560 SQ FT/AC = 19,353 CF



LEED PROVIDED RUNOFF REDUCTION VOLUME

THE TOTAL STORAGE VOLUME PROVIDED IS EQUAL TO THE SUM OF THE STORAGE PROVIDED TO DETAIN THE FIRST 1" OF RAINFALL AND ANY ADDITIONAL STORAGE PROVIDED BY THE VARIOUS RUNOFF REDUCTION PRACTICES. AS CAN BE SEEN WITH THE COMPUTATIONS ON SHEET C-17, 3,852 SQ FT OF ADDITIONAL STORAGE HAS BEEN PROVIDED TO HELP MEET THE LEED REQUIREMENT OF VOLUME REDUCTION. THIS TOTAL STORAGE PROVIDED ON SHEET C-17 (1" RUNOFF REDUCTION) = 3,852 CFS (ADDITIONAL STORAGE) = 11,769 CFS. THIS VOLUME IS LARGER THAN THE RUNOFF REDUCTION REQUIRED FOR LEED. THEREFORE THIS SITE MEETS THE LEED REQUIREMENT OF REDUCING SITE RUNOFF TO 75% OF THE EXISTING CONDICTION RUNOFF VOLUME FOR THE 2-YR STORM.

LEED ALLOWABLE RELEASE RATE

THE ALLOWABLE RELEASE RATE FOR THIS PLAN SHALL BE DICTATED BY THE PFM WHICH DOES NOT ALLOW FOR A RATE GREATER THAN EXISTING. SEE PART II ON THIS SHEET FOR ADDITIONAL INFORMATION.

PART II: PFM COMPLIANCE



PFM ALLOWABLE RELEASE RATE

PER THE PFM DEVELOPED RELEASE RATE FOR THE 2-YEAR AND 10-YEAR STORM MUST NOT EXCEED THE EXISTING CONDICTION RELEASE RATE.

PFM PROVIDED RELEASE RATE

THE TOTAL STORAGE VOLUME PROVIDED IS EQUAL TO THE SUM OF THE STORAGE PROVIDED TO DETAIN THE FIRST 1" OF RAINFALL AND ANY ADDITIONAL STORAGE PROVIDED BY THE VARIOUS RUNOFF REDUCTION PRACTICES. AS CAN BE SEEN WITH THE COMPUTATIONS ON SHEET C-17, 3,852 SQ FT OF ADDITIONAL STORAGE HAS BEEN PROVIDED TO HELP MEET THE PFM REQUIREMENT OF PEAK RELEASE RATE. THIS TOTAL STORAGE PROVIDED ON SHEET C-17 (1" RUNOFF REDUCTION) = 3,852 CFS (ADDITIONAL STORAGE) = 11,769 CFS.

AS CAN BE SEEN BY VIEWING THE PROVIDED VOLUME FOR THE FIRST INCH OF RAINFALL AND WITH THE ADDITIONAL STORAGE PROVIDED BY THE GREEN ROOF AND TREE PITS THE PEAK RELEASE RATE HAS BEEN REDUCED BELOW ALLOWABLE RELEASE RATES FOR BOTH THE 2-YR AND 10-YR STORMS. THEREFORE, NO ADDITIONAL SWM MEASURES (POND AND/OR VAULTS) SHALL BE REQUIRED TO MEET THE PFM OR LEED REQUIREMENT FOR ALLOWABLE PEAK DISCHARGE RATE, HOWEVER THE APPLICANT RESERVES THE RIGHT TO USE A VAULT(S) FOR POTENTIAL LEED REDUCE IF REQUIRED AT SITE PLAN TIME.

ALLOWABLE RELEASE RATE

PER FAIRFAX COUNTY, THE PEAK RELEASE RATE FOR THE POST-DEVELOPED 2-YR AND 10-YR DESIGN STORMS WILL BE REDUCED TO A LEVEL EQUAL TO OR LESS THAN THE EXISTING CONDICTION PEAK RELEASE RATE.

SITE AREA = 6.98 ACRES
 C2 = 5.45 IN/HR, R0 = 7.21 IN/HR
 C1 = 0.05, C10 = 0.05 (EXISTING)
 Q2 = 0.05 x 5.45 x 6.98 = 19.33 CFS
 Q10 = 0.05 x 7.21 x 6.98 = 25.13 CFS

SWM NARRATIVE

EXISTING CONDITIONS

THE 2.30 ACRE SITE CURRENTLY CONSISTS OF A PARKING LOT. THE SITE DRAINS TO THE NORTH AND SOUTH AND STORMWATER IS CONVEYED THROUGH CLOSED CONDUIT STORM SEWER SYSTEM TO AN EXISTING STORM SEWER SYSTEM THAT CROSSES INTERNATIONAL DRIVE AND EVENTUALLY DRAINAGE INTO AN EXISTING POND.

PROPOSED CONDITIONS

THIS SITE PLAN PROPOSES A MULTIFUNCTIONAL DEVELOPMENT. THE WATER QUALITY AND QUANTITY REQUIREMENTS FOR THE PROPOSED DEVELOPMENT WILL BE ACHIEVED THROUGH A COMBINATION OF URBAN BIOM-RETENTION AREAS (TREE PITS), BANY GARDENS, AND GREEN ROOFS WHICH ARE SHOWN ON THE PROVIDED PLAN. SEE SHEET C-18 FOR PLAN VIEW.

THE APPLICANT RESERVES THE RIGHT TO VARY THE NUMBER, SIZE, SHAPE, AND LOCATION OF THE DEPICTED STORMWATER MANAGEMENT FACILITIES WITH FINAL ENGINEERING, AS APPROVED BY OPDES AND IN SUBSTANTIAL CONFORMANCE WITH THE PFM.

QUALITY MEASUREMENTS

THE STORMWATER MANAGEMENT CONTROLS FOR THE PROPOSED DEVELOPMENT WILL BE ACHIEVED THROUGH A COMBINATION OF TECHNIQUES, INCLUDING THE INSTALLATION OF GREEN ROOFS AND URBAN BIOM-RETENTION AREAS (TREE PITS) TO SHAPE THE PEAK RELEASE RATE FOR THE GRAB POST DEVELOPED STORM EVENT. THIS STORMWATER PROGRAM WILL (AS CALLED FOR IN THE TYPICAL CORNER URBAN CENTER COMPENSATORY PLAN) BE EVALUATED FOR THREE DISTINCT CRITERIA. THE ORIGINAL INCLUDE AN EVALUATION FOR COMPLIANCE WITH LEED, CAPTURE/CONTROLLING THE FIRST ONE INCH OF RAINFALL, AS WELL AS THE DETENTION REQUIREMENTS OF THE PFM. IN ORDER TO DESIGN THE DETAILS OF THE PROPOSED SWM/D ELEMENTS, WE HAVE BROKEN OUR COMPUTATIONS DOWN INTO THREE PARTS.

PART I: LEED

THE FIRST TARGET FOR STORMWATER MANAGEMENT DESIGN WILL BE TO ATTEMPT TO MEET CURRENT LEED REQUIREMENTS. THE LEED BOUNDARY IS THE 2.30 ACRE RESIDENTIAL PORTION OF THIS SITE, BECAUSE THE PROPERTY THAT IS THE SUBJECT OF THIS DEVELOPMENT PLAN IS GREATER THAN 50% IMPERVIOUS IN THE EXISTING CONDICTION AND EXISTING SWM FACILITY ARE PROVIDED. THE LEED REQUIREMENT (AND THEREFORE THE TARGET FOR THIS PLAN) IS THE TOTAL VOLUME RELEASED IN THE POST-DEVELOPED CONDICTION FOR THE 2-YR, 24 HOUR STORM EVENT MUST NOT EXCEED 75% OF THE EXISTING CONDICTION VOLUME FOR THE SAME STORM EVENT.

PART II: PFM COMPLIANCE

ADDITIONALLY, PER THE FAIRFAX COUNTY STANDARD REQUIREMENT, THE PEAK RELEASE RATE FOR THE POST DEVELOPED 2-YR AND 10-YR DESIGN STORMS WILL BE REDUCED TO A LEVEL EQUAL TO OR LESS THAN THE EXISTING CONDICTION 2-YR AND 10-YR STORM PEAK RELEASE RATE FOR THE ENTIRE SITE AREA. THIS POST DEVELOPED PEAK RELEASE RATE CONTROL WILL BE ACCOMPLISHED THROUGH RUNOFF REDUCTION METHODS EMPLOYED ON THE SITE. THESE METHODS SHALL REDUCE THE VOLUME OF RAINFALL FROM THE SITE SLOAN THAT THE OUTFLOW INTRODUCED FROM THE SITE SHALL BE BELOW THE ALLOWABLE RELEASE RATES. SEE COMPUTATIONS AND DISCUSS MICRODETAILS ON SHEET C-16. DETENTION OF THE STORMWATER IN UNDERGROUND VAULT(S) WITH AN ENGINEERED OUTFLOW CONTROL DEVICE WAIVE REQUIRED AT SITE PLAN TO MEET LEED REQUIREMENTS THEREFORE THE APPLICANT RESERVES THE RIGHT TO USE SUCH METHODS IF REQUIRED.

PART III: CONSIDER CAPTURE THE FIRST 1" (TYPICAL CORNER COMPENSATORY PLAN SWM) SEE SHEET C-17 FOR COMPUTATIONS.

NOTE:

COMPUTATIONS BASED ON APPROXIMATIONS OF PROPOSED IMPERVIOUS/PERVIOUS AREA AT THE TIME OF FINAL CONSTRUCTION PLANS, BASED ON FINAL PERVIOUS/IMPERVIOUS AREAS, THE FINAL SWM VOLUME REQUIREMENTS WILL BE DETERMINED. THE MICRODETAILED SHALL BE CONSISTENT WITH THAT STORM MODEL.

ALL DRAWING SHOWN IS CONCEPTUAL AND SUBJECT TO CHANGE WITH THE FINAL CDP/TP.

ALL STORMWATER MANAGEMENT FACILITIES MUST BE PRIVATELY MAINTAINED AND A PRIVATE MAINTENANCE AGREEMENT WILL BE REQUIRED BEFORE THE CONSTRUCTION PLAN IS APPROVED.

BMP NARRATIVE


THE DEVELOPMENT PROPOSED ON THE SUBJECT SITE WILL PROVIDE A PROGNOSTICUS REMOVAL RATE OF 40% AT A MINIMUM. THIS WILL BE ACCOMPLISHED BY WAY OF LID TECHNIQUES DESCRIBED IN THE SWM NARRATIVE (BIOM-RETENTION TREE PITS AND GREEN ROOFS) OR THE USE OF STRUCTURAL FILTER SYSTEMS (POTENTIALLY LOCATED IN VAULTS WITHIN THE GARAGES OR A COMBINATION THEREOF). FINAL DESIGN LOCATION AND TYPES OF BMP SYSTEM(S) SHALL BE ESTABLISHED WITH FINAL CONSTRUCTION PLANS AND MAY BE REVISED TO ALTERNATES ALLOWED BY THE PFM.

GREENSBORO PARK PLACE


LEED/PFM SWM COMPUTATIONS

SUBMISSIONS

NO.	DATE	DESCRIPTION
10	01/14/2014	10/20/2013
11	02/12/2013	11/20/2013
12	03/11/2013	12/20/2013
13	04/11/2013	01/20/2014
14	05/11/2013	02/20/2014
15	06/11/2013	03/20/2014
16	07/11/2013	04/20/2014
17	08/11/2013	05/20/2014
18	09/11/2013	06/20/2014
19	10/11/2013	07/20/2014
20	11/11/2013	08/20/2014
21	12/11/2013	09/20/2014
22	01/11/2014	10/20/2014
23	02/11/2014	11/20/2014
24	03/11/2014	12/20/2014
25	04/11/2014	01/20/2015
26	05/11/2014	02/20/2015
27	06/11/2014	03/20/2015
28	07/11/2014	04/20/2015
29	08/11/2014	05/20/2015
30	09/11/2014	06/20/2015
31	10/11/2014	07/20/2015
32	11/11/2014	08/20/2015
33	12/11/2014	09/20/2015
34	01/11/2015	10/20/2015
35	02/11/2015	11/20/2015
36	03/11/2015	12/20/2015
37	04/11/2015	01/20/2016
38	05/11/2015	02/20/2016
39	06/11/2015	03/20/2016
40	07/11/2015	04/20/2016
41	08/11/2015	05/20/2016
42	09/11/2015	06/20/2016
43	10/11/2015	07/20/2016
44	11/11/2015	08/20/2016
45	12/11/2015	09/20/2016
46	01/11/2016	10/20/2016
47	02/11/2016	11/20/2016
48	03/11/2016	12/20/2016
49	04/11/2016	01/20/2017
50	05/11/2016	02/20/2017
51	06/11/2016	03/20/2017
52	07/11/2016	04/20/2017
53	08/11/2016	05/20/2017
54	09/11/2016	06/20/2017
55	10/11/2016	07/20/2017
56	11/11/2016	08/20/2017
57	12/11/2016	09/20/2017
58	01/11/2017	10/20/2017
59	02/11/2017	11/20/2017
60	03/11/2017	12/20/2017
61	04/11/2017	01/20/2018
62	05/11/2017	02/20/2018
63	06/11/2017	03/20/2018
64	07/11/2017	04/20/2018
65	08/11/2017	05/20/2018
66	09/11/2017	06/20/2018
67	10/11/2017	07/20/2018
68	11/11/2017	08/20/2018
69	12/11/2017	09/20/2018
70	01/11/2018	10/20/2018
71	02/11/2018	11/20/2018
72	03/11/2018	12/20/2018
73	04/11/2018	01/20/2019
74	05/11/2018	02/20/2019
75	06/11/2018	03/20/2019
76	07/11/2018	04/20/2019
77	08/11/2018	05/20/2019
78	09/11/2018	06/20/2019
79	10/11/2018	07/20/2019
80	11/11/2018	08/20/2019
81	12/11/2018	09/20/2019
82	01/11/2019	10/20/2019
83	02/11/2019	11/20/2019
84	03/11/2019	12/20/2019
85	04/11/2019	01/20/2020
86	05/11/2019	02/20/2020
87	06/11/2019	03/20/2020
88	07/11/2019	04/20/2020
89	08/11/2019	05/20/2020
90	09/11/2019	06/20/2020
91	10/11/2019	07/20/2020
92	11/11/2019	08/20/2020
93	12/11/2019	09/20/2020
94	01/11/2020	10/20/2020
95	02/11/2020	11/20/2020
96	03/11/2020	12/20/2020
97	04/11/2020	01/20/2021
98	05/11/2020	02/20/2021
99	06/11/2020	03/20/2021
100	07/11/2020	04/20/2021
101	08/11/2020	05/20/2021
102	09/11/2020	06/20/2021
103	10/11/2020	07/20/2021
104	11/11/2020	08/20/2021
105	12/11/2020	09/20/2021
106	01/11/2021	10/20/2021
107	02/11/2021	11/20/2021
108	03/11/2021	12/20/2021
109	04/11/2021	01/20/2022
110	05/11/2021	02/20/2022
111	06/11/2021	03/20/2022
112	07/11/2021	04/20/2022
113	08/11/2021	05/20/2022
114	09/11/2021	06/20/2022
115	10/11/2021	07/20/2022
116	11/11/2021	08/20/2022
117	12/11/2021	09/20/2022
118	01/11/2022	10/20/2022
119	02/11/2022	11/20/2022
120	03/11/2022	12/20/2022
121	04/11/2022	01/20/2023
122	05/11/2022	02/20/2023
123	06/11/2022	03/20/2023
124	07/11/2022	04/20/2023
125	08/11/2022	05/20/2023
126	09/11/2022	06/20/2023
127	10/11/2022	07/20/2023
128	11/11/2022	08/20/2023
129	12/11/2022	09/20/2023
130	01/11/2023	10/20/2023
131	02/11/2023	11/20/2023
132	03/11/2023	12/20/2023
133	04/11/2023	01/20/2024
134	05/11/2023	02/20/2024
135	06/11/2023	03/20/2024
136	07/11/2023	04/20/2024



PLAN VIEW




SECTION A-A

LEED REUSE VAULT TYPICAL DETAIL
NOT TO SCALE

* ONE OUTFLOW PIPE PER VAULT LOCATION TO BE DETERMINED
* NEW FINAL ENGINEERING OUTFALL MAY BE REQUIRED
* FINAL NUMBER AND LOCATION OF INFLOW PIPES PER MEP

NOTES:

- 1) FINAL NUMBER, SHAPE, SIZE, LOCATION AND DESIGN OF STORMWATER MANAGEMENT VAULTS ARE SUBJECT TO CHANGE AT THE TIME OF FINAL ENGINEERING.
- 2) SUPPORT AND REINFORCING FOR VAULTS PER STRUCTURAL ENGINEERING PLANS.



SECTION B-B

CONNECTION TO PUMP
DESIGN AND DETAILS PER MEP/STRUCTURAL

CONNECTION TO PUMP
DESIGN AND DETAILS PER MEP/STRUCTURAL

1/2" DIA.
OUTFLOW PIPES
SIZE TO BE DETERMINED AT
FINAL ENGINEERING - 15' FOR
SINGLE VAULT ROUTING

SUMP PIT FOR PUMP
DESIGN AND DETAILS
PER MEP/STRUCTURAL

SUMP PIT FOR PUMP
DESIGN AND DETAILS
PER MEP/STRUCTURAL

GARAGE FLOOR ABOVE

GARAGE FLOOR (LOWEST LEVEL)

BAFFLE WALL

ACCESS HATCH TO FLOOR ABOVE
(BOLTED SHUT AND SEALED)

ACCESS HATCH TO FLOOR ABOVE
(BOLTED SHUT AND SEALED)

INFLOW PIPES

CONNECTION TO PUMP
DESIGN AND DETAILS PER MEP/STRUCTURAL


CONNECTION TO PUMP
DESIGN AND DETAILS PER MEP/STRUCTURAL

DESIGN AND DETAILS
PER MEP PLAN
TO BUILDING
WATER SYSTEM

DESIGN AND DETAILS
PER MEP PLAN
TO BUILDING
WATER SYSTEM

VA DCB STORMWATER DESIGN SPECIFICATION NO. 3

VEGETATED ROOF



CROSS SECTION VIEW (INTS)

Figure 3.1 Typical Section - Extensive Vegetated Roof
(Source: Northern VA Regional Commission)

Version 2.1, 2010

Page 4 of 17

TYPICAL EXTENSIVE GREEN ROOF DETAIL

VA DCB STORMWATER DESIGN SPECIFICATION NO. 3

BION TENTION




Figure 3.4.3 Example Tree Pit Details

TYPICAL BIO-RETENTION (TREE PIT) DETAIL





Figure 3.6. Typical Detail of Stormwater Basin/Level 2 Change

Version 1.0, March 1, 2011

Page 3 of 14

TYPICAL RAIN GARDEN DETAIL



NOTE: CONTRACTOR TO COORDINATE WITH PAVING SUPPLIER TO PROVIDE A PERFORATED PAVEMENT IN THE LOCATIONS OVER THE BLAD DRAINS TO FACILITATE DRAIN LOCATION & MAINTENANCE.

INTENSIVE (> 6\"/>

VA DCB STORMWATER DESIGN SPECIFICATION NO. 3

VEGETATED ROOF

BION TENTION

TYPICAL EXTENSIVE GREEN ROOF DETAIL

TYPICAL BIO-RETENTION (TREE PIT) DETAIL

TYPICAL RAIN GARDEN DETAIL

INTENSIVE (> 6\"/>

STORMWATER MANAGEMENT DETAILS

GREENSBORO PARK PLACE

PROVIDENCE DISTRICT

FARFAX COUNTY, VIRGINIA

SUBMISSIONS

TITLE


DATE

SCALE

PROJECT/TITLE NO.

SHEET NO.

C-18




FUTURE IMPROVEMENTS ON THIS SITE ARE BY OTHERS

FUTURE IMPROVEMENTS ON THIS SITE ARE BY OTHERS

- LEGEND**
- AREA OF INTENSIVE GREEN ROOF (>8" DEPTH)
 - AREA OF EXTENSIVE GREEN ROOF (<8" DEPTH)
 - AREA TO BIO-RETENTION TREE PITS
 - OFFSITE (CONTROLLED) AREA
 - ADDITIONAL SITE TO BIO-RETENTION (RAIN GARDEN)
 - BIO-RETENTION TREE PITS

SWM NOTES:

- IT IS ASSUMED THAT THE EXTENSIVE ROOF AREA IS TO DRAIN TO THE INTENSIVE GREEN ROOF LOCATED ON THE TOWERS AND PODIUM
- THE SITE AREA (2.30 ADDRESS) IS ONLY THE AREA OF THE RESIDENTIAL BUILDING AND THE CENTERING OF GREENBORO PARK, WVA



VIVA
VIVA ARCHITECTURE & INTERIORS, INC.
1000 W. MARKET STREET, SUITE 100, GREENSBORO, NC 27401
TEL: 336.833.1111 FAX: 336.833.1112


PROJECT TEAM
OWNER: GREENSBORO PARK PROPERTY OWNER LLC
ARCHITECT: VIVA ARCHITECTURE
LANDSCAPE ARCHITECT: VIVA ARCHITECTURE & INTERIORS, INC.
ENGINEER: J. B. ASSOCIATES, INC.

GREENSBORO PARK PLACE
PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA

STORMWATER MANAGEMENT MAP

SUBMISSIONS	
NO.	DATE
1	1/16/2014
2	1/16/2014
3	1/16/2014
4	1/16/2014
5	1/16/2014
6	1/16/2014
7	1/16/2014
8	1/16/2014
9	1/16/2014
10	1/16/2014
11	1/16/2014
12	1/16/2014
13	1/16/2014
14	1/16/2014
15	1/16/2014
16	1/16/2014
17	1/16/2014
18	1/16/2014
19	1/16/2014
20	1/16/2014
21	1/16/2014
22	1/16/2014
23	1/16/2014
24	1/16/2014
25	1/16/2014
26	1/16/2014
27	1/16/2014
28	1/16/2014
29	1/16/2014
30	1/16/2014
31	1/16/2014
32	1/16/2014
33	1/16/2014
34	1/16/2014
35	1/16/2014
36	1/16/2014
37	1/16/2014
38	1/16/2014
39	1/16/2014
40	1/16/2014
41	1/16/2014
42	1/16/2014
43	1/16/2014
44	1/16/2014
45	1/16/2014
46	1/16/2014
47	1/16/2014
48	1/16/2014
49	1/16/2014
50	1/16/2014
51	1/16/2014
52	1/16/2014
53	1/16/2014
54	1/16/2014
55	1/16/2014
56	1/16/2014
57	1/16/2014
58	1/16/2014
59	1/16/2014
60	1/16/2014
61	1/16/2014
62	1/16/2014
63	1/16/2014
64	1/16/2014
65	1/16/2014
66	1/16/2014
67	1/16/2014
68	1/16/2014
69	1/16/2014
70	1/16/2014
71	1/16/2014
72	1/16/2014
73	1/16/2014
74	1/16/2014
75	1/16/2014
76	1/16/2014
77	1/16/2014
78	1/16/2014
79	1/16/2014
80	1/16/2014
81	1/16/2014
82	1/16/2014
83	1/16/2014
84	1/16/2014
85	1/16/2014
86	1/16/2014
87	1/16/2014
88	1/16/2014
89	1/16/2014
90	1/16/2014
91	1/16/2014
92	1/16/2014
93	1/16/2014
94	1/16/2014
95	1/16/2014
96	1/16/2014
97	1/16/2014
98	1/16/2014
99	1/16/2014
100	1/16/2014

DES: PCC DWP: JDA
SCALE: AS SHOWN
PROJECT/FILE NO: V5015X
SHEET NO: C-19



LEGEND

	COFFER/UNDERGROUND GARAGE
	POULTRY/STABLE
	PERVIOUS AREA

PROJECT NO.	150978
SHEET NO.	C-20
SCALE:	AS SHOWN
DATE:	08/14/2013
DESIGNED BY:	DRM, JAM
CHECKED BY:	DRM, JAM
DATE:	08/14/2013
PROJECT:	GREENSBORO PARK PLACE
CLIENT:	PROPERTY OWNER LLC
ARCHITECT:	WGC ARCHITECTURE
LANDSCAPE ARCHITECT:	CSG LANDSCAPE ARCHITECTURE
TRANSPORTATION ENGINEER:	MILLS & ASSOCIATES, INC.




LAND COVER MAP

GREENSBORO PARK PLACE


PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA

VIVA

OWNER: GREENSBORO PARK PROPERTY OWNER LLC
 ATTORNEY: COOLEY LLP
 ARCHITECT: WGC ARCHITECTURE
 LANDSCAPE ARCHITECT: CSG LANDSCAPE ARCHITECTURE
 TRANSPORTATION ENGINEER: MILLS & ASSOCIATES, INC.




02 SECTION D-D
 Office Building 2 (180 Greensboro Drive)




01 SECTION C-C
 Office Building 1 (200 Greensboro Drive)



- Existing office building height is based on average site grade per sheet C-2
 - Building Sections shown in this sheet are diagrammatic representations of existing conditions
 - Architectural plans, elevations, illustrations, materials and heights may be adjusted or modified to conform to CDP and FDP approval as a result of final architectural and engineering design without requiring CDPA, FDPA, PCA or other zoning approval provided it remains in substantial conformance with that shown on the CDP and FDP
 - See civil landscape drawings for proposed site information



02 SECTION B-B
1/32" = 1'-0"



01 SECTION A-A
1/32" = 1'-0"



- Number of floors may be increased to 26 floors (Residential Building A) and 22 floors (Residential Building B) per street C-2.
 - Architectural plans, elevations, restorations, materials and heights may be adjusted or modified subsequent to CDP and FDP approval as a result of final architectural and engineering design without requiring CDPA, FDPA, PCA or other zoning approval, provided it remains in substantial conformance with that shown on the CDP and FDP.
 - See civil/landscape drawings for proposed site information.

VIKA

VIKA ARCHITECTURE & INTERIOR DESIGN


1000 WEST GREENSBORO DRIVE
 GREENSBORO, NC 27401
 TEL: 336.853.1111
 FAX: 336.853.1112
 WWW.VIKAA.COM

GREENSBORO PARK PLACE

PROPOSED BUILDING SECTIONS

DATE: 11/14/2014
 DRAWN BY: J. HARRIS
 CHECKED BY: J. HARRIS
 PROJECT NO: 14-001


A-03b



March 21, September 21 - 9:00 am




June 21 - 9:00 am



December 21 - 9:00 am




March 21, September 21 - 12:00 pm




June 21 - 12:00 pm




December 21 - 12:00 pm



March 21, September 21 - 3:00 pm




June 21 - 3:00 pm




December 21 - 3:00 pm


* Architectural plans, elevations, illustrations, materials and heights may be adjusted or modified subsequent to CDP and FDP approval as a result of final architectural and engineering design without requiring CDPA, FDPA, PCA or other zoning approval provided it remains in substantial conformance with that shown on the CDP and FDP. See and landscape drawings for proposed site information.




01 SOUTH ELEVATION - RESIDENTIAL BUILDING A



02 NORTH ELEVATION - RESIDENTIAL BUILDING A



03 SOUTH ELEVATION - RESIDENTIAL BUILDING B



04 NORTH ELEVATION - RESIDENTIAL BUILDING D



- MATERIALS NOTE:**
- 1 ARCHITECTURAL PANEL SYSTEMS MAY INCLUDE BUT ARE NOT LIMITED TO
 - 2 METAL PANEL SYSTEM
 - 3 GLASS FIBER REINFORCED CONCRETE PANEL SYSTEM
 - 4 FIBER CEMENT PANEL SYSTEM
 - 5 RESIN-BASE COMPOSITE PANEL SYSTEM

- Architectural plans, elevations, illustrations, materials and heights may be adjusted or modified subsequent to CDP and FDP approval as a result of final architectural and engineering design without requiring CDP, FDP, PCA or other zoning approval provided it remains in substantial conformance with that shown on the CDP and FDP.
- See civil landscape drawings for proposed site information.






Perspectives show "CDP/FDP site condition" with "Results Road Option B or C"
 Architectural plans, elevations, illustrations, materials and heights may be adjusted or
 modified subsequent to CDP and FDP approval as a result of final architectural and
 engineering design without requiring CDP, FDP, PCA or other zoning approval
 provided it remains in substantial conformance with that shown on the CDP and FDP
 Plan and landscape drawings for proposed site information

VIVA
 ARCHITECTURAL
 1000 ...
 ...
 ...

GREENSBORO PARK PLACE
 ARCHITECTURAL ...
 ...

PERSPECTIVES

...
 ...
 ...




- Perspectives show "CDP/CP" site condition, with "Routinized Road District II" or "C" - Architectural plans, elevations, sections, materials, and heights may be adjusted or modified subsequent to CDP and CP approval at a date of final architectural and engineering drawings. Final construction documents will be prepared and provided to the City of Greensboro for review and approval. For more information, contact the City of Greensboro Planning Department at 333 North Elm Street, Greensboro, NC 27401.

<p> 1.00 SITE PLAN 2.00 ARCHITECTURAL ELEVATIONS 3.00 ARCHITECTURAL SECTIONS 4.00 ARCHITECTURAL DETAILS 5.00 MECHANICAL, ELECTRICAL, PLUMBING (MEP) PLAN 6.00 STRUCTURAL PLAN 7.00 LANDSCAPE ARCHITECTURE PLAN 8.00 SIGNAGE PLAN 9.00 CONSTRUCTION SPECIFICATIONS 10.00 PERMITS AND REGULATORY REQUIREMENTS </p>	<p> 11.00 CONSTRUCTION SCHEDULE 12.00 BUDGET AND FINANCING PLAN 13.00 ENVIRONMENTAL IMPACT STATEMENT 14.00 HISTORIC PRESERVATION REVIEW 15.00 TRAFFIC IMPACT STUDY 16.00 UTILITIES AND INFRASTRUCTURE PLAN 17.00 PUBLIC PARTICIPATION PLAN 18.00 FINAL REPORT AND RECOMMENDATIONS </p>
---	---

PERSPECTIVES
GREENSBORO PARK PLACE
 333 NORTH ELM STREET
 GREENSBORO, NC 27401

ARCHITECT: [Faint text]
 ENGINEER: [Faint text]
 DATE: [Faint text]





WVA
 ARCHITECTURAL FIRM
 1000 ...
 ...




...
 ...
 ...

GREENSBORO PARK PLACE
 ...
 ...

PERSPECTIVES

...
 ...
 ...

** Perspectives show "CDP/FDP site condition" with "Plan's Road Option B or C"
 - Architectural plans, elevations, illustrations, materials and heights may be adjusted or
 modified subsequent to CDP and FDP approval as a result of final architectural and
 engineering design without requiring CDPA, FDPA, PCA or other zoning approval
 provided it remains in substantial conformance with that shown on the CDP and FDP
 Site and landscape drawings for proposed site information.*





- Perspectives show "CDP/FDP site condition" with "Results Phase Option B or C".
 Architectural plans, elevations, illustrations, materials and heights may be adjusted or
 modified subsequent to CDP and FDP approval as a result of final architectural and
 engineering design without requiring CDPA, FDPA, PCA or other zoning approval
 provided it remains in substantial conformance with that shown on the CDP and FDP.
 See civil landscape drawings for proposed site information.

VIVA
 ARCHITECTURAL FIRM

GREENSBORO PARK PLACE
 GREENSBORO, NC

PERSPPECTIVES

A-11



VISS
 VISUALIZATION & INTERACTIVE SERVICES
 1000 W. 10th Street, Suite 100
 Greensboro, NC 27403
 Phone: 336.275.1111
 Fax: 336.275.1112
 www.viss.com





Architectural rendering of Greensboro Park Place, showing the building facade and surrounding landscape.

GREENSBORO PARK PLACE
 ARCHITECTURAL RENDERING

PERSPECTIVES

Architectural rendering of Greensboro Park Place, showing the building facade and surrounding landscape.

- Perspectives show "CDP/FDP site condition" with "Results Road Option B or C"
 - Architectural plans, elevations, illustrations, materials and heights may be adjusted or modified subsequent to CDP and FDP approval as a result of final architectural and engineering design without requiring CDP, FCPA, PCA or other zoning approval provided it remains in substantial compliance with that shown on the CDP and FDP. See civil landscape drawings for proposed site information.



Architectural plans, elevations, sections, materials and heights may be adjusted or modified subsequent to CDP and FGP approval as a matter of local architectural and engineering practice. All construction shall be in accordance with the CDP and FGP. See the "Conditions" page for the project for more information.

Scale: 1/4" = 1'-0"
 Date: 10/15/15
 A-15

MODEL PHOTOS


GREENSBORO PARK PLACE

1000 PARK PLACE
 GREENSBORO, NC 27401

1000 PARK PLACE
 GREENSBORO, NC 27401


VIVA

1000 PARK PLACE
 GREENSBORO, NC 27401



LEGENDS

- RAIN GARDEN
- BIO-RETENTION TREE PIT
- SHRUB MASS
- GROUNDCOVER & PERENNIAL
- SEAT WALL
- PAVER TYPE 'A'
- PAVER TYPE 'B'
- SCORED CONCRETE
- EXTENSIVE GREEN ROOF
- EXISTING TREE
- LIMITS OF CLEARING & GRADING



CDP/FDP TREE SCHEDULE

KEY	Botanical Names	Common Name	Size	Type	10yr Tree Cover Canopy
STREET TREES (CATEGORY IV)					
	Acer rubrum 'October Glory'	October Glory Red Maple	1' cal	SHB	150
	Platanus acerifolia	Londes Plant Tree	1' cal	SHB	250
	Quercus falcata	Southern Oak Oak	1' cal	SHB	240
	Vitex americana 'Valley Forge'	'Valley Forge' American Elm	1' cal	SHB	200
sub-total					23,750
ORNAMENTAL TREES (CATEGORY II)					
	Aster laevis	Downy Aster	1' cal	SHB	125
	Cornus canadensis	Eastern Spicebush	1' cal	SHB	125
	Euonymus alatus	Winged Spindle Tree	1' cal	SHB	125
	Albizia julibrissin	Star Magnolia	1' cal	SHB	125
sub-total					325
ORNAMENTAL TREES IN ELEVATED DECK (CATEGORY II)					
	Amelanchier alnifolia	Downy Serviceberry	1' cal	SHB	125
	Cornus canadensis	Eastern Spicebush	1' cal	SHB	125
	Cornus kousa	Kousa Dogwood	1' cal	SHB	125
	Magnolia stellata	Star Magnolia	1' cal	SHB	125
sub-total					325
EVERGREEN TREES (CATEGORY I)					
	Pinus strobus	White Pine	3' cal	SHB	75
	Thuja occidentalis	Eastern Arborvitae	3' cal	SHB	75
	Juniperus horizontalis 'Carolin'	Carolina Juniper	3' cal	SHB	75
sub-total					225
GROUNDS SITE AREA:					30,000 sq ft
AREA OF 10-YEAR TREE CANOPY REQUIRED (10% gross site):					33,581 sq ft
TOTAL TREE COVER PROVIDED BY PLANTING:					23,675 sq ft

NOTE:
Species in the plant schedule are indicative of the trees which will be selected for the final planting schedule.
Species may vary depending on final design and availability.

RECOMMENDED PLANT LIST FOR BIORETENTION FACILITIES

GRASSES/SEDGES/RUSHES	PERENNIALS/GROUNDCOVERS
SEDGES/SEDGES/RUSHES	PERENNIALS/GROUNDCOVERS
Andropogon gerardii	Asclepias tuberosa
Andropogon virginicus	Aster laevis
Chrysopsis humilis	Cornus verticillata
Cyperus sparganium	Eupatorium altissimum
Lygodes spectabilis	Impatiens
Tripsacum daniellii	Monarda
	Verbena
	Yucca
	Zinnia
	Black Chokeberry
	Blueberry
	Cardinal Flower
	Common Milkweed
	Daylily
	Goldenrod
	Joe-Pye-Weed
	Red Top
	Shrimp Plant
	Spotted Deadnettle
	Virginia Creeper
	Wildflower
	Yarrow
	Zinnia

- GENERAL NOTES:**
- NO PERIPHERAL AND INTERIOR PARKING LOT LANDSCAPE SHALL BE PROVIDED FOR C.D.P.
 - STREET TREE AMENITY SOIL PANEL AND STRUCTURAL CELL DETAILS, SEE SHEET L-7A.
 - TREE ROOT ZONE SHALL MEET MINIMUM SOIL VOLUME STATED IN THE TYSON'S URBAN DESIGN GUIDELINES.
 - IT IS THE INTENT OF THIS DESIGN TO PRESERVE THE EXISTING TREES ALONG GREENSBORO DRIVE. AS SHOWN; HOWEVER, SHOULD THEIR LONG-TERM VIABILITY BECOME QUESTIONABLE DURING DEVELOPMENT OF THE FINAL ENGINEERED SITE PLAN, THE APPLICANT WILL WORK DILIGENTLY WITH FAIRFAX COUNTY URBAN FOREST MANAGEMENT TO DEVELOP AND IMPLEMENT A PLAN WHICH REPLACES THE TREES IN-KIND, AND IN THE SAME (OR ALTERNATIVE) LOCATION.



NOTE:
THE PLAN AND IMAGERY SHOWN MAY BE MODIFIED WITH FINAL ENGINEERING AND DESIGN, PROVIDED THAT THE GENERAL DESIGN QUALITY AND CHARACTERISTICS ARE IN SUBSTANTIAL CONFORMANCE WITH THAT SHOWN.

1819 GALLONS ROAD, SUITE 110
VIENNA, VIRGINIA 22182
703-821-3048

VKA
VIRGINIA KIMBERLY ARCHITECTS & SURVEYORS & LANDSCAPE ARCHITECTS

PROJECT TEAM
OWNER: FAIRFAX COUNTY, VA
ARCHITECT: VKA ARCHITECTS & SURVEYORS
LANDSCAPE ARCHITECT: LSG LANDSCAPE ARCHITECTURE
TRANSPORTATION: WELLS & ASSOCIATES, INC.

GREENSBORO PARK PLACE
PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA

LANDSCAPE PLANTING PLAN


SUBMISSIONS

1	10/15/2011	10/15/2011
2	10/20/2011	10/20/2011
3	10/25/2011	10/25/2011
4	10/30/2011	10/30/2011
5	11/05/2011	11/05/2011
6	11/10/2011	11/10/2011
7	11/15/2011	11/15/2011
8	11/20/2011	11/20/2011
9	11/25/2011	11/25/2011
10	12/01/2011	12/01/2011

DATE: NOVEMBER 2011
DCA: DMN

SCALE: AS SHOWN

SHEET NO. L-2a



- PROPOSED PARKING COMPOUND AREA 85,651 SF
- PROPOSED INTERIOR PARKING LOT TREES 78 CATEGORY IV TREES (TYP)

PARKING COMPOUND CANOPY AREA EXHIBIT
1" = 50'-0"





Table 12.13 Interior Parking Lot Landscaping Calculations		Remarks
Area to be counted (SF) =	84,342	square feet
Interior Landscaping Required (5%) =	4,217	square feet
Total Shade Tree Canopy Provided (178 trees @ 250 sf ea.) =	19,500	Counting benefit credits
Total Area Required (SF) =	4,217	5%
Total Area Provided (SF) =	19,500	11%

Table 12.10 Preliminary 10-Year Tree Canopy Calculation Worksheet		January 10, 2014
A	Tree Preservation Target and Statement	Totals
A.1	Place the Tree Preservation Target calculations and statement here preceding the 10-year tree canopy	C-4 see § 12-05-10.2 for list of required elements and 100% sheet
B. Tree Canopy Requirements		
B.1	Specify gross site area (SF) =	303,800 § 12-05-11.1A
B.2	Subtract area dedicated to roads, road frontage (SF) =	1,840 12-05-11.1B
B.3	Subtract area of exemptions (SF) =	0 12-05-11.1C(4)
B.4	Identify the site's zoning and/or use	PTC Square feet
B.5	Percentage of 10-year tree canopy required =	10% § 12-05-10.1 and Table 9.1
B.6	Area of 10-year Tree Canopy Required (B.4 x B.5)(SF) =	30,380 Square feet
B.8	Notification of 10-year Tree Canopy Requirements requested?	NO Yes or No
B.9	If "Yes" = yes, then list the requested notification	- Sheet number
C. Tree Preservation		
C.1	Tree Preservation Target (C-4) =	0 Square Feet
C.2	Total canopy area meeting standards of § 12-05-10.3 =	0 Square Feet
C.3	C 2 x 1.0(SF) =	0 § 12-05-10.3B
C.4	C 4 x 1.5(SF) =	0 Square Feet
C.5	C 4 x 1.5(SF) =	0 § 12-05-10.3B(1)
C.6	Total of canopy area provided by "Highway," "Marginal," "Spaceman" or "Street" trees (SF) =	0 Square Feet
C.7	Canopy area of trees within resource Protection Area and 1-year tree terms (SF) =	0 § 12-05-10.3B(2)
C.8	Canopy area of trees within resource Protection Area and 1-year tree terms (SF) =	0 Square Feet
C.9	C 8 x 1.0 (SF) =	0 § 12-05-10.3C(1)
C.10	Total of C.3, C.5, C.7 and C.9 =	23,343 Area of C.10 is as than § 7 remainder of requirement must be met through tree planting - go to D
D. Tree Planting		
D.1	Area of canopy to be met through tree planting (D 7-C10) =	6,870 Square feet
D.2	Area of canopy planted for air quality benefits =	0 Square feet
D.3	D 2 x 1.5 (SF) =	0 § 12-05-10.4B(1)
D.4	Area of canopy planted for energy conservation =	0 Square feet
D.5	D 4 x 1.5 (SF) =	0 § 12-05-10.4B(2)
D.6	Area of canopy planted for water usage benefits =	0 Square feet
D.7	D 6 x 1.25 (SF) =	0 § 12-05-10.4B(3)
D.8	Area of canopy planted for storm water benefits =	0 Square feet
D.9	D 8 x 1.5 (SF) =	0 § 12-05-10.4B(4)
D.10	Area of canopy provided by native trees =	0 Square feet
D.11	Area of canopy provided by native trees =	0 Square feet
D.12	Area of canopy provided by native trees =	0 Square feet
D.13	Area of canopy provided by native trees =	0 Square feet
D.14	Area of canopy provided by native trees =	0 Square feet
D.15	Area of canopy provided by native trees =	0 Square feet
D.16	Percentage of D 14 represented by D 15 =	0 Must not exceed 50% of D 14
D.17	Area of canopy to be planted with no benefit credits =	0 Square feet
D.18	Total of canopy area provided through tree planting =	0 Square feet
D.19	Is an offset planting relief requested?	NO Yes or No
D.20	Tree Bank or Tree Fund?	NO Yes or No § 12-05-12
D.21	Canopy area requested to be provided through offset bank = or tree fund =	0 Square feet
D.22	Amount to be deposited into the Tree Preservation and Planting Fund =	NA
E. 10-year Tree Canopy Provided		
E.1	Total of canopy area provided through tree preservation (C 10) =	23,343 Square feet
E.2	Total of canopy area provided through tree planting (D 18) =	32,675 Square feet
E.3	Total of canopy area provided through offset mechanisms (D 21) =	0 Square feet
E.4	Total of 10-year Tree Canopy Provided (SF) =	56,018 Total of E.1 through E.3, area should meet or exceed area in B.7




1118 GALLONS ROAD, SUITE 110
VENNA, VIRGINIA 22182
703-621-2045


GREENSBORO PARK PLACE
 TREE CANOPY COMPUTATIONS
 SUBMISSIONS
 DATE: NOVEMBER 2012
 DES. DWN.
 SCALE: AS SHOWN
 PROJECT/FILE NO. LSG-NO-110225-00
 SHEET NO. L-2b




1 STREETScape SECTION
1/8"=1'-0"




2 STREETScape SECTION
1/8"=1'-0"




3 STREETScape SECTION
1/8"=1'-0"



5 STREETScape SECTION
1/8"=1'-0"



KEY MAP



4 STREETScape SECTION
1/8"=1'-0"

NOTE:
THE PLAN AND IMAGERY SHOWN MAY BE MODIFIED WITH FINAL ENGINEERING AND DESIGN. PROVIDED THAT THE GENERAL DESIGN QUALITY AND CHARACTERISTICS ARE IN SUBSTANTIAL CONFORMANCE WITH THAT SHOWN.



LSG LANDSCAPE ARCHITECTURE
1818 GALLOWAY ROAD, SUITE 118
VIENNA, VIRGINIA 22182
703-421-2045

VFA
VIRGINIA FIRM ARCHITECTS & SURVEYORS & SUSTAINABLE DESIGN
OWNER: GREENSBORO PARK
PROVIDENCE DISTRICT
ARCHITECT: W&J ARCHITECTURE
LANDSCAPE ARCHITECT: LSG LANDSCAPE ARCHITECTURE
TRANSPORTATION: W&J ARCHITECTURE
WWW.VFA.COM
480 GREENSBORO BLVD. SUITE 500 # FLOOR CORNER, WICHITA 3102
(316) 441-7900 # FAX (316) 741-7297

PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA


GREENSBORO PARK PLACE

TYPICAL SITE
STREETScape
SECTIONS

SUBMISSIONS

NO.	DATE	DESCRIPTION
1	07/06/2014	CDP #12/18/13
2	07/20/2014	
3	07/20/2014	
4	07/20/2014	
5	07/20/2014	
6	07/20/2014	
7	07/20/2014	
8	07/20/2014	
9	07/20/2014	
10	07/20/2014	

DES. DWN.
SCALE: AS SHOWN
PROJECT/FILE NO. LSC NO.11023.00
SHEET NO. L-5



POCKET PARK I


A FLEXIBLE OPEN SPACE WITH OPEN LAWN AREAS, SERVING AS THE PASSIVE RECREATION ACTIVITIES OF A NEIGHBORHOOD, SERVES AS A FOCAL POINT AND UNIQUE PLACE-MAKING SPACES FOR CASUAL USE AS WELL AS COMMUNITY EVENTS, MAY INCLUDE SUCH ITEMS AS:

- SEATING AREAS
- BOCCIE BALL COURT
- CLIMBABLE ART FOR TOTS
- SEASONAL DECORATIONS AND PROGRAMS
- PICKNICKING AND GATHERING SPACE
- MULTI-PURPOSE LAWN AREA
- SUNBATHING
- WAYFINDING SYSTEM FOR THE SITE APPLICATION
- GAME TABLES

NOTE:



THE PLAN AND IMAGERY SHOWN MAY BE MODIFIED WITH FINAL ENGINEERING AND DESIGN, PROVIDED THAT THE GENERAL DESIGN QUALITY AND CHARACTERISTICS ARE IN SUBSTANTIAL CONFORMANCE WITH THAT SHOWN.

REFERENCE IMAGES




A PARK PLACE STREET SECTION
1/8"=1'-0"

POCKET PARK I
1/16"=1'-0"



B POCKET PARK I
1/8"=1'-0"



3 CLIMBABLE ART FOR TOTS
1/8"=1'-0"

LSG LANDSCAPE ARCHITECTURE
PROVIDERS & PLANNERS & LANDSCAPE ARCHITECTS & SURVEYORS & SUSTAINABLE DESIGN
WVA, VIRGINIA, LLC
8180 GREENSBORO DRIVE, SUITE 200 • FARMERS CORNER, VIRGINIA, 22102
(551) 442-1100 • FAX (551) 442-1191
WWW.LSG-VA.COM

GREENSBORO PARK PLACE
OWNER: GREENSBORO PARK
PROPERTY OWNER, LLC
ATTORNEY: COOLEY LLP
ARCHITECT: WDG ARCHITECTURE
LANDSCAPE ARCHITECTURE:
LSG LANDSCAPE ARCHITECTURE
WVA, VIRGINIA, LLC
WOLFE & ASSOCIATES, INC.

GREENSBORO PARK PLACE
PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA


POCKET PARK I

SUBMISSIONS	
NO.	TYPE
1	SCHEMATIC
2	PRELIMINARY
3	CONCEPT
4	SCHEMATIC
5	PRELIMINARY
6	CONCEPT
7	SCHEMATIC
8	PRELIMINARY
9	CONCEPT
10	SCHEMATIC
11	PRELIMINARY
12	CONCEPT
13	SCHEMATIC
14	PRELIMINARY
15	CONCEPT
16	SCHEMATIC
17	PRELIMINARY
18	CONCEPT
19	SCHEMATIC
20	PRELIMINARY
21	CONCEPT
22	SCHEMATIC
23	PRELIMINARY
24	CONCEPT
25	SCHEMATIC
26	PRELIMINARY
27	CONCEPT
28	SCHEMATIC
29	PRELIMINARY
30	CONCEPT
31	SCHEMATIC
32	PRELIMINARY
33	CONCEPT
34	SCHEMATIC
35	PRELIMINARY
36	CONCEPT
37	SCHEMATIC
38	PRELIMINARY
39	CONCEPT
40	SCHEMATIC
41	PRELIMINARY
42	CONCEPT
43	SCHEMATIC
44	PRELIMINARY
45	CONCEPT
46	SCHEMATIC
47	PRELIMINARY
48	CONCEPT
49	SCHEMATIC
50	PRELIMINARY
51	CONCEPT
52	SCHEMATIC
53	PRELIMINARY
54	CONCEPT
55	SCHEMATIC
56	PRELIMINARY
57	CONCEPT
58	SCHEMATIC
59	PRELIMINARY
60	CONCEPT
61	SCHEMATIC
62	PRELIMINARY
63	CONCEPT
64	SCHEMATIC
65	PRELIMINARY
66	CONCEPT
67	SCHEMATIC
68	PRELIMINARY
69	CONCEPT
70	SCHEMATIC
71	PRELIMINARY
72	CONCEPT
73	SCHEMATIC
74	PRELIMINARY
75	CONCEPT
76	SCHEMATIC
77	PRELIMINARY
78	CONCEPT
79	SCHEMATIC
80	PRELIMINARY
81	CONCEPT
82	SCHEMATIC
83	PRELIMINARY
84	CONCEPT
85	SCHEMATIC
86	PRELIMINARY
87	CONCEPT
88	SCHEMATIC
89	PRELIMINARY
90	CONCEPT
91	SCHEMATIC
92	PRELIMINARY
93	CONCEPT
94	SCHEMATIC
95	PRELIMINARY
96	CONCEPT
97	SCHEMATIC
98	PRELIMINARY
99	CONCEPT
100	SCHEMATIC



LSG LANDSCAPE ARCHITECTURE
1919 GALLOWAY ROAD, SUITE 110
VIRDIAK, VIRGINIA 22182
703-421-2045



DES. DWL.
SCALE: AS SHOWN
PROJECT/FILE NO. LSG-ND-11025.00
SHEET NO. L-6a



GREENSBORO DRIVE

POCKET PARK II & III


1/8"=1'-0"



- POCKET PARK II**
 PROVIDES OUTDOOR AMENITY SPACE FOR RESIDENTS AND RETAIL USERS ASSOCIATED WITH THE RECREATION FACILITY AND OUTDOOR EVENTS. MAY INCLUDE SUCH ITEMS AS:
- SEATING AREA
 - OUTDOOR DINNING
 - AMBIENT SOUND SYSTEM
 - LUNCH HOUR PICNIC
 - WAYFINDING SYSTEM FOR THE SITE APPLICATION


- POCKET PARK III**
 SMALL SCALE OPEN SPACES DESIGNED FOR CASUAL USE BY PEOPLE WORKING AND LIVING IN THE IMMEDIATE AREAS. MAY INCLUDE SUCH ITEMS AS:
- RAIN GARDEN
 - SEATING AREA
 - LUNCH HOUR PICNIC
 - GATHERING SPACES
 - LANDSCAPE AREA
 - INTERPRETIVE SIGNAGE
 - WAYFINDING SYSTEM FOR THE SITE APPLICATION

NOTE:
 THE PLAN AND IMAGERY SHOWN MAY BE MODIFIED WITH FINAL ENGINEERING AND DESIGN, PROVIDED THAT THE GENERAL DESIGN QUALITY AND CHARACTERISTICS ARE IN SUBSTANTIAL CONFORMANCE WITH THAT SHOWN.



B POCKET PARK III
 1/8"=1'-0"

REFERENCE IMAGES



LSG LANDSCAPE ARCHITECTURE
 10119 GALLOWAY ROAD, SUITE 110
 VIENNA, VIRGINIA 22182
 703-821-2045

VIFA
 VIRGINIA FLEXIBLE INFRASTRUCTURE AUTHORITY
 DIVISION OF PLANNING & LANDSCAPE ARCHITECTURE & SURVEYING & SUSTAINABLE DESIGN
 1000 COMMONWEALTH BLVD., SUITE 1000
 ARLINGTON, VA 22202
 (703) 412-7000 FAX (703) 311-3787
 WWW.VIFA.COM

DESIGN: TERRACON CONSULTANTS
 ATTORNEY: COOLEY LLP
 ARCHITECT: HED ARCHITECTURE
 LANDSCAPE ARCHITECT: LSG LANDSCAPE ARCHITECTURE
 TRANSPORTATION: BELLS & ASSOCIATES, INC.


GREENSBORO PARK PLACE
 PROVIDENCE DISTRICT
 FAIRFAX COUNTY, VIRGINIA

POCKET PARKS II & III

SUBMISSIONS


1	CONCEPT PLAN	11/15/2011
2	CONCEPT PLAN	11/15/2011
3	CONCEPT PLAN	11/15/2011
4	CONCEPT PLAN	11/15/2011
5	CONCEPT PLAN	11/15/2011
6	CONCEPT PLAN	11/15/2011
7	CONCEPT PLAN	11/15/2011
8	CONCEPT PLAN	11/15/2011
9	CONCEPT PLAN	11/15/2011
10	CONCEPT PLAN	11/15/2011
11	CONCEPT PLAN	11/15/2011
12	CONCEPT PLAN	11/15/2011
13	CONCEPT PLAN	11/15/2011
14	CONCEPT PLAN	11/15/2011
15	CONCEPT PLAN	11/15/2011
16	CONCEPT PLAN	11/15/2011
17	CONCEPT PLAN	11/15/2011
18	CONCEPT PLAN	11/15/2011
19	CONCEPT PLAN	11/15/2011
20	CONCEPT PLAN	11/15/2011
21	CONCEPT PLAN	11/15/2011
22	CONCEPT PLAN	11/15/2011
23	CONCEPT PLAN	11/15/2011
24	CONCEPT PLAN	11/15/2011
25	CONCEPT PLAN	11/15/2011
26	CONCEPT PLAN	11/15/2011
27	CONCEPT PLAN	11/15/2011
28	CONCEPT PLAN	11/15/2011
29	CONCEPT PLAN	11/15/2011
30	CONCEPT PLAN	11/15/2011
31	CONCEPT PLAN	11/15/2011
32	CONCEPT PLAN	11/15/2011
33	CONCEPT PLAN	11/15/2011
34	CONCEPT PLAN	11/15/2011
35	CONCEPT PLAN	11/15/2011
36	CONCEPT PLAN	11/15/2011
37	CONCEPT PLAN	11/15/2011
38	CONCEPT PLAN	11/15/2011
39	CONCEPT PLAN	11/15/2011
40	CONCEPT PLAN	11/15/2011
41	CONCEPT PLAN	11/15/2011
42	CONCEPT PLAN	11/15/2011
43	CONCEPT PLAN	11/15/2011
44	CONCEPT PLAN	11/15/2011
45	CONCEPT PLAN	11/15/2011
46	CONCEPT PLAN	11/15/2011
47	CONCEPT PLAN	11/15/2011
48	CONCEPT PLAN	11/15/2011
49	CONCEPT PLAN	11/15/2011
50	CONCEPT PLAN	11/15/2011

DES: DWN.
 SCALE: AS SHOWN
 PROJECT/FILE NO. LSC NO.11025.00
 SHEET NO. L-6D




POCKET PARK IV

1/8"=1'-0"



A POCKET PARK IV
1/8"=1'-0"



B POCKET PARK IV
1/8"=1'-0"

REFERENCE IMAGES



POCKET PARK IV

A FLEXIBLE OPEN SPACE WITH OPEN LAWN AREAS, USE BY PEOPLE WORKING AND LIVING IN THE IMMEDIATE AREAS, MAY INCLUDE SUCH ITEMS AS:

- LUNCH HOUR PICNIC
- OPEN LAWN SPACE
- WAYFINDING SYSTEM FOR THE SITE APPLICATION
- SUNBATHING

NOTE:

THE PLAN AND IMAGERY SHOWN MAY BE MODIFIED WITH FINAL ENGINEERING AND DESIGN, PROVIDED THAT THE GENERAL DESIGN QUALITY AND CHARACTERISTICS ARE IN SUBSTANTIAL CONFORMANCE WITH THAT SHOWN.



1915 GALLOWAY ROAD, SUITE 110
VIENNA, VIRGINIA 22182
703-461-3245

LSG LANDSCAPE ARCHITECTURE
 PLANNERS & LANDSCAPE ARCHITECTS & SCAPTORES & SUSTAINABLE DESIGN
 840 GREENBORO DRIVE, SUITE 200 & FLOYD CORNER, VIENNA, VIRGINIA 22182
 (703) 441-7800 & FAX (703) 441-1237
 WWW.LSGA.COM

GREENSBORO PARK PLACE
 PROPERTY OWNER: LSC
 ATTORNEY: COOLEY LLP
 ARCHITECT: HOK ARCHITECTURE
 LANDSCAPE ARCHITECT: LSG LANDSCAPE ARCHITECTURE
 LANDSCAPE ARCHITECT: WELLS ASSOCIATES, INC.

GREENSBORO PARK PLACE
 PROVIDENCE DISTRICT
 FAIRFAX COUNTY, VIRGINIA


POCKET PARK IV

SUBMISSIONS	
NO.	TYPE
1	CONCEPT
2	CONCEPT
3	CONCEPT
4	CONCEPT
5	CONCEPT
6	CONCEPT
7	CONCEPT
8	CONCEPT
9	CONCEPT
10	CONCEPT
11	CONCEPT
12	CONCEPT
13	CONCEPT
14	CONCEPT
15	CONCEPT
16	CONCEPT
17	CONCEPT
18	CONCEPT
19	CONCEPT
20	CONCEPT
21	CONCEPT
22	CONCEPT
23	CONCEPT
24	CONCEPT
25	CONCEPT
26	CONCEPT
27	CONCEPT
28	CONCEPT
29	CONCEPT
30	CONCEPT
31	CONCEPT
32	CONCEPT
33	CONCEPT
34	CONCEPT
35	CONCEPT
36	CONCEPT
37	CONCEPT
38	CONCEPT
39	CONCEPT
40	CONCEPT
41	CONCEPT
42	CONCEPT
43	CONCEPT
44	CONCEPT
45	CONCEPT
46	CONCEPT
47	CONCEPT
48	CONCEPT
49	CONCEPT
50	CONCEPT
51	CONCEPT
52	CONCEPT
53	CONCEPT
54	CONCEPT
55	CONCEPT
56	CONCEPT
57	CONCEPT
58	CONCEPT
59	CONCEPT
60	CONCEPT
61	CONCEPT
62	CONCEPT
63	CONCEPT
64	CONCEPT
65	CONCEPT
66	CONCEPT
67	CONCEPT
68	CONCEPT
69	CONCEPT
70	CONCEPT
71	CONCEPT
72	CONCEPT
73	CONCEPT
74	CONCEPT
75	CONCEPT
76	CONCEPT
77	CONCEPT
78	CONCEPT
79	CONCEPT
80	CONCEPT
81	CONCEPT
82	CONCEPT
83	CONCEPT
84	CONCEPT
85	CONCEPT
86	CONCEPT
87	CONCEPT
88	CONCEPT
89	CONCEPT
90	CONCEPT
91	CONCEPT
92	CONCEPT
93	CONCEPT
94	CONCEPT
95	CONCEPT
96	CONCEPT
97	CONCEPT
98	CONCEPT
99	CONCEPT
100	CONCEPT


DES: Dwnl.

SCALE: AS SHOWN


SHEET NO. L-6c




1 TREE/BIO-RETENTION (TYPE 1)
SCALE: 1/8"=1'-0"




4 TREE/BIO-RETENTION (TYPE 2)
SCALE: 1/8"=1'-0"




7 TREE AT RESIDENTIAL BUILDINGS
SCALE: 1/2"=1'-0"




2 PLANTING BIO-RETENTION (TYPE 1)
SCALE: 1/2"=1'-0"




5 PLANTING BIO-RETENTION (TYPE 2)
SCALE: 1/2"=1'-0"



8 TREE AT POCKET PARK III
SCALE: 1/2"=1'-0"



3 TREE BIO-RETENTION (TYPE 1)
SCALE: 1/2"=1'-0"



6 TREE BIO-RETENTION (TYPE 2)
SCALE: 1/2"=1'-0"

NOTE:
SEE ARCHITECTURE AND STRUCTURE DRAWINGS
FOR BUILDING SLAB AND SUB-GRADE CONDITIONS.



118 GALLOWAY ROAD, SUITE 110
VIENNA, VIRGINIA 22182
703-421-2045

VKA
VIRGINIA KIMBERLY ARCHITECTS & ASSOCIATES, INC.
ARCHITECTS & PLANNERS • LANDSCAPE ARCHITECTS & SUSTAINABLE DESIGN

PROJECT TEAM
OWNER: GREENSBORO PARK PLACE
ARCHITECT: HSG ARCHITECTURE
LANDSCAPE ARCHITECT: LSG LANDSCAPE ARCHITECTURE
TRANSPORTATION: WELLS & ASSOCIATES, INC.

GREENSBORO PARK PLACE
PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA

TYPICAL
BIO-RETENTION
TREE DETAILS

SUBMISSIONS

DATE	DESCRIPTION
09/11/2012	ISSUED FOR PERMIT
11/22/2012	ISSUED FOR CONSTRUCTION
09/11/2012	ISSUED FOR PERMIT
11/22/2012	ISSUED FOR CONSTRUCTION

SCALE: AS SHOWN
PROJECT/FILE NO. LSG NO.11025.00
SHEET NO. L-7d

STREET LIGHTS
MAKE: SE'LUX
MODEL: ARC MINI




1 STREET LIGHT FIXTURE

STICK LIGHTS
MAKE: BEGA
MODEL: 8994




BOLLARDS
MAKE: BEGA
MODEL: 8216P



2 DECORATIVE SITE LIGHT FIXTURE

BENCHES
MAKE: LANDSCAPE FORMS
MODEL: REST METRO 40



3 SITE BENCH

TRASH RECEPTACLES
MAKE: LANDSCAPE FORMS
MODEL: CHASE PARK




4 LITTER RECEPTACLES

PLANTERS
MAKE: LANDSCAPE FORMS
MODEL: SORELLA




5 PLANTER

TABLE & CHAIRS
MAKE: LANDSCAPE FORMS
MODEL: CATENA



6 TABLE AND CHAIRS

BIKE RACKS
MAKE: CREATIVE PIPE
MODEL: HORSESHOE RACK




7 BIKE RACKS

UMBRELLA
MAKE: LANDSCAPE FORMS
MODEL: EQUINOX



8 UMBRELLA

PAVER MATERIAL
MAKE: WAUSAU PAVERS
TYPE: PLANK STYLE PAVERS



9 PAVER

NOTE:
1. LIGHTING AND SITE FURNISHINGS ARE REPRESENTATIVE OF QUALITY AND MATERIALS. FINAL SELECTION SHALL BE MADE BY THE APPLICANT FROM ITEMS SHOWN OR SIMILAR PRODUCTS IN THE TYSONS URBAN DESIGN GUIDELINES.
2. SELECTION OF LIGHT FIXTURES FOR LIGHTING IN ROW SUBJECT TO CONFORMANCE WITH POWER COMPANY REQUIREMENTS.

VIFA
DESIGNERS & PLANNERS • LANDSCAPE ARCHITECTS • SURVEYORS • SUSTAINABLE DESIGN
VIFA VIRGINIA, LLC
810 CRENSHAW BLVD., SUITE 200 • FALLS CHURCH, VIRGINIA 22024
(703) 445-3300 • FAX (703) 740-7317
WWW.VIFA.COM

PROJECT TEAM
OWNER: GREENSBORO PARK
ARCHITECT: COLETT LIP
ARCHITECT: HOG ARCHITECTURE
LSG LANDSCAPE ARCHITECTURE
TRANSPORTATION:
WELLS & ASSOCIATES, INC.

GREENSBORO PARK PLACE
PROVIDENCE DISTRICT
FAIRFAX COUNTY, VIRGINIA


STREETSCAPE
FURNISHING
&
MATERIAL IMAGES

SUBMISSIONS

DATE:	REV:
DES.	DWN.
SCALE:	AS SHOWN
PROJECT/FILE NO.	LSG NO. 11025.00
SHEET NO.	L-8



LSG LANDSCAPE ARCHITECTURE
1919 GALLONS ROAD, SUITE 110
VIENNA, VIRGINIA 22182
703-421-0465



NOTE: THE ULTIMATE ADJUSTMENT OF THE STREETS SHOWN HEREON IS CONCEPTUAL ONLY AND IS SUBJECT TO FURTHER REFINEMENT BY THE OWNERS OF THE ADJACENT PROPERTIES OR THEIR AGENTS, AS PART OF FUTURE CONCEPTUAL/FINAL DEVELOPMENT PLANS AND SITE PLANS.



VISA
 CONSULTING ENGINEERS & ARCHITECTS
 1000 WEST 10TH AVENUE, SUITE 200
 DENVER, COLORADO 80202
 TEL: 303.733.1100
 WWW.VISA-CEA.COM


COLLETT
 OWNER: GREENSBORO PARK
 PROPERTY OWNER LLC
 ARCHITECT: COLLETT LLP
 PROJECT: 1600 INDUSTRIAL DRIVE
 LANDSCAPE ARCHITECTURE
 1000 WEST 10TH AVENUE, SUITE 200
 DENVER, COLORADO 80202
 TEL: 303.733.1100
 WWW.COLLETT.COM

GREENSBORO PARK PLACE
 PROVIDENCE DISTRICT
 FAYETTE COUNTY, VIRGINIA

RESULTS ROAD, ALTERNATIVE LAYOUT

SUBMISSIONS	
NO.	DATE
10	CONTR. 10/18/2014
9	CONTR. 12/24/2013
8	CONTR. 11/08/2013
7	CONTR. 09/03/2013
6	CONTR. 07/22/2013
5	CONTR. 04/15/2013
4	CONTR. 01/13/2013
3	CONTR. 09/11/2012
2	CONTR. 02/03/2012
1	CONTR. 11/22/2011

DATE: NOVEMBER 2011
 DES: []
 UVA: []
 DWN: []
 SCALE: AS SHOWN
 PROJECT FILE NO: V501SR
 SHEET NO: S-1



METRO ACCESS DIAGRAM

NTS



VFA
 VISIONARY FIRM ARCHITECTS
 4400 ROCKY HOLLOW DRIVE, SUITE 200 • ROCKY HOLLOW, MICHIGAN 48309
 (248) 411-7868 • FAX (248) 911-1747
 WWW.VFA.COM

LEG LANDSCAPE ARCHITECTURE
 1919 GALLONS ROAD, SUITE 110
 VENTNA, VIRGINIA 22182
 703.421.2045

GREENSBORO PARK PLACE
 PROVIDENCE DISTRICT
 FAIRFAX COUNTY, VIRGINIA

METRO ACCESS EXHIBIT

SUBMISSIONS

CDP / JLP	01/18/2014
CDP / JLP	12/18/2013
CDP / JLP	11/20/2013
CDP / JLP	09/15/2013
CDP / JLP	08/15/2013
CDP / JLP	05/20/2013
CDP / JLP	03/15/2013
CDP / JLP	01/15/2013
CDP / JLP	09/15/2012
CDP / JLP	11/23/2011
DATE	NOVEMBER 2011
DCS	DWN

SCALE: AS SHOWN
 PROJECT/FILE NO: LSC-10-11023-00
 SHEET NO: S-2



LEG LANDSCAPE ARCHITECTURE
 1919 GALLONS ROAD, SUITE 110
 VENTNA, VIRGINIA 22182
 703.421.2045

CONCEPTUAL DEVELOPMENT PLAN CONDITIONS

CDP 2012-PR-002

February 25, 2014

The Board of Supervisors approves Conceptual Development Plan CDP 2012-PR-002, on property located at Tax Map 29-3 ((15)) 12A and 20-4 ((9)) 12B, with the following development condition.

1. In order to achieve the runoff reduction specified in the proffers, and to ensure the continuous function and performance, all BMPs installed on site shall be designed, constructed, operated and privately maintained by the owners, in a manner consistent with the applicable standards and specifications included in the PFM in effect at the time of site plan approval, as approved by DPWES, including, but not limited to, the execution of a private maintenance agreement. If new or advanced technologies, or alternative designs, are proposed, such shall be subject to the approval of DPWES in accordance with the criteria specified in PFM Sect. 2-1200.

Development Conditions

FDP 2012-PR-002

Greensboro Park Property Owner, LLC

January 22, 2014

The Planning Commission approves Final Development Plan FDP 2012-PR-002 to permit residential buildings and site improvements on Tax Map No. 29-3 ((15)) 12A and 29-4 ((9)) 12B, requiring conformance with the following development conditions.

1. This FDP is subject to the provisions of Article 17, Site Plans, as may be determined by the Director, Department of Public Works and Environmental Services (DPWES). Any plan submitted pursuant to this final development plan (FDP) shall be in substantial conformance with the approved FDP entitled Greensboro Park Place, prepared by WDG Architecture, and revised January 16, 2014, and these conditions. Minor modifications to the approved FDP may be permitted pursuant to Par. 4 of Sect. 16-403 of the Zoning Ordinance.
2. Stormwater management and best management practices shall be provided in substantial conformance with that shown on the FDP. Specifically, the size and function of the green roof, rain garden, and bio-retention facilities shall be in substantial conformance with those depicted on Sheets 18 and 19 of the FDP. During the preparation of the final site plan, exact locations, sizes and facilities may change as long as they meet the requirements as outlined in the FDP's Stormwater Management Plan. Additional LID facilities may be provided as desired by the applicant.



COUNTY OF FAIRFAX
 Department of Planning and Zoning
 Zoning Evaluation Division
 12055 Government Center Parkway, Suite 801
 Fairfax, VA 22035 (703) 324-1290, TTY 711
www.fairfaxcounty.gov/dpz/zoning/applications

APPLICATION No: RZ 2012-PR-002
 (Assigned by staff)

RECEIVED
 Department of Planning & Zoning
 NOV 22 2011
 Zoning Evaluation Division

APPLICATION FOR A REZONING
 (PLEASE TYPE or PRINT IN BLACK INK)

PETITION

TO: THE BOARD OF SUPERVISORS OF FAIRFAX COUNTY, VIRGINIA

I (We), Greensboro Park Property Owner: LLC, the applicant (s) petition you to adopt an ordinance amending the Zoning Map of Fairfax County, Virginia, by reclassifying from the C-4 District to the PTC District the property described below and outlined in red on the Zoning Section Sheet(s) accompanying and made part of this application.

APPLICATION TYPE(S): PCA () CDP (X) FDP () CDPA () FDPA ()

LEGAL DESCRIPTION:

12 B			21314	1244
12 A			21314	1244
Lot(s)	Block(s)	Subdivision	Deed Book	Page No.

TAX MAP DESCRIPTION:

29-4	9		12 B	3.68
29-3	15		12 A	3.29
				6.9
Map No.	Double Circle No.	Single Circle No.	Parcel(s)/Lot(s) No.	Total Acreage

POSTAL ADDRESS OF PROPERTY:

8180 & 8200 Greensboro Drive, McLean, VA

ADVERTISING DISCRIPTION: (Example - North side of Lee Highway approx. 1000 feet west of its intersection with Newgate Blvd.)

North of Greensboro Drive, west and south of International Drive.
 PRESENT USE: Office PROPOSED USE: Office & Residential
 MAGISTERIAL DISTRICT: Providence OVERLAY DISTRICT (S): SC

The name(s) and address(s) of owner(s) of record shall provided on the affidavit form attached and made part of this application. The undersigned has the power to authorize and does hereby authorize Fairfax County staff representative on official business to enter on the subject property as necessary to process the application.

Jill S. Parks, Esq.
 Type or Print Name

Jill Parks
 Signature of Applicant or Agent

11951 Freedom Dr., #1500, Reston, VA
 Address 20190

(Work) (703) 456-8067 (Mobile)
 Telephone Number

Please provide name and telephone number of contact if different from above:

DO NOT WRITE BELOW THIS SPACE

Date application accepted: February 13, 2012

RZ 2011-0294
 Fee Paid \$ 36,095.00



COUNTY OF FAIRFAX
Department of Planning and Zoning
Zoning Evaluation Division
 12055 Government Center Parkway, Suite 801
 Fairfax, VA 22035 (703) 324-1290, TTY 711
www.fairfaxcounty.gov/dpz/zoning/applications

APPLICATION No: FDP 2012-PR-002
 (Assigned by staff)

APPLICATION FOR A REZONING
 (PLEASE TYPE or PRINT IN BLACK INK)

PETITION

TO: THE BOARD OF SUPERVISORS OF FAIRFAX COUNTY, VIRGINIA

I (We), Greensboro Park Property Owner, LLC, the applicant (s) petition you to adopt an ordinance amending the Zoning Map of Fairfax County, Virginia, by reclassifying from the C-4 District to the PTC District the property described below and outlined in red on the Zoning Section Sheet(s) accompanying and made part of this application.

APPLICATION TYPE(S):	PCA ()	CDP ()	FDP (X)	CDPA ()	FDPA ()
----------------------	---------	---------	---------	----------	----------

LEGAL DESCRIPTION:

12 B			21314	1244
12 A			21314	1244
Lot(s)	Block(s)	Subdivision	Deed Book	Page No.

TAX MAP DESCRIPTION:

29-4	9		12 B	3.68
29-3	15		12 A	3.29
				6.97
Map No.	Double Circle No.	Single Circle No.	Parcel(s)/Lot(s) No.	Total Acreage

POSTAL ADDRESS OF PROPERTY:

8180 and 8200 Greensboro Drive, McLean, VA

ADVERTISING DISCRIPTION: (Example - North side of Lee Highway approx. 1000 feet west of its intersection with Newgate Blvd.)

North of Greensboro Drive, west and south of International Drive	
PRESENT USE: Office	PROPOSED USE: Office, Residential, and Retail
MAGISTERIAL DISTRICT: Providence	OVERLAY DISTRICT (S): SC

The name(s) and address(s) of owner(s) of record shall provided on the affidavit form attached and made part of this application. The undersigned has the power to authorize and does hereby authorize Fairfax County staff representative on official business to enter on the subject property as necessary to process the application.

Jill S. Parks, Esq.

 Type or Print Name
 11951 Freedom Drive, Reston VA 20190

 Address

Jill S Parks

 Signature of Applicant or Agent
 (Work) (703) 456-8067 (Mobile)

 Telephone Number

Please provide name and telephone number of contact if different from above:

MPC
2/6/13

DO NOT WRITE BELOW THIS SPACE

Date application accepted: February 6, 2013

FDP 2013-0014
 Fee Paid \$ 17,120.00

11
Urania Ruffner

RZ 2012-PR-002

Zoning Application Closeout Summary Report

Printed: 7/17/2014

General Information

APPLICANT: GREENSBORO PARK PROPERTY OWNER LLC
DECISION DATE: 02/25/2014
CRD: NO
HEARING BODY: BOS
ACTION: APPROVE
STAFF COORDINATOR: BOB KATAI
SUPERVISOR DISTRICT: PROVIDENCE

DECISION SUMMARY:

ON FEBRUARY 25, 2014, THE BOARD UNANIMOUSLY APPROVED RZ 2012-PR-002 ON A MOTION BY SUPERVISOR SMYTH SUBJECT TO PROFFERS DATED FEBRUARY 19, 2014 AND SUBJECT TO A CONCEPTUAL DEVELOPMENT PLAN CONDITION DATED FEBRUARY 25, 2014.

APPLICATION DESCRIPTION:

OFFICE AND RESIDENTIAL

Zoning Information

Existing Zoning		Proposed Zoning		Approved Zoning	
DISTRICT	AREA	DISTRICT	AREA	DISTRICT	AREA
C- 4	6.90 ACRES	PTC	6.90 ACRES	PTC	6.90 ACRES

Tax Map Numbers

0294 ((09)) ()0012 B 0293 ((15)) ()0012 A

Approved Land Uses

Zoning District: PTC

LAND USE	DU'S	RES LAND AREA	ADU'S	WDU'S	GFA	FAR	NRES LAND AREA
MFD	520	6.98 ACRES		104			
ALT/PUB/FA					3,000		
OFFC/GENRL					504,574	1.65	
RETAIL/EST					1,999	0.16	
TOTALS	520	6.98		104	509,573	1.81	

Approved Waivers/Modifications

SEE FILE FOR ALL WAIVERS AND MODIFICATIONS

MODIFY LOADING SPACE REQUIREMENT

MODIFY STREETScape & TRAIL REQUIREMENT

DEVIATION FROM TREE PRESERVATION TARGET PERCENTAGE

MODIFY TREE CONSERVATION PLAN

WAIVE FRONTAGE IMPROVEMENTS

WAIVE PERIPHERAL PARKING LOT LANDSCAPING

WAIVE 600 FT. PRIVATE STREET LENGTH REQUIREMENT

WAIVE INTERPARCEL ACCESS

Approved Proffers

PROFFER STATEMENT DATE: 02-19-2014

PROFFER	DUE	TRIG #	TRIG EVENT	CONTRIB AMT	EXPIR. DTE
INTERNAL CIRCULATION	01-01-0001	0	SITE PLAN	\$0	01-01-0001
ENERGY EFFICIENCY	01-01-0001	0	SITE PLAN	\$0	01-01-0001
BICYCLE RELATED FACILITIES	01-01-0001	0	SITE PLAN	\$0	01-01-0001
LOW IMPACT DESIGN (LID)/ RAINGARDEN	01-01-0001	0	N/A	\$0	01-01-0001
BUILDING FOOTPRINT	01-01-0001	0	SITE PLAN	\$0	01-01-0001
LANDSCAPE PLAN REQUIRED	01-01-0001	0	SITE PLAN	\$0	01-01-0001
OTHER - TRANSPORTATION	01-01-0001	0	SITE PLAN	\$0	01-01-0001
OFF-SITE CONTRIBUTION - RECREATION	01-01-0001	1	RUP	\$0	12-13-2015
CONTRIBUTION - SCHOOLS	01-01-0001	1	RUP	\$0	01-01-0001
STREETScape	01-01-0001	1	RUP	\$0	01-01-0001
CONSTRUCTION VEHICLE RESTRICTIONS	01-01-0001	0	N/A	\$0	01-01-0001
ALTERNATIVE SWM MEASURES	01-01-0001	0	SITE PLAN	\$0	01-01-0001
INTERIM USE	01-01-0001	0	N/A	\$0	01-01-0001
EXISTING STRUCTURES (RETAIN)	01-01-0001	0	SITE PLAN	\$0	01-01-0001
PROFFERED PLANS	01-01-0001	0	SITE PLAN	\$0	01-01-0001
ANTENNAS	01-01-0001	0	BLDG PRMT APRV	\$0	01-01-0001
DENSITY / DWELLING UNITS PER ACRE (DU/AC)	01-01-0001	0	BLDG PRMT APRV	\$0	01-01-0001
ARCHITECTURE / BUILDING MATERIALS / COLORS	01-01-0001	0	BLDG PRMT APRV	\$0	01-01-0001
TREE PRESERVATION / SURVEY	01-01-0001	0	SITE PLAN	\$0	01-01-0001
NOISE ATTENUATION (STUDY / WALL)	01-01-0001	0	BLDG PRMT APRV	\$0	01-01-0001
PARKING	01-01-0001	0	SITE PLAN	\$0	01-01-0001
ESCROW - TRANSPORTATION	01-01-0001	1	RUP	\$0	01-01-0001
CONTRIBUTION / OTHER TRANSPORTATION	01-01-0001	0	N/A	\$0	01-01-0001
RECREATION FACILITIES	01-01-0001	1	RUP	\$0	01-01-0001
FLOOR AREA RATIO (FAR) / GROSS FLOOR AREA (GFA)	01-01-0001	0	BLDG PRMT APRV	\$0	01-01-0001
RIGHT OF WAY - DEDICATION	01-01-0001	0	SITE PLAN	\$0	01-01-0001
LANDSCAPING - SWM	01-01-0001	0	SITE PLAN	\$0	01-01-0001
BEST MANAGEMENT PRACTICES (BMP)	01-01-0001	0	SITE PLAN	\$0	01-01-0001
PUBLIC MEETING SPACE	01-01-0001	1	BLDG PRMT APRV	\$0	01-01-0001
HEIGHT - BUILDING / STRUCTURE	01-01-0001	0	BLDG PRMT APRV	\$0	01-01-0001
WORKFORCE HOUSING	01-01-0001	0	N/A	\$0	01-01-0001
HOA ESTABLISH	01-01-0001	1	RUP	\$0	01-01-0001
TRANSPORTATION DEMAND MANAGEMENT PROGRAM (TDM)	01-01-0001	0	SITE PLAN	\$0	01-01-0001
USE RESTRICTIONS	01-01-0001	0	SITE PLAN	\$0	01-01-0001
OTHER - ENVIRONMENT	01-01-0001	0	SITE PLAN	\$0	01-01-0001
BUS STOP / SHELTER / MAINTENANCE	01-01-0001	1	RUP	\$0	01-01-0001

7/17/2014

Approved Development ConditionsDEVELOPMENT CONDITION STATEMENT DATE: 02-25-2014

<u>DEVELOPMENT CONDITION</u>	<u>DUE</u>	<u>TRIG #</u>	<u>TRIG EVENT</u>	<u>CONTRIB</u>	<u>EXPIR DTE</u>
SWM / BEST MANAGEMENT PRACTICES (BMP)	01-01-0001	0	SITE PLAN	0	01-01-0001

7/17/2014

FDP 2012-PR-002

Zoning Application Closeout Summary Report

Printed: 7/17/2014

General Information

APPLICANT: GREENSBORO PARK PROPERTY OWNER, LLC
DECISION DATE: 02/19/2014
CRD: NO
HEARING BODY: PC
ACTION: APPROVE
STAFF COORDINATOR: BOB KATAI
SUPERVISOR DISTRICT: PROVIDENCE

DECISION SUMMARY:

ON FEBRUARY 19, 2014, THE PLANNING COMMISSION UNANIMOUSLY APPROVED FDP 2012-PR-002 ON A MOTION BY COMMISSIONER LAWRENCE SUBJECT TO DEVELOPMENT CONDITIONS DATED JANUARY 22, 2014 AND TO THE BOARD'S APPROVAL OF THE REZONING RZ 2012-PR-002.

APPLICATION DESCRIPTION:

MIXED USE

Zoning Information

Existing Zoning		Proposed Zoning		Approved Zoning	
DISTRICT	AREA	DISTRICT	AREA	DISTRICT	AREA
				PTC	6.97 ACRES

Tax Map Numbers

0294 ((09)) ()0012 B 0293 ((15)) ()0012 A

Approved Land Uses

Zoning District: PTC

LAND USE	DU'S	RES LAND AREA	ADU'S	WU'S	GFA	FAR	NRES LAND AREA
MFD	520	6.9B ACRES		104			
ALT/PUB/FA					3,000		
OFFC/GENRL					504,574	1.65	
RETAIL/EST					1,999	0.16	
TOTALS	520	6.98		104	509,573	1.81	

7/17/2014

Approved Waivers/Modifications

MODIFY LOADING SPACE REQUIREMENT
MODIFY STREETScape & TRAIL REQUIREMENT
SEE FILE FOR ALL WAIVERS AND MODIFICATIONS
DEVIATION FROM TREE PRESERVATION TARGET PERCENTAGE
MODIFY TREE CONSERVATION PLAN
WAIVE FRONTAGE IMPROVEMENTS
WAIVE PERIPHERAL PARKING LOT LANDSCAPING
WAIVE 600 FT. PRIVATE STREET LENGTH REQUIREMENT
WAIVE INTERPARCEL ACCESS

Approved Development Conditions

DEVELOPMENT CONDITION STATEMENT DATE: 01-22-2014

<u>DEVELOPMENT CONDITION</u>	<u>DUE</u>	<u>TRIG #</u>	<u>TRIG EVENT</u>	<u>CONTRIB</u>	<u>EXPIR DTE</u>
SUBJECT TO SITE PLANS / SUBDIVISION PLATS	01-01-0001	0	SITE PLAN	0	01-01-0001
APPROVED FOR LOCATION/STRUCTURE/USES ETC ON PLATS	01-01-0001	0	SITE PLAN	0	01-01-0001
SWM / BEST MANAGEMENT PRACTICES (BMP)	01-01-0001	0	SITE PLAN	0	01-01-0001
LANDSCAPING - SWM	01-01-0001	0	SITE PLAN	0	01-01-0001
LOW IMPACT DESIGN (LID) / RAINGARDEN	01-01-0001	0	SITE PLAN	0	01-01-0001
UNDERGROUND - SWM	01-01-0001	0	SITE PLAN	0	01-01-0001

7/17/2014