



County of Fairfax, Virginia

To protect and enrich the quality of life for the people, neighborhoods and diverse communities of Fairfax County

August 25, 2015

Revised – *added additional language
regarding Planning Commission approval

Sara V. Mariska
Walsh, Colucci, Lubeley & Walsh, P.C.
2200 Clarendon Boulevard, Suite 1300
Arlington, VA 22201

RECEIVED
Department of Planning & Zoning

SEP 18 2015

Zoning Evaluation Division

RE: Proffered Condition Amendment Application PCA 2011-LE-022
(Concurrent with Proffered Condition Amendment Applications PCA 2008-LE-015-02 and
PCA 1998-LE-064-03)

Dear Ms. Mariska:

Enclosed you will find a copy of an Ordinance adopted by the Board of Supervisors at a regular meeting held on July 28, 2015, approving Proffered Condition Amendment Application PCA 2011-LE-022 in the name of Springfield Metro Center II, LLC and Springfield 6601 LLC. The Board's action amends the proffers for Rezoning Application RZ 2011-LE-022 previously approved for office development and associated modifications to proffers and site design with an overall Floor Area Ratio (FAR) of 1.89. The subject property is located on the W. side of Springfield Center Drive, S.W. of Springfield Metro Center, on approximately 6.28 acres of land zoned PDC [Tax Map 90-2 ((1)) 56C pt., 58D, and 90-4 ((1)) 11B pt.], in the Lee District and is subject to the proffers dated July 14, 2015.

*Please note that on July 15, 2015, the Planning Commission approved Conceptual/Final Development Plan Amendment Application CDPA/FDPA 2011-LE-022, subject to the development conditions dated July 1, 2015.

The Board also:


- Reaffirmed the previously approved modification of the loading space requirement to allow four spaces instead of the required five spaces by Paragraph 15 of Section 11-202 of the Zoning Ordinance as depicted on the CDPA/FDPA
- Reaffirmed an increase in the maximum floor area ratio from 1.5 to 1.89 for the previously approved Option 1 to be retained, in accordance with Section 6-208 of the Zoning Ordinance as depicted on the CDPA/FDPA
- Reaffirmed a previously approved waiver of the barrier requirement and modification of the transitional screening yard requirement for the eastern portion of the site in accordance with Paragraph 11 of Section 13-305 of the Zoning Ordinance as depicted on the CDPA/FDPA

Office of the Clerk to the Board of Supervisors
12000 Government Center Parkway, Suite 533
Fairfax, Virginia 22035

Phone: 703-324-3151 ♦ Fax: 703-324-3926 ♦ TTY: 703-324-3903
Email: clerktothebos@fairfaxcounty.gov
<http://www.fairfaxcounty.gov/bosclerk>

- Directed the Director of DPWES to permit a deviation from the tree preservation target requirement identified in Section 12-0508 of the Public Facilities Manual in favor of what is shown on the CDPA/FDPA

Sincerely,



Catherine A. Chianese
Clerk to the Board of Supervisors

Cc: Chairman Sharon Bulova
Supervisor Jeffrey McKay, Lee District
Tim Shirocky, Acting Director, Real Estate Division, Dept. of Tax Administration
Barbara C. Berlin, Director, Zoning Evaluation Division, DPZ
Diane Johnson-Quinn, Deputy Zoning Administrator, Dept. of Planning and Zoning
Michael Davis, Section Chief, Transportation Planning Division
Thomas Conry, Dept. Manager – GIS - Mapping/Overlay
Donald Stephens, Transportation Planning Division
Ken Williams, Plans & Document Control, ESRD, DPWES
Department of Highways-VDOT
Sandy Stallman, Park Planning Branch Manager, FCPA
Charlene Fuhrman-Schulz, Development Officer, DHCD/Design Development Division
Jill Cooper, Executive Director, Planning Commission
Ajay Rawat, Coordinator, Facilities Planning/Fairfax County Public Schools
Karyn Moreland, Chief Capital Projects Sections, Dept. of Transportation

At a regular meeting of the Board of Supervisors of Fairfax County, Virginia, held in the Board Auditorium in the Government Center at Fairfax, Virginia, on the 28th day of July 2015, the following ordinance was adopted.

**AN ORDINANCE AMENDING THE ZONING ORDINANCE
PROFFERED CONDITION AMENDMENT APPLICATION PCA 2011-LE-022
(Concurrent with Proffered Condition Amendment Applications PCA 1998-LE-064-03 and
PCA 2008-LE-015-02)**

WHEREAS, Springfield Metro Center II, LLC and Springfield 6601 LLC, filed in the proper form an application to amend the proffers for RZ 2011-LE-022, previously hereinafter described, by amending conditions proffered and accepted pursuant to Virginia Code Ann. 15.2-2303(a), and

WHEREAS, at a duly called public hearing the Planning Commission considered the application and the propriety of amending the Zoning Ordinance in accordance therewith, and thereafter did submit to this Board its recommendation, and

WHEREAS, this Board has today held a duly called public hearing and after due consideration of the reports, recommendation, testimony and facts pertinent to the proposed amendment, the Board is of the opinion that the Ordinance should be amended,

NOW, THEREFORE, BE IT ORDAINED, that that certain parcel of land situated in the Lee District, and more particularly described as follows (see attached legal description): Be, and hereby is further restricted by the amended conditions proffered and accepted pursuant to Virginia Code Ann., 15.2-2303(a), which conditions are incorporated into the Zoning Ordinance as it affects said parcel, and

BE IT FURTHER ENACTED, that the boundaries of the Zoning Map heretofore adopted as a part of the Zoning Ordinance be, and they hereby are, amended in accordance with this enactment, and that said zoning map shall annotate and incorporate by reference the additional conditions governing said parcels.

GIVEN under my hand this 28th day of July 2015.



Catherine A. Chianese
Clerk to the Board of Supervisors

PROFFERS

Springfield Metro Center II, LLC and Springfield 6601 LLC

PCA 2011-LE-022

July 14, 2015

Pursuant to Section 15.2-2303(a) Code of Virginia, 1950, as amended, Springfield Metro Center II, LLC and Springfield 6601 LLC, (hereinafter referred to as the "Applicants"), for themselves, successors and assigns in PCA 2011-LE-022, filed for property identified as Tax Map 90-2 ((1)) 56C (part) and 58D and 90-4 ((1)) 11B (part) (hereinafter referred to as the "Application Property") hereby proffer that the development of the Application Property shall be in accordance with the following proffers, provided that the Board of Supervisors approves PCA 2011-LE-022 to rezone the Application Property to the PDC District.

1. CONCEPTUAL/FINAL DEVELOPMENT PLAN

- a. Subject to the provisions of 16-204 of the Fairfax County Zoning Ordinance (hereinafter referred to as the "Zoning Ordinance"), development of the Application Property shall be in substantial conformance with the Conceptual Development Plan Amendment/Final Development Plan Amendment (CDPA/FDPA), consisting of twenty-nine (29) sheets prepared by Urban, Ltd., dated February 10, 2011 and revised through June 17, 2015.
- b. Pursuant to Paragraph 4 of Section 16-403 of the Zoning Ordinance, minor modifications from the CPDA/FDPA may be permitted as determined by the Zoning Administrator. The Applicants reserve the right to make minor modifications to the building footprints shown on the CDPA/FDPA and make other modifications provided that such modifications are in substantial conformance with the CDPA/FDPA as determined by the Zoning Administrator, and do not increase building height nor decrease the amount and location of open space, limits of clearing and grading, landscaping, or distances to peripheral lot lines as dimensioned on the CDPA/FDPA.
- c. Notwithstanding that the CDPA/FDPA is presented on twenty-nine (29) sheets and said CDPA/FDPA is the subject of Proffer 1.a. above, it shall be understood that the CDPA shall be limited to the building footprint, location and amount of open space, limits of clearing and grading, location and number of entrances, and the maximum square footage of development. The Applicants have the option to request Final Development Plan Amendments ("FDPAs") for elements other than CDPA elements from the Planning Commission for all of, or a portion of, the CDPA/FDPA in accordance with the provisions set forth in Section 16-402 of the Zoning Ordinance.

- d. Either of the buildings shown on the CDPA/FDPA may be the subject of a partial and separate Proffered Condition Amendment (PCA) and/or FDPA without joinder and/or consent of the other building owners as determined by the Zoning Administrator pursuant to Paragraph 6 of Section 18-204 of the Zoning Ordinance. Previously approved proffered conditions applicable to buildings that are not the subject of such a PCA or FDPA shall otherwise remain in full force and effect.
- e. In the Applicants' sole discretion, the Application Property may be developed with up to 517,600 square feet of Gross Floor Area in Option 1 or with up to 390,800 square feet of GFA in Option 2. With Option 2, the Applicants reserve the right to transfer office square footage from the Application Property to the property subject to PCA 1998-LE-064-3/PCA 2008-LE-015-2. Up to 126,800 square feet of GFA may be transferred from the Application Property to the property subject to PCA 1998-LE-064-3/PCA 2008-LE-015-2 provided that the square footage permitted on the Application Property shall be reduced by the amount of square footage transferred.

2. USES

- a. As shown on the CDPA/FDPA, the Application Property shall be developed with, office and accessory uses. Accessory uses internal to the buildings may include, but not be limited to, a personal service establishment, sundry shop, banking center, establishment, and fast food restaurant, to support the tenants in each building. Accessory uses shall be designed for tenant use with the intent to minimize midday vehicle trips to and from the Application Property. Among the two (2) buildings proposed with this application and the two (2) buildings proposed in conjunction with PCA 1998-LE-064-3/PCA 2008-LE-015-2, the Applicants shall provide a minimum of 5,000 square feet of accessory uses between both sites, which shall be identified prior to the issuance of a tenant layout building permit for the accessory uses. If at time of final site plan submission for the last of the buildings the Applicants can demonstrate to the satisfaction of the Zoning Administrator that they have made diligent efforts to lease a minimum of 5,000 square feet for accessory uses, and those efforts have been unsuccessful in meeting the minimum square footage required under this proffer, this proffer shall be deemed satisfied and the Applicants shall have no further obligations under this proffer.
- b. Telecommunications facilities (building-mounted only) may be added to the building without necessitating approval of a PCA or FDPA.
- c. Cellar space in each building, if provided, shall include a mix of uses such as the following:
 - (i) Unoccupied areas used by the building tenants or owners (such as restrooms, mechanical rooms, electrical rooms, janitor and building

maintenance rooms, bulk storage for documents, paper and office supplies, goods and products of the building tenant or janitorial supplies);

- (ii) Specialty areas used by the building tenants or owners (such as computer rooms, battery rooms, "clean rooms," security tanks, SCIF rooms, libraries, etc.) but not to include office space;
- (iii) Simultaneous or accessory uses used by the building tenants or owners (such as conference rooms, conference centers, fitness center, employee cafeterias or canteens, employee lounges or classrooms, banking center, sundry shop).

3. TRANSPORTATION

a. Springfield Center Drive/Frontier Drive Extended

- (i) Interim Condition. Prior to the issuance of the first Non-Residential Use Permit (Non-RUP) for the Application Property, the Applicants shall construct those improvements along Springfield Center Drive as generally depicted on Sheet 6 of the CDPA/FDPA in order to provide a continuous connection between Joseph Alexander Drive and the Application Property. This street shall be privately maintained by the Applicants until such time as the ultimate section is constructed as described below.
- (ii) Ultimate Condition. The ultimate section for Springfield Center Drive/Frontier Drive Extended is depicted on Sheet 24 of the CDPA/FDPA. This section, as recommended by the Comprehensive Plan, will include four (4) travel lanes, each eleven (11) feet in width, two (2) in each direction, with bicycle lanes five (5) feet in width on both sides of the street, parking lanes eight (8) feet in width on both sides of the street, and eight (8) foot sidewalks on both sides of the street. The section shall transition to be one hundred sixteen (116) feet in width with the alignment as generally shown on Sheet 24 of the CDPA/FDPA. The ultimate section of Springfield Center Drive/Frontier Drive Extended will be constructed by others. The Applicants shall provide the reservation of right-of-way along the Application Property's frontage as shown on Sheet 23 of the CDPA/FDPA and described more fully below.
- (iii) Right-of-Way. The Applicants shall reserve right-of-way on the Application Property for the ultimate section of Springfield Center Drive/Frontier Drive Extended at the time of site plan approval as shown on Sheet 23 of the CDPA/FDPA. Springfield Center Drive shall transition to a seventy- (70) foot section that will connect to the Springfield Center Drive Extension to the northwest. The Applicants shall convey the reserved area in fee simple to the Board of Supervisors, without encumbrances, following construction and final street acceptance inspection by Fairfax County and/or Virginia Department of

Transportation (VDOT) of the ultimate street section and streetscape improvements or upon demand, whichever occurs first. All right-of-way dedications shall be subject to advanced density credit.

- (iv) Phase I Garage Access. Notwithstanding Subparagraphs i through iii, should the final design of Frontier Drive result in a garage access for the garage associated with PCA 1998-LE-064-2/PCA 2008-LE-015-2 that does not meet VDOT access management requirements, then at such time as VDOT and/or Fairfax County demand the dedication of right-of-way for the Frontier Drive Extension as described more fully in Subparagraphs ii and iii above, then the Applicant shall prepare and submit plans to VDOT and FCDOT a plan for the relocation of the garage access associated with PCA 1998-LE-064-2/PCA 2008-LE-015-2 north to approximately Station 12+66.47 on Springfield Center Drive as more generally shown on Sheet 24 of the CDP/FDP. Coincident with the submission of the design plans, the Applicants shall prepare an operational analysis to assess the impacts of the garage access relocation on the new Springfield Center Drive/Frontier Drive Extended intersection.

If upon review, VDOT and FCDOT determine that the new garage access will not impact Springfield Center Drive operations or the new intersection with Frontier Drive Extended, then the Applicant shall proceed with the closure of the existing access and the construction of the new garage access.

If VDOT and FCDOT determine upon review of the operational analysis that the new garage access will significantly impact Springfield Center Drive operations or the new intersection with Frontier Drive Extended, then the Applicant shall restrict the existing garage access to right-in movements only or close the access as may be determined by VDOT and FCDOT.

Regardless of the above, any modifications or relocation of the Phase I garage access may be accomplished without the need for a PCA, CDPA and/or FDPA. The Applicant further reserves the right to relocate the Phase I garage access north at any time prior to the timing listed above after consultation with both FCDOT and VDOT.

- b. Springfield Road Fund Contribution. Prior to the issuance of the first Non-RUP, the Applicants shall contribute \$517,600.00 to the Springfield Area Road Fund to be used to construct transportation improvements within two (2) miles of the Application Property.
- c. Springfield Center Drive/Loisdale Road. Subject to VDOT approval, the Applicants shall restripe Springfield Center Drive to accommodate a left turn lane from westbound Springfield Center Drive to southbound Loisdale Road within the existing pavement and right-of-way.

- d. Future Grid Connection. At time of site plan approval, or upon demand by Fairfax County and/or VDOT, the Applicants shall dedicate thirty-five (35) feet from the centerline of the existing private access road between the Application Property and property identified as Fairfax County Tax Map Reference 90-4 ((1)) 11C ("Parcel 11C"). The Applicants shall construct frontage improvements along the Application Property with the face of curb set thirty (30) feet from the opposing face of curb located along Parcel 11C.
- e. Contributions toward Off-Site Road Improvements
- (i) Loisdale Road. Prior to the issuance of the first Non-RUP for the Application Property, the Applicants shall contribute to the Board of Supervisors a total of thirty-five thousand seven hundred dollars (\$35,700.00) toward the provision of a second westbound left turn lane from Loisdale Road onto southbound Fairfax County Parkway.
- (ii) Fairfax County Parkway. Prior to the issuance of the first Non-RUP for the Application Property, the Applicants shall contribute a total of sixty-thousand eighty-eight dollars (\$60,088.00) toward the provision of an exclusive northbound right turn lane from the Fairfax County Parkway onto eastbound Loisdale Road.
- f. Reallocation of Monetary Contributions
- The Board of Supervisors may elect to reallocate/combine the Applicant's transportation contributions, provided such contributions are used by FCDOT or VDOT for transportation improvement(s) within two (2) miles of the Application Property.
- g. Traffic Signal. Within twelve (12) months after issuance of the first Non-RUP for the Application Property, the Applicants shall submit for VDOT's review and approval, a traffic signal warrant study for the installation of a new signal at Loisdale Road and Springfield Center Drive if a signal has not already been installed at this location. If a signal has already been installed within twelve (12) months after issuance of the first Non-RUP for the Application Property, the Applicants shall have no further obligation under this proffer.

In the event that VDOT determines that a signal is necessary at this location, then the Applicants shall design, equip, and install said signal. The Applicants shall be permitted to utilize such funds as may have been previously proffered to the County at this location by others. In the event that the signal is not deemed warranted within twelve (12) months after the issuance of the first Non-RUP, then the Applicants shall conduct a second warrant study within six (6) months of eighty-five percent (85%) occupancy of the second office building on the Application Property to determine whether a signal is warranted at that time. In the event that the signal is not warranted within six (6) months of eighty-five

(85%) occupancy of the second office building, the Applicants shall contribute to the Board of Supervisors a total of twenty-five thousand dollars (\$25,000.00) toward the provision of a future signal by others.

- h. Shuttle Bus. A shuttle bus system in the vicinity of the Application Property will operate as outlined in the proffers associated with PCA 1998-LE-064-2/PCA 2008-LE-015. Prior to the issuance of the first Non-RUP for the Application Property, the Applicants shall pay to participate in the existing shuttle bus system on a pro-rata basis.

In the event that public transportation via a connector bus service or some other mode of public transportation is developed which renders provision of shuttle service unnecessary, as determined by Fairfax County Department of Transportation (FCDOT) in consultation with the Lee District Supervisor and the Applicants, then the shuttle bus shall be discontinued. In lieu of the shuttle, the Applicants shall contribute funds on an equitable basis that would otherwise be paid for the shuttle toward operation of a bus circulator system.

- i. Bus Shelter. Prior to issuance of the first Non-RUP for the Application Property, the Applicants shall install a bus shelter along the Application Property's southern frontage as shown on the CDPA/FDPA, subject to review and approval by VDOT, the Fairfax Connector, FCDOT, and/or WMATA.

4. TRANSPORTATION DEMAND MANAGEMENT

- a. TDM Coordinator. Within 180 days after the issuance of the first building permit for the first office building on the Application Property, the Applicants shall appoint and continuously employ a Transportation Demand Management ("TDM") Coordinator (the "TC"). The TC duties may be assigned to an office property manager, who will implement the TDM strategies described herein. Within 120 days of such appointment, the Applicants, through the TC, shall develop and submit to FCDOT for review, a Transportation Demand Management ("TDM") Plan for the Application Property. The TDM Plan shall be implemented upon issuance of the first Non-RUP for the first building. The TC shall notify FCDOT in writing within thirty (30) days of the appointment of the TC. Thereafter, the Applicants shall do the same within thirty (30) days of any change in such appointment.
- b. TDM Plan. The TDM Plan shall consist of, but not limited to, the following elements, unless FCDOT determines that one or more of these elements are unnecessary (other substitute elements may be included upon mutual agreement between the Applicants and FCDOT):
 - (i) The TC shall work cooperatively with FCDOT staff to promote opportunities to enhance participation in TDM programs.

- (ii) Participation in the shuttle bus program as set forth herein.
- (iii) Metro maps, schedules, forms and ride sharing and other relevant transit option information shall be available to tenants and employees through a common web site, common location, or newsletter to be published at least twice a year.
- (iv) The Applicants shall provide at least twenty (20) reserved parking spaces for each office building for carpools/vanpools.
- (v) Secure, weather protected bicycle storage shall be provided in a location convenient to tenants, employees, and visitors.
- (vi) Actively promote the use of carpooling/vanpooling, the Guaranteed Ride Home Program, Metro-Check, telework and other components of the TDM Plan. The TC will work with staff from the Fairfax County RideSources Program to exchange information. The RideSources Program will maintain a database of registered carpools and vanpools along with origin, designation, and work hours of the registered carpools/vanpools.
- (vii) Employers will be encouraged to allow flexible work hours for personnel. The exact policy of the implementation of flexible work hours will vary by employer and implementation shall be at their sole discretion.
- (viii) The Applicants shall provide 300 SmarTrip cards, per building each with a one-time value of \$50.00 to the TDM Coordinator at the time of the issuance of the first tenant Non-RUP for each building. The TC shall distribute the SmarTrip cards to employers to promote the use of mass transit by their employees.
- (ix) The TC shall administer the on-site sale of fare media with the permission of the relevant transit service providers. Fare media to be sold shall include, but is not limited to VRE, Metrorail, Metrobus, and Fairfax Connector.
- (x) The TC shall become a member of TAGS.
- (xi) Beginning twelve (12) months after the issuance of the first tenant Non-RUP for the first building on the Application Property, and annually thereafter, the TC shall prepare and submit to FCDOT a report quantifying the use of public transportation, carpooling, vanpooling and other rideshare programs, created under the TDM Plan. Upon completion of each annual report, a copy of said report shall be transmitted to FCDOT.

- c. Transportation Management Association. The Applicants shall participate in TAGS, the area's Transportation Management Association.
- d. Trip Reduction Goal. The goal of the TDM Plan shall be to produce a thirty percent (30%) peak hour reduction in vehicle trips on the entire Application Property based upon the Institute of Transportation Engineers (ITE), 8th Edition, Trip Generation, rates/equations for the applicable uses.
- e. Annual Report. Beginning twelve (12) months after the issuance of the first office tenant Non-RUP for the first building on the Application Property, and annually thereafter, the TC shall prepare and submit to FCDOT a report quantifying the use of public transportation, carpooling, vanpooling, and other rideshare programs, created under the TDM Plan (the "Annual Report"). Any changes to the TDM Plan shall be highlighted in this report. The Annual Report shall be submitted to FCDOT no later than May 15 of each calendar year.
- f. Monitoring. Beginning with the first year following full occupancy of the second office building on the Application Property and concurrent with that year's annual report, the effectiveness of TDM strategies shall be evaluated using surveys and/or traffic counts, prepared by the TC in cooperation with FCDOT. The TC shall submit to FCDOT the results of these surveys and/or traffic counts in order to determine travel characteristics and whether the required reduction in trips has been achieved. If the peak hour trip reduction goal of thirty percent (30%) has not been achieved as evidenced by the surveys and/or traffic counts, the TC shall meet with FCDOT to review the TDM program for the purpose of identifying additional strategies and programs that may be implemented to assist in achieving the trip reduction goal. The Applicants shall have the benefit of two (2) surveys/counts to evaluate the effectiveness of the implemented TDM strategies. Each of these years shall be considered a "Remedial Cycle." Based on two (2) Remedial Cycles, the Applicants, in consultation with FCDOT, shall determine additional strategies and programs that could be implemented. These additional strategies shall be implemented by the TC for the remainder of the calendar year. If after two (2) Remedial Cycles, the trip reduction goal has not been met, the Applicants shall pay penalties as outlined below. The surveys and/or counts shall be conducted annually and submitted to FCDOT in the Annual Report from the year following occupancy of the second office building until achievement of the trip reduction goal for two (2) successive years following.
- g. Remedy Fund. In the event that the goal of a thirty percent (30%) peak hour reduction in vehicle trips is not met after two (2) Remedial Cycles, the Applicants shall provide a contribution in the amount of two thousand five hundred dollars and 00/100 (\$2,500.00) toward measures which will directly reduce vehicle trips associated with the Application Property. An additional two thousand five hundred dollars and 00/100 (\$2,500.00) shall be paid to Fairfax County for congestion management or other transportation improvements/enhancements in the area surrounding the Application Property. Such incentives may include, but

not be limited to, the provision of additional SmarTrip cards to employees and additional coordination with employees to promote ridesharing and increased transit use. Said contributions shall be made each year that the goal of a thirty percent (30%) peak hour reduction in vehicle trips is not reached, or for a period of five (5) years following two (2) Remedial Cycles, or until the Applicants and FCDOT agree to readjust the reduction percentage, whichever shall first occur. This TDM goal may be readjusted as described herein without necessitating approval of a proffered condition amendment.

- h. Continuing Implementation. The TC shall bear sole responsibility for continuing implementation of the TDM Program and compliance with this proffer. The TC shall continue to administer the TDM Program in accordance with this proffer including the submission of Annual Reports.
- i. Notice to Owners. All owners of the Application Property shall be advised of the TDM Program set forth in this proffer. The current owner shall advise all successor owners of their funding obligations pursuant to this proffer prior to purchase and the requirements of the TDM program shall be included in all initial and subsequent purchase documents.
- j. Enforcement. If the TC fails to timely submit a report to FCDOT as required by this proffer, the TC will have sixty (60) days within which to cure the violation. If after such sixty (60) day period the TC has not submitted the delinquent report, then the Applicants shall be subject to a penalty of \$50 per day not to exceed \$18,250 for one incident. Such penalty shall be payable to Fairfax County.

5. PARKING

- a. The Applicants shall provide parking to meet minimum Zoning Ordinance requirements, including parking as may be required for those areas defined as cellar space.
- b. Prior to the issuance of a building permits for the parking garage, the Applicants shall conduct a noise analysis, subject to DPWES and the Environment and Development Review Branch of DPZ review and approval, to determine whether the garage wall facing the RF&P railroad line will reflect noise into the Windsor Park subdivision in excess of Zoning Ordinance standards. If it does, the Applicants shall include recognized noise attenuating materials and/or design in the design and construction of this wall of the garage.
- c. The Applicant shall provide a minimum of one (1) recharging station that serves two (2) parking spaces for electric cars.

6. RECREATION

- a. A minimum of 1,000 square feet of floor space shall be allocated in one or more of the office buildings to provide indoor recreational exercise facilities. If all the space is allocated to one building, this facility shall be available to occupants of both buildings. Such facilities shall include locker room facilities.
- b. At time of building permit application for the first building on either the Application Property or the property subject to PCA 1998-LE-064-3/PCA 2008-LE-015-2, whichever occur first, the Applicants shall contribute forty thousand dollars (\$40,000.00) to the Fairfax County Park Authority (FCPA) for park and recreational improvements at Lee District Park. At time of building permit application for the second building on either the Application Property or the property subject to PCA 1998-LE-064-3/PCA 2008-LE-015-2, whichever occurs second, the Applicants shall contribute an additional twenty-two thousand dollars (\$22,000.00) to the FCPA for park and recreational improvements at Lee District Park.
- c. Prior to the issuance of the first Non-RUP, the Applicants shall record a public access easement over the common areas in front of the two (2) office buildings on the eastern side of the Application Property.

7. STORMWATER MANAGEMENT/BEST MANAGEMENT PRACTICES

- a. Stormwater management shall be served by an existing off-site pond located on property identified as Fairfax County Tax Map Reference 90-4 ((1)) 11, or as may be approved by DPWES.
- b. Prior to the issuance of the first Non-RUP, the Applicants shall install at least one (1) cistern on the Application Property that will be used for landscaping irrigation.
- c. The Applicants shall implement low impact development techniques on the Application Property to the extent feasible, based on site constraints and infiltration rates. Such techniques, if implemented, may include, but not be limited to, bio-retention, vegetated swales, filter strips, and tree box filters. Should the Applicants implement any of these features in the northeastern portion of the Application Property, the Applicants shall have the ability to adjust the proposed screen walls in this area by ten (10) feet in any direction without necessitating a PCA/FDPA.

8. PEDESTRIAN CONNECTIVITY

The Applicants shall provide pedestrian connections to facilitate pedestrian travel from the Application Property to the Metro Access Road and to the adjacent office buildings that are subject to PCA 1998-LE-064-3/PCA 2008-LE-015-2, as shown on Sheets 17 and 18 of the CDPA/FDPA. Pedestrian connections as may be modified from those shown

on the CDPA/FDPA to facilitate pedestrian travel so long as said modifications do not degrade the pedestrian network shown on the CDPA/FDPA, as determined by the Department of Planning & Zoning.

9. DESIGN

- a. The principal façade building materials for the office buildings shall consist of brick, natural stone, pre-cast concrete, or other masonry finish and glass. In addition, one or two additional accent materials (e.g., stone) may be included. Features, such as canopies and/or awnings, shall be used to identify building entrances. The two (2) buildings shall be designed to include "storefront" type features which may include, but not be limited to, canopies, awnings, and/or other decorative features on the eastern building facades to activate the eastern streetscape. The features shall be installed regardless of whether the eastern facades are used as entrances to the buildings.
- b. The building materials used for the parking garage shall be complementary to those used for the office buildings, of comparable quality, and subdued colors. The Applicants shall install a screen on the northern side of the parking garage adjacent to Springfield Center Drive that will either be an architectural screen or a screen that is seasonally covered in vines to enhance the appearance of the garage. Prior to site plan approval, final architectural drawings shall be submitted to the Lee District Supervisor and Planning Commissioner for review for compliance with these proffers.
- c. Development and landscaping of the urban plaza areas in front of the buildings shall be in substantial conformance with the details shown on Sheets 19, 21 and 22 of the CDPA/FDPA.
- d. The light standards shall feature semi-cutoff shielding for street lights. Lighting standards in the plaza area and in the parking lots shall feature full cut-off shielding.
- e. Low-level lighting, designed to provide for a safe pedestrian pathway to the Metro Access Road, shall be installed along all perimeter sidewalks adjacent to the Application Property and phased with individual building construction.
- f. The design of the buildings shall not preclude future first floor retail.
- g. Prior to site plan approval for the first office building on the Application Property, the Applicants shall submit a coordinated plan for benches, bike racks, and other furniture on the Application Property to the Lee District Supervisor and Planning Commissioner for their review and approval.

- h. Public art may be provided within selected common areas of the Application Property as shown on the CDPA/FDPA. The selection of public art shall be coordinated with the Lee District Supervisor and Planning Commissioner.

10. SIGNAGE

The Applicants shall provide coordinated and complementary signs to serve the Application Property in accordance with the Zoning Ordinance. Prior to issuance of the first Non-RUP, the Applicants shall submit proposed sign drawings to the Lee District Supervisor and Planning Commissioner for compliance with these proffers. Alternatively, the Applicants may seek approval of a Comprehensive Sign Plan on the Application Property.

11. GREEN BUILDING PRACTICES

- a. The Applicants shall include a U.S. Green Building Council (USGBC) Leadership in Energy and Environmental Design ("LEED") accredited professional as a member of the design team. The LEED accredited professional shall work with the team to incorporate the current version, at the time of Applicants' registration, of LEED design elements into the project. At time of site plan submission, the Applicants shall provide documentation to the Environmental and Development Review Branch of DPZ demonstrating compliance with the commitment to engage such a professional.
- b. The Applicants will include, as part of the site plan submission and building plan submission for any building to be constructed, a list of specific credits within the most current version, at the time of Applicants' registration, of the USGBC's Core and Shell LEED rating system or other LEED rating system determined by the USGBC that the Applicants anticipate attaining. The LEED-accredited professional will provide certification statements at both the time of site plan review and the time of building plan review confirming that the items on the list will meet at least the minimum number of credits necessary to attain LEED Silver Core and Shell certification of the project. In addition, prior to site plan approval, the Applicants will designate the Chief of the Environment and Development Review Branch of the Department of Planning and Zoning (DPZ) as a team member in the USGBC's LEED online system. This team member will have privileges to review the project status and monitor the progress of all documents submitted by the project team, but will not be assigned responsibility for any LEED credits and will not be provided with the authority to modify any documentation or paperwork.
- c. Prior to the building plan approval, the Applicants will execute a separate agreement and post, for each building, a "Green Building Escrow," in the form of cash, bond, or a Letter of Credit from a financial institution acceptable to DPWES as defined in the Public Facilities Manual, in the amount of \$2.00 per gross square foot for that building. This Green Building Escrow shall be in addition to and

separate from other bond or escrow requirements and shall be released upon demonstration of attainment of Silver certification by the USGBC under the most current version at the time of Applicants' registration of LEED Core and Shell rating system or other LEED rating system determined by the USGBC, to be applicable to each building. The provision to the Environment and Development Review Branch of DPZ of documentation from the USGBC that each building has attained LEED Silver Core and Shell certification will be sufficient to satisfy this commitment. If the Applicants fail to provide documentation to the Environmental and Development Review Branch of DPZ demonstrating attainment of LEED Silver Core and Shell certification within two (2) years of issuance of the first Non-RUP for each building, the Green Building Escrow will be released to Fairfax County and will be posted to a fund within the County budget supporting implementation of County environmental initiatives.

- d. If the Applicants provide documentation to the Environment and Development Review Branch of DPZ, within two (2) years of issuance of the first Non-RUP for each building, that demonstrates that LEED Silver certification for the particular building in question has not been obtained but the building has been determined by USGBC to fall within three (3) points of attainment of LEED Silver certification, fifty percent (50%) of the Green Building Escrow will be released to the Applicants. The other fifty percent (50%) of the Green Building Escrow will be posted to a fund within the County budget to support implementation of County environmental initiatives.
- e. If the Applicants provide evidence that LEED Silver Core and Shell certification has been delayed through no fault of the Applicants, this proffered time frame shall be extended by the Zoning Administrator, and no release of escrowed funds shall be made to the Applicants or to the County during this extended time frame.
- f. All references to the U.S. Green Building Council shall apply to similar certifying agencies that are created subsequent to approval of this application, provided that the alternative certifying agency is acceptable to Fairfax County and the Applicants.

12. GEOTECHNICAL

Prior to site plan approval, and in accordance with the provisions of the Public Facilities Manual, the Applicants shall submit a geotechnical study of the Application Property to the Geotechnical Review Board through DPWES and shall incorporate appropriate engineering practices as recommended by the Geotechnical Review Board and DPWES to alleviate potential structural problems, to the satisfaction of DPWES. The recommendations of the Geotechnical Review Board shall be implemented during construction.

13. ADVANCED DENSITY CREDIT

Advanced density credit is reserved consistent with the provisions of Paragraph 4 of Section 2-308 of the Zoning Ordinance for all eligible dedications described herein or as may be required by Fairfax County or VDOT.

14. TIMING OF IMPROVEMENTS

Upon demonstration by the Applicants that despite diligent efforts, or due to factors beyond the Applicants' control, the required improvements have been or will be delayed beyond the time set forth in these proffers, the Zoning Administrator may agree to a later date for completion of such improvements.

15. SUCCESSORS AND ASSIGNS

These proffers shall bind and inure to the benefit of the Applicants and their successors or assigns.

16. COUNTERPARTS


These proffers may be executed in one or more counterparts, each of which when so executed and delivered shall be deemed an original, and all of which taken together shall constitute one and the same instrument.

APPLICANT/TITLE OWNER OF TAX MAP
90-2 ((1)) 58D

SPRINGFIELD 6601 LLC, a Delaware limited liability company

By: Boston Properties Limited Partnership, a Delaware Limited
partnership, its Managing Member

By: Boston Properties Inc., a Delaware Corporation, its General
Partner

A handwritten signature in black ink, appearing to read 'Kenneth F. Simmons', is written over a horizontal line.

By: Kenneth F. Simmons
Its: Senior Vice President, Development


[SIGNATURES CONTINUE ON THE NEXT PAGE]

APPLICANT/TITLE OWNER OF TAX MAP
90-4 ((1)) 11B PT.

SPRINGFIELD METRO CENTER II, LLC, a Delaware limited
liability company

By: Boston Properties Limited Partnership, a Delaware Limited
partnership, its Managing Member

By: Boston Properties Inc., a Delaware Corporation, its General
Partner

A handwritten signature in black ink, appearing to read "Kenneth F. Simmons", is written over a horizontal line.

By: Kenneth F. Simmons
Its: Senior Vice President, Development


[SIGNATURES CONTINUE ON THE NEXT PAGE]

TITLE OWNER OF TAX MAP 90-2 ((1)) 56C PT.

SPRINGFIELD PARCEL C LLC, a Delaware limited liability company

By: Boston Properties Limited Partnership, a Delaware Limited partnership, its Managing Member

By: Boston Properties Inc., a Delaware Corporation, its General Partner

A handwritten signature in black ink, appearing to read "Kenneth F. Simmons", is written over a horizontal line.

By: Kenneth F. Simmons

Its: Senior Vice President, Development

[SIGNATURES END]

FINAL DEVELOPMENT PLAN CONDITIONS


PCA/FDPA 2011-LE-022

July 1, 2015

If it is the intent of the Planning Commission to approve FDPA 2011-LE-022 for an office development located at Tax Maps 90-2 ((1)) 15C pt. and 58D, and 90-4 ((1)) 11B pt., staff recommends that the Planning Commission condition the approval by requiring conformance with the following development conditions, which supersede all previous conditions:

1. Development of the property shall be in substantial conformance with the CDPA/FDPA entitled "Metro Center II Phase II", consisting of twenty-nine sheets prepared by Urban Engineering dated February 2011 as revised through June 17, 2015.

The above proposed conditions are staff recommendations and do not reflect the position of the Planning Commission unless and until adopted by that Commission.



NO.	DATE	REVISIONS
1	02/20/2011	ISSUED FOR PERMITS
2	02/20/2011	REVISED PER COMMENTS
3	02/20/2011	REVISED PER COMMENTS
4	02/20/2011	REVISED PER COMMENTS
5	02/20/2011	REVISED PER COMMENTS
6	02/20/2011	REVISED PER COMMENTS
7	02/20/2011	REVISED PER COMMENTS
8	02/20/2011	REVISED PER COMMENTS
9	02/20/2011	REVISED PER COMMENTS
10	02/20/2011	REVISED PER COMMENTS

urban
 Urban Planning, Inc.
 10000 W. 10th Street, Suite 100
 Denver, CO 80202
 Phone: 303.733.8888
 Fax: 303.733.8889
 www.urbanplanning.com




DATE: FEB. 2011
 SCALE: 1"=40'
 CL: 2'

OPEN SPACE EXHIBIT
 METRO CENTER II
 PHASE II CDP/FP/PA
 LEE DISTRICT
 FAIRFAX COUNTY, VA


OPEN SPACE AREA: 37.89% (2.38 AC)

SHEET
 07
 OF
 24
 REZ-1258





PLAN VIEW
SCALE: 1"=50'

EX DRIVE
PRIVATE ROADWAY
DESIGN SPEED=20 MPH (SPEED LIMIT NOT POSTED)
PROP./EX. WIDTH VARIES
CATEGORY: LOCAL COLLECTOR



PLAN VIEW
SCALE: 1"=50'

EX SPRINGFIELD CENTER DRIVE
PRIVATE ROADWAY
POSTED SPEED=25 MPH
PROP./EX. WIDTH VARIES
CATEGORY: LOCAL COLLECTOR



NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		


Urban
 Planning • Engineering • Architecture • Land Surveying




SIGHT DISTANCE PROFILE
METRO CENTER II
PHASE II CDPA/FDPA
 LEE DISTRICT
 FAIRFAX COUNTY, VA
 SCALE: (H) 1"=50' (V) 1"=5' CL: 2
 DATE: FEB. 2011

SHEET
 08
 OF
 24
 REZ-12588

EXISTING IMPERVIOUS AREA = 4.53 ACRES (OR 197,326.80 S.F.)



PROPOSED IMPERVIOUS AREA = 4.40 ACRES (OR 191,853.20 S.F.)



		DATE: FEB. 2011 SCALE: (B) 1"=50' (V) 1"=5' CL:2 SHEET 10 OF 24 REZ-12588
		IMPERVIOUS AREA EXHIBIT METRO CENTER II PHASE II CDDP/FDPA FARMEX COUNTY, VA
PLANNING 01 02 03 04 05 06 07 08 09 10 11 12	DESIGN 01 02 03 04 05 06 07 08 09 10 11 12	REVISIONS NO. DATE DESCRIPTION

BMP FACILITY DESIGN CALCULATIONS

Plan Name: Metro Center II P22
 Date: 02/2011
 Plan Number: _____ Engineer: CSM

I. WATER QUALITY NARRATIVE

II. WATERSHED INFORMATION

Part 1: List all of the Subarea and "C" factors used in the BMP Computations

Subarea Designation	"C" Factor	Area (a)	Product (b)
(1) TOTAL ONSITE CONTROLLED BY POND, STORM FILTER	0.00	1.48	1.48
(2) TOTAL ONSITE UNCONTROLLED NON-OPEN SPACE	0.80	2.80	2.24
(3) TOTAL ONSITE UNCONTROLLED OPEN SPACE	0.80	2.78	2.22
Total			6.38

III. PHOSPHORUS REMOVAL - "OCOCOQUAN METHOOD"

Part 2: Compute the Weighted Average "C" Factor for the Site

(A) Area of the Site (a) = 6.38 acres

Subarea Designation	"C" Factor	Area (a)	Product (b)
(1) TOTAL ONSITE CONTROLLED BY POND, STORM FILTER	0.00	1.48	1.31
(2) TOTAL ONSITE UNCONTROLLED NON-OPEN SPACE	0.80	2.80	2.24
(3) TOTAL ONSITE UNCONTROLLED OPEN SPACE	0.80	2.18	1.74
Total			5.29

(C) Weighted average "C" factor (b)/(a) = (C) = 0.83

Part 3: Compute the Total Phosphorus Removal for the Site

Subarea Designation	Removal Efficiency (%)	Area (a)	"C" Factor	Product (b)
(1) TOTAL ONSITE CONTROLLED BY POND, STORM FILTER	80	1.48	0.00	13.16
(2) TOTAL ONSITE UNCONTROLLED NON-OPEN SPACE	0	2.80	0.80	0.00
(3) TOTAL ONSITE UNCONTROLLED OPEN SPACE	0	2.18	0.80	0.00
Total				13.16

Part 4: Determine Compliance with Phosphorus Removal Requirement

(A) Select Requirement (a) = 0.32

Water Supply Overlay District (Occoquan Watershed) = 82% (Fairfax County and Prince William County)

Chesapeake Bay Preservation Area (Near Development) = 42% (Fairfax County)


Chesapeake Bay Preservation Area (Redevelopment) = 82% (Prince William County)

(1) $0.83 \times (7 \text{ ppb} \times 100) = 0.58 \%$

(2) If Line 3(a) > Line 4(a), the Phosphorus removal requirement is satisfied.

Line 3(a) = 13.16 > 0.32

PHOSPHORUS REMOVAL REQUIREMENT IS SATISFIED



BMP NARRATIVE

THE METRO CENTER II - PHASE 2 PROJECT CONSISTS OF TWO OFFICE BUILDINGS A PARKING GARAGE, ACCESS WAYS, UTILITIES AND ASSOCIATED INFRASTRUCTURE. FOR BEST MANAGEMENT PRACTICES (BMP) THE AREA UNDER CONSIDERATION CONSISTS OF APPROXIMATELY 6.38 ACRES. THE SITE HAS A WEIGHTED AVERAGE RUNOFF COEFFICIENT OF 0.80. THE PROJECT WILL UTILIZE A SINGLE STORM FILTER SYSTEM TO COMPLY WITH THE FAIRFAX COUNTY BMP REQUIREMENTS OF 0.32% POLLUTANT REMOVAL EFFICIENCY UNDER THE REDEVELOPMENT REQUIREMENTS OF FAIRFAX COUNTY. THE APPLICANT RESERVES THE RIGHT TO MODIFY THE EFFICIENCY REMOVAL SHOWN ON THESE COMPUTATIONS DURING THE FINAL SITE PLAN PHASE AS LONG AS THE EFFICIENCY IS MORE THAN 0.32%.

THE BMP IS LOCATED AT THE NORTHEASTERN LIMITS OF THE SITE. THE TOTAL DRAINAGE AREA TO THIS FACILITY IS 1.48 ACRES. THE DRAINAGE AREA FOR THE FACILITY HAS AN ASSOCIATED WEIGHTED AVERAGE RUNOFF COEFFICIENT OF 0.80.

THE REMAINING AREA OF APPROXIMATELY 4.82 ACRES LEAVES THE SITE AS UNCONTROLLED RUNOFF.

SWM NARRATIVE

STORM WATER MANAGEMENT FOR THE SITE IS CONTROLLED BY AN EXISTING OFFSITE POND THAT WAS PROPOSED UNDER 89-1508 AND MODIFIED WITH FAIRFAX COUNTY PLAN 87562-89-01. THE EXISTING POND WILL REMAIN IN SERVICE WITH NO NECESSARY IMPROVEMENTS. THE EXISTING POND IS SHOWN ON THE CULFALL MAP PROVIDED ON SHEET 13 AND ALSO ON SHEET 14. THE SUBJECT SITE WAS INCLUDED IN THE ORIGINAL DESIGN OF THE EXISTING POND AS SHOWN IN THE DRAINAGE DIVIDES PROVIDED ON SHEET 12. COMPUTATIONS FOR THE EXISTING POND HAVE BEEN PROVIDED ON SHEET 14. THE PROPOSED IMPROVEMENTS OF THE SUBJECT SITE LOWER THE IMPERVIOUSNESS OF THE SITE AS DEPICTED ON SHEET 10. THEREFORE, THE PROPOSED IMPROVEMENTS OF THIS SITE DO NOT HAVE A NEGATIVE IMPACT ON THE EXISTING POND.

REVISIONS	NO.	DATE	DESCRIPTION
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			
46			
47			
48			
49			
50			
51			
52			
53			
54			
55			
56			
57			
58			
59			
60			
61			
62			
63			
64			
65			
66			
67			
68			
69			
70			
71			
72			
73			
74			
75			
76			
77			
78			
79			
80			
81			
82			
83			
84			
85			
86			
87			
88			
89			
90			
91			
92			
93			
94			
95			
96			
97			
98			
99			
100			



Urban
 Planning Engineers & Architects, Ltd.

DATE: FEB. 2011

SCALE: 1"=50'

SHEET 11 OF 24

REZ-12588



POST DEVELOPMENT CONDITIONS:

CROSS SECTION 4-4
 DA = 148.18 AC.
 C' FACTOR = 0.50
 S = 2.76 IN/HR
 I10 = 3.71 IN/HR
 TC = 30 MIN
 Q2 = 284 CFS
 Q10 = 274 CFS
 CHANNEL SLOPE = 0.0184
 S' = 0.050 STONY STREAM CHANNEL
 V2 = 5.54 FPS
 D10 = 4.24 FT.

POST DEVELOPMENT CONDITIONS:

CROSS SECTION 6-6
 DA = 148.18 AC.
 C' FACTOR = 0.50
 S = 2.76 IN/HR
 I10 = 3.71 IN/HR
 TC = 30 MIN
 Q2 = 284 CFS
 Q10 = 274 CFS
 CHANNEL SLOPE = 0.0184
 S' = 0.050 STONY STREAM CHANNEL
 V2 = 2.40 FPS
 D10 = 4.18 FT.

POST DEVELOPMENT CONDITIONS:

CROSS SECTION 8-8
 DA = 148.18 AC.
 C' FACTOR = 0.50
 S = 2.76 IN/HR
 I10 = 3.71 IN/HR
 TC = 30 MIN
 Q2 = 284 CFS
 Q10 = 274 CFS
 CHANNEL SLOPE = 0.0184
 S' = 0.050 STONY STREAM CHANNEL
 V2 = 2.40 FPS
 D10 = 4.22 FT.

*PERMISSIBLE VELOCITY IS 5.0 FPS PER TABLE 5-22 OF MESH. THIRD COLUMN FOR COARSE GRAVEL. SEE PICTURE THIS SHEET.

PLANNING DATE	DESCRIPTION	REVISIONS
01-14-11	01-14-11	01-14-11
02-14-11	02-14-11	02-14-11
03-14-11	03-14-11	03-14-11
04-14-11	04-14-11	04-14-11
05-14-11	05-14-11	05-14-11
06-14-11	06-14-11	06-14-11
07-14-11	07-14-11	07-14-11
08-14-11	08-14-11	08-14-11
09-14-11	09-14-11	09-14-11
10-14-11	10-14-11	10-14-11
11-14-11	11-14-11	11-14-11
12-14-11	12-14-11	12-14-11



OUTFALL CROSS SECTIONS
METRO CENTER II
PHASE II CDP/ADPA
 LEE DISTRICT
 FAIRFAX COUNTY, VA
 SCALE: AS SHOWN
 CL: 5
 DATE: FEB. 2011

SHEET
 15
 OF
 24
 REZ-12588

NO.	INLET		AREA		REMARKS
	AREA (SQ. FT.)	C	AREA (SQ. FT.)	C	
1	15.75	0.85	1001	0.85	1/2 IN. OF INLET PIPE OF DRAINAGE AND TRAP
2	0.50	0.70	1.51	0.65	
3	0.75	0.70	0.52	0.60	
TOTAL					0.82
TOTAL 1/2 IN. OF INLET PIPE OF DRAINAGE AND TRAP					0.82
4	45.11	0.71	10.77	0.60	

$C_u = 0.85$
 $C_d = 0.77$
 $C_e = 0.82$
 $C_o = 0.84$

h (BASE LAYER) (NO. OF LAYERS) = 10
 $A_1 = 4.00$ $A_2 = 8.75$ $A_3 = 17.17$
 $A_4 = 3.00$ $A_5 = 25.17$ $A_6 = 19.64$
 $A_7 = 10.00$ $A_8 = 37.74$ $A_9 = 34.47$

EMERGENCY SPILLWAY

SPILLWAY ELEVATION = 74.55
 $Q_{max} = 348.45$
 BETA THROUGH OUTLET PIPE = 170.4
 BALANCE THROUGH SPILLWAY = 170.45

CHANNEL ADJUSTMENT OF THE SPILLWAY

$Q = C \cdot L \cdot H^{3/2}$
 $L = 30$
 $H = 3.0$
 $Q = 170$
 $C = 1.0$

DESIGN DISCHARGE IN THE POND




(A) 2 YEAR STORM = 149.52
 (B) 10 YEAR STORM = 194.93
 (C) 100 YEAR STORM = 195.70

DESIGN FLOOD IN SPILLWAY


DESIGN FLOOD (CFS)	DESIGN FLOOD (MGD)	DESIGN FLOOD (MGD)	DESIGN FLOOD (MGD)
149.52	0.51	0.51	0.51
194.93	0.68	0.68	0.68
195.70	0.68	0.68	0.68

NO.	AREA (SQ. FT.)	C	AREA (SQ. FT.)	C	REMARKS
1	15.75	0.85	1001	0.85	1/2 IN. OF INLET PIPE OF DRAINAGE AND TRAP
2	0.50	0.70	1.51	0.65	
3	0.75	0.70	0.52	0.60	
TOTAL					0.82
TOTAL 1/2 IN. OF INLET PIPE OF DRAINAGE AND TRAP					0.82
4	45.11	0.71	10.77	0.60	

NO.	AREA (SQ. FT.)	C	AREA (SQ. FT.)	C	REMARKS
1	15.75	0.85	1001	0.85	1/2 IN. OF INLET PIPE OF DRAINAGE AND TRAP
2	0.50	0.70	1.51	0.65	
3	0.75	0.70	0.52	0.60	
TOTAL					0.82
TOTAL 1/2 IN. OF INLET PIPE OF DRAINAGE AND TRAP					0.82
4	45.11	0.71	10.77	0.60	




TIME (MIN)	DISCHARGE (CFS)	DEPTH (FEET)
0	0	0
5	150	8
10	100	5
15	50	3
20	0	0



WEIR WALL ADDITION
 TO INCREASE DISCHARGE FROM THE EXISTING POND

DISCHARGE FROM THE EXISTING POND
 $Q = C \cdot L \cdot H^{3/2}$
 $Q = 0.82 \cdot 30 \cdot 3.0^{3/2} = 170.4$



WEIR WALL ADDITION DETAIL
 TO INCREASE DISCHARGE FROM THE EXISTING POND

SHEET NO. 150 OF 24
 REVISIONS
 DATE FEB. 2011
 SCALE NOT TO SCALE
 CL: N/A
 DATE FEB. 2011
 URBAN
 METRO CENTER II
 PHASE II CDDA/FDPA
 FARMEX COUNTY, VA
 SHEET 150 OF 24
 REZ-12588



RECEIVED
Department of Planning & Zoning

MAR 06 2015

Zoning Evaluation Division

PLANNERS
ENGINEERS
LANDSCAPE
ARCHITECTS
LAND
SURVEYORS

March 3, 2015

**Description of
SPRINGFIELD 6601 LLC
Tax Map #090-2-01-0058D
Fairfax County, Virginia
&
SPRINGFIELD METRO CENTER II LLC
Tax Map #090-4-01-0011B
Fairfax County, Virginia
&
A PORTION OF SPRINGFIELD PARCEL C LLC
Tax Map #090-2-01-0056C
Fairfax County, Virginia**

Beginning at a point at the northeast corner of the lands to Springfield 6601 LLC, as recorded in Deed Book 19065 at Page 158 among the land records of Fairfax County, Virginia said point being on a southerly line of the lands to Springfield Parcel C LLC as recorded in Deed Book 19256 at Page 2081; thence departing said point and running with the lines of said Springfield 6601 LLC the following courses and distances:

South 47° 44' 23" East, 19.62 feet to a point; thence

86.89 feet along the arc of a curve deflecting to the left having a radius of 45.00 feet and a chord bearing and distance of South 13° 03' 29" East, 74.01 feet to a point; thence

28.19 feet along the arc of a curve deflecting to the right having a radius of 30.00 feet and a chord bearing and distance of South 41° 27' 35" East, 27.16 feet to a point; thence

123.06 feet along the arc of a curve deflecting to the right having a radius of 474.00 feet and a chord bearing and distance of South 07° 06' 18" East, 122.72 feet to a point; thence

139.78 feet along the arc of a curve deflecting to the right having a radius of 480.00 feet and a chord bearing and distance of South 08° 40' 30" West, 139.28 feet to a point; thence

South 17° 01' 03" West, 58.45 feet to a point being an eastern corner of the lands to Springfield Metro Center II LLC as recorded in Deed Book 19040 at Page 67; thence departing said point and running with the lines of said Springfield Metro Center II LLC the following courses and distances:

South 17° 01' 03" West, 95.55 feet to a point; thence

84.79 feet along the arc of a curve deflecting to the right having a radius of 197.00 feet and a chord bearing and distance of South 29° 20' 53" West, 84.14 feet to a point; thence

South 41° 40' 43" West, 107.52 feet to a point; thence

157.76 feet along the arc of a curve deflecting to the right having a radius of 197.00 feet and a chord bearing and distance of South 64° 37' 10" West, 153.57 feet to a point; thence

117.98 feet along the arc of a curve deflecting to the left having a radius of 284.00 feet and a chord bearing and distance of South 75° 39' 35" West, 117.13 feet to a point being the eastern corner of INOVA Health Care Services, Deed Book 10700 Page 1192 and being at the



southwest corner of the lands to Springfield Center Industrial Park as recorded in Deed Book 9587 at Page 990; thence departing said point and running with the eastern line of said INOVA Health Care Services

North 47° 45' 00" West, 240.18 feet to a point; thence departing said point and running through the lands of said Springfield Metro Center II, LLC the following courses and distances:

North 42° 15' 00" East, 7.01 feet to a point; thence

North 47° 45' 00" West, 60.62 feet to a point; thence

North 42° 15' 11" East, 89.99 feet to the point; thence departing said point and running through the lands of said Springfield Parcel C LLC the following courses and distances:

North 42° 15' 11" East, 645.72 feet to the point; thence

South 47° 44' 49" East, 60.58 feet to a point; thence

North 42° 15' 00" East, 66.98 feet to the point of beginning, containing 273,471 square feet or 6.2780 acres, more or less.



PCA 2011-LE-022
CDPA 2011-LE-022



COUNTY OF FAIRFAX
Department of Planning and Zoning
Zoning Evaluation Division
12055 Government Center Parkway, Suite 801
Fairfax, VA 22035 703-324-1290, TTY 711
www.fairfaxcounty.gov/dpz/zoning/applications

APPLICATION No: FDPA 2011-LE-022

(Assigned by staff)

Concurrent with
PCA 1998-LE-064-03
PCA 2008-LE-015-02

RECEIVED
Department of Planning & Zoning

APPLICATION FOR A REZONING
(PLEASE TYPE or PRINT IN BLACK INK)

JAN 23 2015

Zoning Evaluation Division

PETITION

TO: THE BOARD OF SUPERVISORS OF FAIRFAX COUNTY, VIRGINIA

I (We), Springfield Metro Center II, LLC and Springfield 6601 LLC, the applicant (s) petition you to adopt an ordinance amending the Zoning Map of Fairfax County, Virginia, by reclassifying from the PDC District to the PDC District the property described below and outlined in red on the Zoning Section Sheet(s) accompanying and made part of this application.

APPLICATION TYPE(S): PCA CDP CSP FDP CDPA CSPA FDPA

LEGAL DESCRIPTION:

See Attached Legal Description				
Lot(s)	Block(s)	Subdivision	Deed Book	Page No.

TAX MAP DESCRIPTION:

90-4	((1))		11B pt.	Approx. 6.28 acres
90-2	((1))		56C pt.	
90-2	((1))		58D	
Map No.	Double Circle No.	Single Circle No.	Parcel(s)/Lot(s) No.	Total Acreage

POSTAL ADDRESS OF PROPERTY:

N/A

ADVERTISING DESCRIPTION: (Example - North side of Lee Highway approx. 1000 feet west of its intersection with Newgate Blvd.)

Located west side of Springfield Center Drive to the southwest of Springfield Metro Center.

PRESENT USE: Vacant	PROPOSED USE: Office
MAGISTERIAL DISTRICT: Lee	OVERLAY DISTRICT (S): N/A

The name(s) and address(s) of owner(s) of record shall provided on the affidavit form attached and made part of this application. The undersigned has the power to authorize and does hereby authorize Fairfax County staff representative on official business to enter on the subject property as necessary to process the application.

Sara V. Mariska, attorney/agent
Type or Print Name
Walsh, Colucci, Lubeley & Walsh, P.C.
2200 Clarendon Blvd, #1300, Arlington, VA 22201
Address

Sara V. Mariska
Signature of Applicant or Agent
(Work) (703) 528-4700 (Mobile)
Telephone Number

msc
3/16/15

Please provide name and telephonic number of contact if different from above:

PCA/CDPA/FDPA 2015-0021/0022/0023

DO NOT WRITE BELOW THIS SPACE

Date application accepted: March 10, 2015

Debra Hester

Fee Paid \$ 23,055.00